



230 West Monroe Street
Suite 2370
Chicago, IL 60606

312.578.0870 PHONE
312.578.0877 FAX

www.TRCSolutions.com

October 3, 2011

Mr. Jim Baumann
Special Assistant to Bureau Director
Bureau of Watershed Management
Wisconsin Department of Natural Resources
101 S. Webster Street, Box 7921
Madison, WI 53707-7921

Ms. Jean Greensley
U.S. Environmental Protection Agency
Remediation and Reuse Branch
Land and Chemicals Division
77 W. Jackson Boulevard
Chicago, IL 60604-3511

**Re: Proposed Overbank Removal Boundaries and Sample Results
Operable Unit 3, Reach L
Hayton Area Remediation Project**

Dear Mr. Baumann and Ms. Greensley:

On August 12, 2011, WDNR submitted its review of the proposed removal boundaries in Reaches K, L and M, and identified locations where additional sampling is needed to adequately define removal boundaries. On September 14, 2011, WDNR submitted draft Conditions of Approval for Reaches K, L and M, which specified additional locations for characterization and post-remedial verification (PRV) sampling. To address each of the locations identified by WDNR, TRC has collected additional characterization samples in Reaches K, L and M, and has modified removal boundaries, as appropriate.

Enclosed for your approval are a figure and tables showing modified overbank removal boundaries in Reach L of the Hayton Area Remediation Project, Operable Unit 3 (OU3). Electronic copies of this submittal are also being provided via email to James.Baumann@Wisconsin.gov and Greensley.Jean@epamail.epa.gov.

Table 1 lists the additional characterization samples were collected and analyzed in Reach L to address each of the locations identified by WDNR. Figure 1 shows the sample results and modified removal boundaries. The additional characterization samples and modified removal boundaries are shown in magenta.

Figure 1 also shows the locations of proposed post-remedial verification (PRV) samples in Reach L. TRC has added PRV sample locations based on those requested in the September 14, 2011 draft Conditions of Approval. Several PRV sample locations were added based the modified removal boundaries. Table 2 is an updated list of PRV sample locations in Reach L. Table 3 provides the rationale for each of the modified removal

boundaries. Table 4 is an updated list of stream bank PRV samples. Table 4 also indicates the segment of stream bank (by Station ID) that is represented by each stream bank PRV sample.

As requested, TRC has also enclosed copies of the following reference documents to help streamline the review and approval process:

- Reach L sample elevation information from the *HARP OU2/L & OU3 In-Channel and Overbank Sampling Technical Memorandum* (February 2006);
- Reach L soil boring log information from the *HARP OU2/L & OU3 In-Channel and Overbank Sampling Technical Memorandum* (February 2006);
- Figures of the stream channel location in Reach L, from the Earth Tech document *HARP OU3 Overbank Sampling and Analysis Plan* (December 2003)
- Reach L soil boring logs from the Earth Tech document *HARP OU3 Overbank Sampling and Analysis Plan* (December 2003)

We would appreciate your comments and approval for Reach L by October 14, 2011.

Please contact me at (312) 578-0870, extension 8486, with any questions.

Sincerely,

A handwritten signature in black ink, appearing to read 'CH' followed by a flourish.

Christopher D. Harvey, PE
Program Manager

Enclosures: *Figure 1 - Sample Results, Excavation Boundaries and Proposed PRV Samples, Reach L*
Table 1- Additional Characterization Sampling Results 2011, Reach L
Table 2- Rationale for Modified Removal Boundaries, Reach L
Table 3 - Proposed Post-Removal Verification Samples, Reach L
Table 4 - Proposed Stream Bank PRV Samples, Reach L
Reach L Reference Documents

Table 1. Additional Characterization Sampling Results 2011
Reach L
Hayton Area Remediation Project

10/03/2011

| Sample Name | Total PCBs (mg/kg) | Location | Comments |
|---------------|-----------------------|-------------|--------------------------------|
| RL 014L 0-6 | 35.7 | 1LL / L108 | |
| RL 014L 6-12 | 43.5 | 1LL / L108 | |
| RL 014L 12-18 | 0.337 | 1LL / L108 | |
| RL 014L 18-24 | 3.74 | 1LL / L108 | |
| RL 015L 0-6 | 24.2 | 1LL / L109 | |
| RL 015L 6-12 | 28.4 | 1LL / L109 | |
| RL 015L 12-18 | 0.204 | 1LL / L109 | |
| RL 016L 0-6 | 7.32 | 3LLa / L110 | |
| RL 016L 6-12 | 24.1 | 3LLa / L110 | |
| RL 016L 12-18 | 4.66 | 3LLa / L110 | |
| RL 017L 0-6 | 0.212 | 6LL | |
| RL 017L 6-12 | 0.0351 (J) | 6LL | |
| RL 018L 6-12 | 0.1 (J) | 4LL | |
| RL 019L 6-12 | <0.0336 | 5LL | |
| RL 020L 0-6 | 2.4 | 14LL | |
| RL 020L 6-12 | 0.234 | 14LL | |
| DUP 113 | 0.367 | 14LL | |
| RL 021L 0-6 | 25.9 | 1LL / L108a | |
| RL 021L 6-12 | 2.83 | 1LL / L108a | |
| RL 021L 12-18 | 1.1 | 1LL / L108a | |
| RL 022L 0-6 | 19.4 | 1LL / L108a | |
| RL 022L 6-12 | 4.58 | 1LL / L108a | |
| RL 022L 12-18 | 2.97 | 1LL / L108a | |
| RL 023L 0-6 | 22.7 | 1LL / L108a | |
| RL 023L 6-12 | 2.96 | 1LL / L108a | |
| RL 023L 12-18 | 0.234 | 1LL / L108a | |
| DUP 117 | 0.0518 (J) | 1LL / L108a | |
| RL 024L 0-6 | 3.18 | 1LL / L109 | |
| RL 024L 6-12 | 0.716 | 1LL / L109 | |
| RL 025L 0-6 | 14.3 | 1LL / L109 | |
| RL 025L 6-12 | 4.33 | 1LL / L109 | |
| RL 026L 0-6 | 0.541 | 1LL / L109 | |
| RL 026L 6-12 | 0.221 | 1LL / L109 | |
| RL 027L 0-6 | 17 | 3LLa / L102 | |
| RL 027L 6-12 | 3.14 | 3LLa / L102 | |
| RL 028L 0-6 | 11.5 | 3LLa / L110 | |
| RL 028L 6-12 | 15.3 | 3LLa / L110 | |
| RL 029L 0-6 | 9.97 | 3LLa / L110 | |
| DUP 118 | 13.3 | 3LLa / L110 | |
| RL 029L 6-12 | 22.2 | 3LLa / L110 | |
| RL 030L 0-6 | 7.21 | 1LL / L108a | at high point near top of bank |
| RL 031L 0-6 | 14.5 | 1LL / L108a | |
| RL 032L 0-6 | 19.7 | 1LL / L108a | at high point near top of bank |
| RL 033L 0-6 | 3.31 | 1LL / L109 | at high point near top of bank |
| RL 033L 6-12 | 0.684 | 1LL / L109 | |
| RL 034L 0-6 | 6.18 | 3LLa / L110 | at high point near top of bank |
| RL 034L 6-12 | 7.0 | 3LLa / L110 | |
| RL 035L 0-6 | 6.84 | 3LLa / L102 | |

Table 1. Additional Characterization Sampling Results 2011

Reach L

Hayton Area Remediation Project

10/03/2011

| Sample Name | Total PCBs (mg/kg) | Location | Comments |
|---------------|-----------------------|-------------|--------------------------------|
| RL 036L 0-6 | 5.36 | 3LLa / L102 | at high point near top of bank |
| RL 036L 6-12 | 4.67 | 3LLa / L102 | |
| RL 037L 0-6 | 4.04 | L108a | at high point near top of bank |
| DUP 122 | 5.59 | L108a | |
| RL 038L 0-6 | 0.255 | L108a | |
| RL 039L 0-6 | 6.69 | 3LLa / L110 | at high point near top of bank |
| RL 039L 6-12 | 7.81 | 3LLa / L110 | at high point near top of bank |
| RL 040L 0-6 | 4.93 | 3LLc / L102 | |
| RL 041L 0-6 | 9.05 | 1LL / L108a | at high point near top of bank |
| RL 041L 6-12 | 3.46 | 1LL / L108a | |
| RL 042L 0-6 | 2.41 | L110 | at high point near top of bank |
| RL 042L 6-12 | 0.193 | L110 | at high point near top of bank |
| DUP 127 | 0.26 | L110 | |
| RL 043L 0-6 | 1.28 | 14LL / L107 | |
| RL 044L 0-6 | 5.3 | 1LL / L108a | |
| RL 044L 6-12 | 0.098 (J) | 1LL / L108a | |
| RL 045L 0-6 | 2.22 | L108a | |
| RL 511R 0-6 | 17.7 | 3LR / L201c | |
| RL 511R 6-12 | 11.3 | 3LR / L201c | |
| RL 511R 12-18 | 3 | 3LR / L201c | |
| RL 512R 0-6 | 0.531 | 7LR | |
| RL 512R 6-12 | <0.0361 | 7LR | |
| DUP 112 | 0.0479 (J) | 7LR | |
| RL 513R 0-6 | 2.42 | 8LR | |
| RL 513R 6-12 | 0.516 | 8LR | |
| RL 514R 0-6 | 2.31 | 4LR / L201c | |
| RL 514R 6-12 | 0.591 | 4LR / L201c | |
| RL 515R 0-6 | 0.518 | 6LR | |
| RL 515R 6-12 | 0.197 | 6LR | |
| RL 516R 0-6 | 6.64 | 11LR / L205 | at high point near top of bank |
| RL 516R 6-12 | 0.232 | 11LR / L205 | at high point near top of bank |
| RL 517R 0-6 | 6.64 | 3MR / L206 | |
| RL 517R 6-12 | 1.3 | 3MR / L206 | |
| RL 518R 0-6 | 12.4 | 1LR / L201c | |
| RL 518R 6-12 | 6.44 | 1LR / L201c | |
| RL 518R 12-18 | 0.287 | 1LR / L201c | |
| RL 519R 0-6 | 0.0405 | 1LR / L201c | |
| RL 519R 6-12 | <0.0361 | 1LR / L201c | |
| RL 520R 0-6 | 5.63 | L201c | |
| RL 520R 6-12 | 0.527 | L201c | |
| RL 521R 0-6 | 9.49 | L205 | |
| RL 522R 0-6 | 0.532 | L205 | |
| RL 523R 0-6 | 1.8 | L205 | |
| RL 524R 0-6 | 3.5 | L206 | |
| RL 525R 0-6 | 5.13 | L206 | |
| RL 526R 0-6 | 3.92 | L201d | |
| RL 527R 0-6 | 2.34 | L201d | |
| RL 528R 0-6 | 4.77 | 9LR / L205 | at high point near top of bank |

Table 1. Additional Characterization Sampling Results 2011

Reach L

Hayton Area Remediation Project

10/03/2011

| Sample Name | Total PCBs (mg/kg) | Location | Comments |
|--------------|-----------------------|----------|----------------------------|
| RL 529R 0-6 | 6.9 | L205 | about 20 away from bank |
| RL 530R 0-6 | 4.58 | L205 | about 35 ft away from bank |
| RL 531R 0-6 | 2.46 | L201 | |
| RL 531R 6-12 | 0.503 | L201 | |
| RL 532R 0-6 | 6.87 | L202 | |
| RL 533R 0-6 | 11.9 | L202 | |
| RL 534R 0-6 | 3.01 | L202 | |

(J) = Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

Table 2. Rationale for Modified Removal Boundaries
Reach L
Hayton Area Remediation Project

10/03/2011

| Removal Zone ID | Rationale |
|-----------------|--|
| L102 | <ul style="list-style-type: none"> Upstream boundary established by samples RL-270+00-W10 0-6" = 3.6 mg/kg; and RL 042L 0-6" = 2.41 mg/kg. Upland boundary established by samples RL-270+00-W10 0-6" = 3.6 mg/kg; RL 040L 0-6" = 4.93 mg/kg; and the northwest polygon boundary of 3LLc, with reference to sample RL-272+00-W40 0-6" = 0.37 mg/kg. Downstream boundary established by sample RL 004L 0-6" = 2.53 mg/kg. Boundary with L110 established by sample RL 027L 6-12" = 3.14 mg/kg; the polygon line between 3LLa and 3LLc; and sample RL 036L 6-12" = 4.67 mg/kg. Floor established by samples RL 027L 6-12" = 3.14 mg/kg; and RL-272+00-W10 6-12" = 0.72 mg/kg. |
| L108 | <ul style="list-style-type: none"> Upstream boundary established by sample RL 022L 6-12" = 4.56 mg/kg. Upland boundary established by sample RL 021L 6-12" = 2.83 mg/kg. Downstream boundary established by sample RL 023L 6-12" = 2.96 mg/kg. Floor established by sample RL 014L 12-18" = 0.337 mg/kg. |
| L108a | <ul style="list-style-type: none"> Upstream boundary established by samples RL 041L 6-12" = 3.46 mg/kg; RL 044L 6-12" = 0.098 (J) mg/kg; and RK 042L 6-12" = 0.349 mg/kg. Upland boundary established by samples RL 045L 0-6" = 2.22 mg/kg; RL 038L 0-6" = 0.255 mg/kg; and RL 001L 0-6" = 1.5 mg/kg. Downstream boundary established by sample RL 001L 0-6" = 1.5 mg/kg. Boundary with L108 established by samples RL 022L 6-12" = 4.58 mg/kg; RL 021L 6-12" = 2.83 mg/kg; and RL 023L 6-12" = 2.96 mg/kg. Floor established by samples RL 022L 6-12" = 4.58 mg/kg; RL 021L 6-12" = 2.83 mg/kg; RL 023L 6-12" = 2.96 mg/kg; RL 041L 6-12" = 3.46 mg/kg; and RL 044L 6-12" = 0.098 (J) mg/kg. |
| L109 | <ul style="list-style-type: none"> Upstream boundary established by samples RL 024L 0-6" = 3.18 mg/kg; and RL 024L 6-12" = 0.716 mg/kg. Upland boundary established by samples RL 026L 0-6" = 0.541 mg/kg; and RL 026L 6-12" = 0.221 mg/kg. Downstream boundary established by samples RL 033L 0-6" = 3.31 mg/kg; and RL 033L 6-12" = 0.664 mg/kg. Floor established by sample RL 015L 12-18" = 0.204 mg/kg. |
| L110 | <ul style="list-style-type: none"> Upstream boundary established by samples RL 042L 0-6" = 2.41 mg/kg; and RL 042L 6-12" = 0.193 mg/kg. Boundary with L102 established by sample RL 027L 6-12" = 3.14 mg/kg; the polygon line between 3LLa and 3LLc; and sample RL 036L 6-12" = 4.67 mg/kg. Downstream boundary established by sample RL 036L 6-12" = 4.67 mg/kg. Floor established by sample RL 016L 12-18" = 4.66 mg/kg. |
| L201c | <ul style="list-style-type: none"> Upstream boundary established by sample RL 504R 0-6" = 3.83 mg/kg. Upland boundary established by the upland polygon line of 1LR, with reference to samples RL 519R 0-6" = 0.0405 (J) mg/kg; and RL 519R 6-12" = <0.0361 mg/kg; and sample RL 520R 6-12" = 0.527 mg/kg. Boundary with L201d established by the upland polygon boundary of 4LR, with reference to sample RL 520R 6-12" = 0.527 mg/kg. Downstream boundary established by samples RL 514R 0-6" = 2.31 mg/kg; and RL 514R 6-12" = 0.591 mg/kg. Floor established by samples RL 518R 12-18" = 0.287 mg/kg; and RL 511R 12-18" = 3.0 mg/kg. |

Table 2. Rationale for Modified Removal Boundaries**Reach L****Hayton Area Remediation Project****10/03/2011**

| Removal Zone ID | Rationale |
|------------------------|--|
| L201d | <ul style="list-style-type: none"> • Upstream boundary established by sample RL 520R 6-12" = 0.527 mg/kg. • Upland boundary established by sample RL 526R 0-6" = 3.92 mg/kg. • Boundary with L201c established by the upland polygon boundary of 4LR, with reference to sample RL 520R 6-12" = 0.527 mg/kg. • Downstream boundary established by sample RL 527R 0-6" = 2.34 mg/kg. • Floor established by sample RL 520R 6-12" = 0.527 mg/kg. |
| L202 | <ul style="list-style-type: none"> • Upstream boundary established by sample RL 534R 0-6" = 3.01 mg/kg. • Upland boundary established by samples RL 534R 0-6" = 3.01 mg/kg; RL-268+70-E60 0-6" = 1.5 mg/kg; and the upland polygon boundary of 2LRa, with reference to samples RL 519R 0-6" = 0.0405 (J) mg/kg and RL 534R 0-6" = 3.01 mg/kg. • Boundary with L201 and L201b established by the upland polygon line of 1LR, with reference to samples RL-268+70-E60 6-12" = 0.67 mg/kg and RL 519R 6-12" = <0.0361 mg/kg. • Downstream boundary established by the upland polygon line of 1LR, with reference to sample RL 519R 0-6" = 0.0405 (J) mg/kg. • Floor established by sample RL-268+70-E30 6-12" = 0.67 mg/kg. |
| L205 | <ul style="list-style-type: none"> • Upstream boundary established by samples RL 528R 0-6" = 4.77 mg/kg; and RL 530R 0-6" = 4.58 mg/kg. • Upland boundary established by samples RL 530R 0-6" = 4.58 mg/kg; and RL 523R 0-6" = 1.6 mg/kg; and the polygon line between 11LR and 12LR, with reference to sample RL 523R 0-6" = 1.6 mg/kg. • Downstream boundary established by sample RL 522R 0-6" = 0.532 mg/kg. • Floor established by sample RL 516R 6-12" = 0.232 mg/kg. |
| L206 | <ul style="list-style-type: none"> • Upstream boundary established by the creek bank near station 281+90. • Upland (northeast) boundary established by sample RL 524R 0-6", following the top of the ditch based on field observation. • Southeast boundary established by following the top of the ditch based on field observation. A post-removal verification sample (RL PRVW 514R 0-6") will be collected at the top of the ditch. • Downstream boundary established by the creek bank near station 287+00 (in Reach M). • Floor established by sample RL 517R 6-12" = 1.3 mg/kg. |

(J) = Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

Table 3. Proposed Post-Removal Verification Samples
Reach L
Hayton Area Remediation Project

10/03/2011

| Sample ID | In-channel¹ or Overbank | Type | Northing | Easting |
|----------------------|---|-------------|-----------------|----------------|
| RL IC PRVF 900C | In-channel | Floor | 733693 | 2469474 |
| RL IC PRVF 901C | In-channel | Floor | 733878 | 2469386 |
| RL IC PRVF 902C | In-channel | Floor | 734124 | 2469360 |
| RL IC PRVF 903C | In-channel | Floor | 734320 | 2469277 |
| RL IC PRVF 904C | In-channel | Floor | 734570 | 2469263 |
| RL IC PRVF 905C | In-channel | Floor | 734701 | 2469038 |
| RL BK PRVW 001L | Stream bank | Sidewall | 733741 | 2469462 |
| RL BK PRVW 002L | Stream bank | Sidewall | 733757 | 2469360 |
| RL BK PRVW 003L | Stream bank | Sidewall | 733886 | 2469385 |
| RL BK PRVW 004L | Stream bank | Sidewall | 733956 | 2469449 |
| RL BK PRVW 005L | Stream bank | Sidewall | 734116 | 2469363 |
| RL BK PRVW 006L | Stream bank | Sidewall | 734240 | 2469212 |
| RL BK PRVW 007L | Stream bank | Sidewall | 734427 | 2469337 |
| RL BK PRVW 008L | Stream bank | Sidewall | 734571 | 2469247 |
| RL BK PRVW 009L | Stream bank | Sidewall | 734693 | 2469165 |
| RL BK PRVW 010L | Stream bank | Sidewall | 734654 | 2468974 |
| RL BK PRVW 011L | Stream bank | Sidewall | 734046 | 2469406 |
| RL BK PRVW 012L | Stream bank | Sidewall | 734185 | 2469232 |
| RL BK PRVW 500R | Stream bank | Sidewall | 733752 | 2469470 |
| RL BK PRVW 501R | Stream bank | Sidewall | 733767 | 2469370 |
| RL BK PRVW 502R | Stream bank | Sidewall | 733879 | 2469394 |
| RL BK PRVW 503R | Stream bank | Sidewall | 733956 | 2469459 |
| RL BK PRVW 504R | Stream bank | Sidewall | 734127 | 2469367 |
| RL BK PRVW 505R | Stream bank | Sidewall | 734238 | 2469229 |
| RL BK PRVW 506R | Stream bank | Sidewall | 734436 | 2469349 |
| RL BK PRVW 507R | Stream bank | Sidewall | 734580 | 2469274 |
| RL BK PRVW 508R | Stream bank | Sidewall | 734706 | 2469166 |
| RL BK PRVW 509R | Stream bank | Sidewall | 734681 | 2468977 |
| RL BK PRVW 510R | Stream bank | Sidewall | 734049 | 2469418 |
| RL BK PRVW 511R | Stream bank | Sidewall | 734724 | 2469078 |
| RL PRVF 511R 12-18 " | Overbank | Floor | 733781 | 2469372 |
| RL PRVF 512R 12-18 " | Overbank | Floor | 734320 | 2469303 |
| RL PRVF 513R 6-12 " | Overbank | Floor | 734709 | 2468931 |
| RL PRVF 514R 12-18" | Overbank | Floor | 733899 | 2469423 |
| RL PRVF 515R 6-12" | Overbank | Floor | 734566 | 2469289 |
| RL PRVF 516R 6-12" | Overbank | Floor | 734800 | 2468961 |
| RL PRVF 517R 6-12" | Overbank | Floor | 733659 | 2469506 |
| RL PRVW 518R 0-6" | Overbank | Sidewall | 733655 | 2469515 |
| RL PRVW 519R 0-6" | Overbank | Sidewall | 733769 | 2469470 |
| RL PRVW 520R 0-6" | Overbank | Sidewall | 733805 | 2469420 |
| RL PRVF 521R 6-12" | Overbank | Floor | 733821 | 2469380 |

**Table 3. Proposed Post-Removal Verification Samples
Reach L
Hayton Area Remediation Project**

10/03/2011

| Sample ID | In-channel¹ or Overbank | Type | Northing | Easting |
|----------------------|---|-------------|-----------------|----------------|
| RL PRVF 014L 12-18 " | Overbank | Floor | 734439 | 2469321 |
| RL PRVF 015L 6-12 " | Overbank | Floor | 734677 | 2469164 |
| RL PRVF 016L 18-24 " | Overbank | Floor | 734704 | 2469086 |
| RL PRVF 017L 0-6 " | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 017L 6-12 " | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 017L 12-18 " | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 018L 12-18" | Overbank | Floor | 733726 | 2469450 |
| RL PRVF 019L 12-18" | Overbank | Floor | 733964 | 2469434 |
| RL PRVW 020L 0-6" | Overbank | Sidewall | 733756 | 2469327 |
| RL PRVW 021L 0-6" | Overbank | Sidewall | 734442 | 2469317 |
| RL PRVW 021L 6-12" | Overbank | Sidewall | 734442 | 2469317 |

¹ The locations of in-channel samples may be adjusted, or additional in-channel samples may be added, based on visual cues observed during removal.

**Table 4. Proposed Stream Bank PRV Samples - Reach L
Hayton Area Remediation Project**

10/03/2011

| PRV Sample Name or Removal Zone | Length of Streambank Represented | | Description |
|------------------------------------|-------------------------------------|-----------------------|--|
| | Upstream Station | Downstream Station | |
| Right Bank | | | |
| RL BK PRVW 500R | 266+00 | 268+00 | Outer meander along L201a and L201 |
| RL BK PRVW 501R | 268+00 | 269+45 | Inner meander along L201 and L201b |
| RL BK PRVW 502R | 269+45 | 270+50 | Straight section downstream of L201b |
| RL BK PRVW 503R | 270+50 | 271+40 | Outer meander |
| RL BK PRVW 510R | 271+40 | 272+50 | Straight section near Station 272+00 |
| RL BK PRVW 504R | 272+50 | 273+75 | Outer meander |
| RL BK PRVW 505R | 273+75 | 276+00 | Inner meander |
| RL BK PRVW 506R | 276+00 | 278+00 | Outer meander opposite of L103 |
| RL BK PRVW 507R | 278+00 | 279+80 | Straight section |
| RL BK PRVW 508R | 279+80 | 281+20 | Outer meander opposite of L105 and L106 |
| RL BK PRVW 511R | 281+20 | 282+00 | Opposite of L106 |
| RL BK PRVW 509R | 282+00 | 284+00 | Inner meander along L204 |
| Left Bank | | | |
| RL BK PRVW 001L | 266+00 | 268+00 | Inner meander opposite of L201a and L201 |
| RL BK PRVW 002L | 268+00 | 269+65 | Outer meander along L101 |
| RL BK PRVW 003L | 269+65 | 270+50 | Straight section |
| RL BK PRVW 004L | 270+50 | 271+40 | Inner meander |
| RL BK PRVW 011L | 271+40 | 272+50 | Straight section near Station 272+00 |
| RL BK PRVW 005L | 272+50 | 273+75 | Inner meander |
| RL BK PRVW 012L | 273+75 | 274+70 | Left bank at 274+40, along polygon 4LL |
| RL BK PRVW 006L | 274+70 | 276+00 | Outer meander |
| RL BK PRVW 007L | 276+00 | 278+00 | Inner meander along L103 |
| RL BK PRVW 008L | 278+00 | 279+80 | Straight section upstream of L105 |
| RL BK PRVW 009L | 279+80 | 281+10 | Inner meander along L105 |
| L106 | 281+10 | 282+10 | 18 removal " |
| RL BK PRVW 010L | 282+10 | 284+00 | Outer meander along L107 |

**Table 1. In-Channel Sampling Location Summary
HARP OU2/L & OU3**

| Sampling Point | Date | Northing | Easting | Elevation | Sampling Depth | Sediment Thickness | Average Sediment Thickness | Water Depth | Calculated Water Elevation | Average Water Elevation |
|----------------|----------|--------------------|-------------|-------------|----------------|--------------------|----------------------------|-------------|----------------------------|-------------------------|
| | | (State Plane - ft) | | (NAVD - ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) |
| RI-222+30-IC | 08/24/05 | 731,467.0 | 2,471,800.0 | 816.6 | 1.40 | 0.80 | Reach I 0.7 | 1.55 | 818.2 | Reach I 818.1 |
| RI-227+00-IC | 08/24/05 | 731,768.3 | 2,471,618.9 | 817.1 | 1.00 | 0.40 | | 0.94 | 818.0 | |
| RI-231+30-IC | 08/24/05 | 731,991.8 | 2,471,366.4 | 816.4 | 0.90 | 0.80 | | 1.56 | 818.0 | |
| RJ-232+50-IC | 08/24/05 | 731,960.9 | 2,471,236.3 | 816.7 | 1.00 | 0.60 | Reach J 0.6 | 1.19 | 817.9 | Reach J 817.8 |
| RJ-234+50-IC | 08/24/05 | 731,946.3 | 2,471,092.2 | 816.6 | 1.10 | 0.50 | | 1.32 | 817.9 | |
| RJ-237+00-IC | 08/24/05 | 731,962.2 | 2,470,919.9 | 816.3 | 0.80 | 0.80 H | | 1.41 | 817.7 | |
| RJ-241+20-IC | 08/24/05 | 732,197.4 | 2,470,774.5 | 816.6 | 0.80 | 0.50 | | 1.31 | 817.9 | |
| RJ-243+50-IC | 08/24/05 | 732,251.7 | 2,470,610.2 | 817.0 | 1.50 | 0.60 | | 0.62 | 817.6 | |
| RJ-247+70-IC | 08/24/05 | 732,586.7 | 2,470,462.9 | 816.4 | 1.10 | 0.50 | | 1.49 | 817.9 | |
| RJ-249+40-IC | 08/24/05 | 732,732.7 | 2,470,466.3 | 815.9 | 1.40 | 0.40 | | 1.82 | 817.7 | |
| RK-251+10-IC | 08/24/05 | 732,817.5 | 2,470,353.7 | 815.8 | 1.20 | 0.30 | Reach K 0.4 | 1.87 | 817.7 | Reach K 817.1 |
| RK-252+50-IC | 08/24/05 | 732,811.0 | 2,470,130.0 | 816.1 | 0.90 | 0.50 | | 1.47 | 817.6 | |
| RK-254+80-IC | 08/24/05 | 732,843.0 | 2,470,022.3 | 815.6 | 0.90 | 0.50 | | 1.79 | 817.4 | |
| RK-257+00-IC | 08/24/05 | 733,009.0 | 2,469,849.9 | 816.1 | 0.80 | 0.25 | | 1.29 | 817.4 | |
| RK-259+00-IC | 08/24/05 | 733,146.1 | 2,469,890.4 | 815.8 | 1.50 | 0.40 | | 1.49 | 817.3 | |
| RK-263+50-IC | 08/23/05 | 733,418.4 | 2,469,614.9 | 815.4 | 1.00 | 0.50 | | 0.92 | 816.3 | |
| RK-265+00-IC | 08/23/05 | 733,552.9 | 2,469,534.0 | 815.3 | 1.40 | 0.60 | | 0.70 | 816.0 | |
| RL-266+40-IC | 08/23/05 | 733,626.0 | 2,469,526.5 | 815.0 | 0.75 | 0.60 | Reach L 0.6 | 0.92 | 815.9 | Reach L 816.0 |
| RL-268+70-IC | 08/23/05 | 733,743.1 | 2,469,405.5 | 814.7 | 1.20 | 0.60 | | 1.19 | 815.9 | |
| RL-272+00-IC | 08/23/05 | 734,038.0 | 2,469,413.2 | 814.9 | 0.70 | 0.20 | | 1.18 | 816.1 | |
| RL-277+70-IC | 08/23/05 | 734,440.9 | 2,469,334.3 | 814.5 | 0.80 | 0.70 | | 1.36 | 815.9 | |
| RL-282+00-IC | 08/23/05 | 734,705.1 | 2,469,148.9 | 815.0 | 0.80 | 0.80 H | | 1.09 | 816.1 | |
| RM-287+50-IC | 08/23/05 | 735,053.8 | 2,468,763.3 | 814.6 | 1.00 | 0.50 | Reach M 0.7 | 1.15 | 815.8 | Reach M 815.7 |
| RM-290+00-IC | 08/23/05 | 735,231.3 | 2,468,693.8 | 814.6 | 0.60 | 0.60 C | | 0.94 | 815.5 | |
| RM-293+30-IC | 08/23/05 | 735,424.5 | 2,468,696.0 | 814.5 | 0.90 | 0.70 | | 1.21 | 815.7 | |
| RM-295+40-IC | 08/23/05 | 735,395.5 | 2,468,466.8 | 814.9 | 1.25 | 0.60 | | 0.82 | 815.7 | |
| RM-298+50-IC | 08/23/05 | 735,595.0 | 2,468,395.8 | 814.6 | 1.30 | 0.90 | | 1.09 | 815.7 | |
| RN-304+50-IC | 08/23/05 | 735,738.2 | 2,467,978.9 | 813.8 | 1.25 | 0.70 | Reach N 0.8 | 1.72 | 815.5 | Reach N 815.5 |
| RN-307+60-IC | 08/23/05 | 735,832.4 | 2,467,838.2 | 814.3 | 0.80 | 0.80 H | | 1.30 | 815.6 | |
| RN-311+60-IC | 08/23/05 | 736,013.6 | 2,467,550.3 | 814.5 | 1.30 | 0.70 | | 0.87 | 815.4 | |
| RN-314+00-IC | 08/23/05 | 736,171.1 | 2,467,397.8 | 814.3 | 0.90 | 0.90 C | | 1.08 | 815.4 | |
| RN-317+00-IC | 08/23/05 | 736,349.5 | 2,467,198.7 | 814.1 | 0.70 | 0.70 H | | 1.43 | 815.5 | |

Table 2. Sediment Poling Summary
HARP OU2/L & OU3

| Reach | Poling Location | Northing | Easting | Sediment Thickness Observations (ft) | | | Average Sediment Thickness (ft) | |
|-------|-----------------|--------------------|--------------|--------------------------------------|--------|------------|---------------------------------|-------|
| | | (State Plane - ft) | | Left Side | Center | Right Side | Across Creek | Reach |
| H | 265 | 730,919.57 | 2,472,741.24 | 0.5 | 0.8 | 0.8 | 0.7 | 0.7 |
| | 266 | 730,982.20 | 2,472,711.68 | 1.7 | 1.7 | 1.7 | 1.7 | |
| | 267 | 731,015.34 | 2,472,677.62 | 0.3 | 0.3 | 0.3 | 0.3 | |
| | 268 | 731,075.17 | 2,472,636.75 | 0.5 | 0.2 | 0.2 | 0.3 | |
| | 268A | 731,152.30 | 2,472,595.78 | 0.5 | 0.3 | 0.3 | 0.4 | |
| | 269 | 731,272.09 | 2,472,478.67 | 0.8 | 0.8 | 0.3 | 0.6 | |
| | 270 | 731,411.25 | 2,472,318.05 | 0.7 | 0.7 | 0.7 | 0.7 | |
| I | 271 | 731,300.17 | 2,472,113.86 | 0.7 | 1.0 | 0.7 | 0.8 | 0.5 |
| | 272 | 731,328.58 | 2,472,065.83 | 0.3 | 0.5 | 0.5 | 0.4 | |
| | 273 | 731,477.46 | 2,471,894.80 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 274 | 731,514.30 | 2,471,772.68 | 0.2 | 0.5 | 0.8 | 0.5 | |
| | 275 | 731,535.45 | 2,471,779.23 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 276 | 731,694.86 | 2,471,788.77 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 276A | 731,758.95 | 2,471,645.70 | 0.5 | 0.6 | 0.6 | 0.6 | |
| J | 277 | 731,868.58 | 2,471,460.25 | 0.5 | 0.5 | 0.5 | 0.5 | 0.5 |
| | 278 | 731,954.97 | 2,471,252.06 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 279 | 731,945.38 | 2,471,098.73 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 280 | 731,963.72 | 2,470,919.30 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 281 | 732,431.60 | 2,470,569.89 | 0.5 | 0.5 | 0.5 | 0.5 | |
| K | 281A | 732,529.05 | 2,470,492.65 | 0.6 | 0.6 | 0.6 | 0.6 | 0.7 |
| | 282 | 732,880.42 | 2,470,265.68 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 283 | 732,827.64 | 2,470,186.64 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 284 | 732,896.30 | 2,469,896.79 | 1.0 | 0.5 | 1.0 | 0.8 | |
| | 285 | 733,202.12 | 2,469,766.35 | 0.8 | 0.8 | 0.8 | 0.8 | |
| | 285A | 733,208.65 | 2,469,740.51 | 0.8 | 0.8 | 0.8 | 0.8 | |
| | 286 | 733,324.34 | 2,469,705.33 | 0.6 | 0.6 | 0.6 | 0.6 | |
| L | 287 | 733,924.73 | 2,469,425.82 | 0.6 | 0.6 | 0.6 | 0.6 | 0.6 |
| | 288 | 734,045.91 | 2,469,409.89 | 0.8 | 0.8 | 0.8 | 0.8 | |
| | 289 | 734,158.31 | 2,469,275.71 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 290 | 734,290.95 | 2,469,259.97 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 290A | 734,334.56 | 2,469,306.12 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 291 | 734,499.06 | 2,469,294.25 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 292 | 734,595.54 | 2,469,261.34 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 293 | 734,659.91 | 2,469,203.34 | 0.6 | 0.6 | 0.2 | 0.5 | |
| | 294 | 734,679.45 | 2,468,943.58 | 0.5 | 0.5 | 1.0 | 0.7 | |
| M | 295 | 734,753.61 | 2,468,797.58 | 1.0 | 1.0 | 1.0 | 1.0 | 0.6 |
| | 296 | 734,924.88 | 2,468,780.06 | 0.5 | 0.5 | 0.8 | 0.6 | |
| | 297 | 735,027.67 | 2,468,783.37 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 297A | 735,058.59 | 2,468,770.16 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 298 | 735,137.80 | 2,468,711.83 | 0.7 | 0.6 | 0.6 | 0.6 | |
| | 298A | 735,225.50 | 2,468,698.14 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 299 | 735,357.62 | 2,468,782.76 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 300 | 735,432.04 | 2,468,698.48 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 301 | 735,389.87 | 2,468,558.65 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 301A | 735,382.81 | 2,468,484.04 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 302 | 735,460.54 | 2,468,388.67 | 0.5 | 0.5 | 0.5 | 0.5 | |
| | 303 | 735,551.30 | 2,468,345.84 | 1.5 | 0.6 | 0.6 | 0.9 | |
| | 304 | 735,640.40 | 2,468,383.13 | 0.8 | 0.8 | 0.8 | 0.8 | |
| | 305 | 735,675.57 | 2,468,279.22 | 0.5 | 1.0 | 1.0 | 0.8 | |
| | 306 | 735,713.46 | 2,468,183.04 | 0.6 | 0.6 | 0.6 | 0.6 | |
| | 307 | 735,641.51 | 2,468,069.58 | 0.5 | 0.5 | 0.5 | 0.5 | |

**Table 3. Overbank Sampling Location Summary
HARP OU2/L & OU3**

| Sampling Point | Date | Northing | Easting | Elevation | Original Point or Step-Out | Sampling Depth (ft) |
|----------------|----------|--------------------|--------------|-------------|----------------------------|---------------------|
| | | (State Plane - ft) | | (NAVD - ft) | | |
| RJ-246+20-S80 | 09/29/05 | 732,457.68 | 2,470,508.68 | na | Sept/Oct. Step-Out | 2.4 |
| RJ-247+50-E20 | 11/11/05 | 732,577.29 | 2,470,498.70 | na | Nov. Step-Out | 4.0 |
| RJ-247+70-E20 | 09/14/05 | 732,594.78 | 2,470,489.01 | 818.6 | Original Point | 2.25 |
| RJ-247+70-E40 | 09/29/05 | 732,596.18 | 2,470,508.96 | na | Sept/Oct. Step-Out | 2.2 |
| RJ-247+70-E60 | 09/29/05 | 732,598.27 | 2,470,528.86 | na | Sept/Oct. Step-Out | 2.2 |
| RJ-247+90-E20 | 11/11/05 | 732,613.81 | 2,470,482.83 | na | Nov. Step-Out | 4.0 |
| RJ-249+00-W10 | 09/14/05 | 732,710.16 | 2,470,470.79 | 818.9 | Original Point | 2.0 |
| RJ-249+40-N10 | 09/14/05 | 732,760.19 | 2,470,469.20 | 818.4 | Original Point | 2.0 |
| RJ-249+40-N40 | 09/30/05 | 732,789.30 | 2,470,476.46 | na | Sept/Oct. Step-Out | 1.9 |
| RJ-249+40-S100 | 11/14/05 | 732,694.05 | 2,470,376.96 | na | Nov. Step-Out | 2.0 |
| RJ-249+40-S50 | 09/14/05 | 732,699.45 | 2,470,426.65 | 818.6 | Original Point | 1.5 |
| RJ-249+40-S80 | 09/30/05 | 732,696.84 | 2,470,396.77 | na | Sept/Oct. Step-Out | 2.4 |
| RK-251+10-N10 | 09/14/05 | 732,834.78 | 2,470,358.85 | 818.4 | Original Point | 2.75 |
| RK-251+10-N20 | 09/14/05 | 732,843.88 | 2,470,362.16 | 818.7 | Original Point | 2.0 |
| RK-251+10-N50 | 09/14/05 | 732,872.86 | 2,470,372.73 | 820.0 | Original Point | 2.0 |
| RK-251+10-S20 | 09/15/05 | 732,790.82 | 2,470,355.46 | 819.0 | Original Point | 2.25 |
| RK-251+10-S50 | 09/30/05 | 732,760.93 | 2,470,352.85 | na | Sept/Oct. Step-Out | 1.9 |
| RK-253+30-N100 | 09/15/05 | 732,940.51 | 2,470,158.55 | 819.9 | Original Point | 1.75 |
| RK-253+30-S20 | 09/15/05 | 732,803.81 | 2,470,068.81 | 817.6 | Original Point | 2.0 |
| RK-253+30-S40 | 09/30/05 | 732,784.12 | 2,470,065.34 | na | Sept/Oct. Step-Out | 1.5 |
| RK-254+80-S15 | 09/15/05 | 732,804.01 | 2,469,992.23 | 818.8 | Original Point | 2.0 |
| RK-254+80-S5 | 09/15/05 | 732,809.14 | 2,470,001.43 | 818.4 | Original Point | 1.6 |
| RK-254+80-S50 | 09/15/05 | 732,773.36 | 2,469,960.64 | 820.8 | Original Point | 2.0 |
| RK-256+00-E10 | 09/30/05 | 732,882.75 | 2,469,982.50 | na | Sept/Oct. Step-Out | 2.0 |
| RK-256+00-E70 | 09/30/05 | 732,942.42 | 2,469,988.77 | na | Sept/Oct. Step-Out | 2.0 |
| RK-257+00-E10 | 09/15/05 | 732,990.82 | 2,469,880.24 | 818.1 | Original Point | 2.0 |
| RK-257+00-E120 | 09/30/05 | 733,021.98 | 2,469,997.13 | na | Sept/Oct. Step-Out | 2.0 |
| RK-257+00-E90 | 09/15/05 | 733,015.74 | 2,469,967.79 | 818.7 | Original Point | 2.3 |
| RK-258+00-W10 | 09/15/05 | 733,071.18 | 2,469,873.95 | 818.5 | Original Point | 2.0 |
| RK-258+00-W60 | 09/15/05 | 733,091.11 | 2,469,823.97 | 819.8 | Original Point | 1.0 |
| RK-261+10-W10 | 09/15/05 | 733,214.82 | 2,469,699.16 | 818.5 | Original Point | 2.5 |
| RK-261+10-W25 | 09/15/05 | 733,209.92 | 2,469,686.65 | 819.4 | Original Point | 2.0 |
| RK-261+10-W50 | 09/15/05 | 733,204.86 | 2,469,656.12 | 821.2 | Original Point | 0.5 |
| RK-263+80-S10 | 09/15/05 | 733,420.20 | 2,469,560.60 | 818.1 | Original Point | 2.3 |
| RK-263+80-S30 | 09/15/05 | 733,402.70 | 2,469,543.88 | 818.4 | Original Point | 1.0 |
| RK-265+00-E10 | 09/15/05 | 733,554.64 | 2,469,551.54 | 817.0 | Original Point | 2.0 |
| RK-265+00-E30 | 09/15/05 | 733,558.22 | 2,469,573.90 | 818.5 | Original Point | 1.5 |
| RK-265+00-E50 | 09/30/05 | 733,557.52 | 2,469,593.89 | na | Sept/Oct. Step-Out | 2.0 |
| RK-265+00-W10 | 09/15/05 | 733,552.42 | 2,469,518.47 | 818.0 | Original Point | 1.75 |
| RK-265+00-W30 | 09/15/05 | 733,550.15 | 2,469,492.60 | 818.0 | Original Point | 2.5 |
| RK-265+00-W50 | 09/30/05 | 733,552.94 | 2,469,472.79 | na | Sept/Oct. Step-Out | 2.0 |
| RL-267+00-W100 | 09/15/05 | 733,679.50 | 2,469,373.68 | 818.0 | Original Point | 1.0 |
| RL-267+40-E10 | 09/30/05 | 733,732.95 | 2,469,489.74 | na | Sept/Oct. Step-Out | 1.9 |
| RL-267+40-E30 | 09/30/05 | 733,733.79 | 2,469,499.17 | na | Sept/Oct. Step-Out | 2.2 |
| RL-268+70-E10 | 09/15/05 | 733,789.20 | 2,469,389.90 | 817.9 | Original Point | 2.25 |
| RL-268+70-E30 | 09/15/05 | 733,771.71 | 2,469,376.12 | 817.7 | Original Point | 2.0 |
| RL-268+70-E60 | 09/30/05 | 733,808.48 | 2,469,412.88 | na | Sept/Oct. Step-Out | 2.5 |
| RL-268+70-W10 | 09/15/05 | 733,744.87 | 2,469,347.31 | 818.1 | Original Point | 2.0 |
| RL-268+70-W30 | 10/03/05 | 733,731.49 | 2,469,332.45 | na | Sept/Oct. Step-Out | 2.5 |
| RL-270+00-W10 | 10/03/05 | 733,905.88 | 2,469,357.90 | na | Sept/Oct. Step-Out | 2.0 |
| RL-270+00-W80 | 10/03/05 | 733,947.56 | 2,469,324.82 | na | Sept/Oct. Step-Out | 2.25 |
| RL-272+00-E100 | 09/15/05 | 734,048.60 | 2,469,520.97 | 818.3 | Original Point | 3.0 |
| RL-272+00-E20 | 09/15/05 | 734,048.91 | 2,469,431.91 | 818.9 | Original Point | 2.0 |
| RL-272+00-W10 | 09/15/05 | 734,028.56 | 2,469,397.76 | 817.9 | Original Point | 2.0 |

**Table 3. Overbank Sampling Location Summary
HARP OU2/L & OU3**

| Sampling Point | Date | Northing | Easting | Elevation | Original Point or Step-Out | Sampling Depth (ft) |
|----------------|----------|--------------------|--------------|-------------|----------------------------|---------------------|
| | | (State Plane - ft) | | (NAVD - ft) | | |
| RL-272+00-W40 | 10/03/05 | 734,008.88 | 2,469,375.12 | na | Sept/Oct. Step-Out | 2.0 |
| RL-274+40-S10 | 09/16/05 | 734,173.08 | 2,469,242.27 | 817.4 | Original Point | 2.25 |
| RL-274+40-S30 | 09/16/05 | 734,150.52 | 2,469,231.67 | 818.5 | Original Point | 1.5 |
| RL-275+80-E10 | 09/15/05 | 734,322.37 | 2,469,300.42 | 816.9 | Original Point | 2.5 |
| RL-275+80-E40 | 09/30/05 | 734,298.73 | 2,469,318.89 | na | Sept/Oct. Step-Out | 2.2 |
| RL-277+70-E20 | 09/15/05 | 734,471.47 | 2,469,350.19 | 817.4 | Original Point | 2.3 |
| RL-277+70-W10 | 09/16/05 | 734,428.24 | 2,469,330.36 | 816.8 | Original Point | 2.5 |
| RL-277+70-W40 | 09/16/05 | 734,397.22 | 2,469,309.30 | 818.1 | Original Point | 2.0 |
| RL-278+00-W100 | 09/16/05 | 734,417.98 | 2,469,254.17 | 818.5 | Original Point | 2.0 |
| RL-279+50-E100 | 09/15/05 | 734,619.99 | 2,469,371.39 | 817.3 | Original Point | 2.75 |
| RL-280+10-E10 | 09/16/05 | 734,682.17 | 2,469,221.47 | 818.2 | Original Point | 2.75 |
| RL-280+10-E30 | 09/16/05 | 734,697.05 | 2,469,239.68 | 818.0 | Original Point | 2.5 |
| RL-280+10-W15 | 09/16/05 | 734,649.65 | 2,469,198.43 | 817.2 | Original Point | 2.25 |
| RL-280+10-W30 | 09/16/05 | 734,632.42 | 2,469,188.11 | 818.0 | Original Point | 1.75 |
| RL-280+10-W5 | 09/16/05 | 734,660.53 | 2,469,202.11 | 816.6 | Original Point | 2.25 |
| RL-281+80-S15 | 09/16/05 | 734,694.25 | 2,469,081.95 | 817.2 | Original Point | 2.0 |
| RL-281+80-S40 | 09/16/05 | 734,673.14 | 2,469,109.90 | 817.7 | Original Point | 2.0 |
| RL-281+90-S5 | 09/16/05 | 734,704.55 | 2,469,068.05 | 817.3 | Original Point | 1.5 |
| RL-282+50-N20 | 09/16/05 | 734,704.95 | 2,469,001.41 | 817.9 | Original Point | 2.0 |
| RL-282+50-N40 | 10/03/05 | 734,724.84 | 2,469,003.50 | na | Sept/Oct. Step-Out | 1.5 |
| RL-282+50-S10 | 10/03/05 | 734,650.25 | 2,469,000.72 | na | Sept/Oct. Step-Out | 1.5 |
| RL-282+50-S30 | 11/14/05 | 734,630.25 | 2,469,000.72 | na | Nov. Step-Out | 2.0 |
| RM-285+50-E30 | 09/16/05 | 734,798.54 | 2,468,809.97 | 817.5 | Original Point | 1.75 |
| RM-285+50-E5 | 09/16/05 | 734,795.33 | 2,468,785.60 | 816.5 | Original Point | 2.0 |
| RM-285+50-W25 | 09/16/05 | 734,791.97 | 2,468,743.04 | 818.3 | Original Point | 2.0 |
| RM-285+50-W5 | 09/16/05 | 734,793.63 | 2,468,758.02 | 818.1 | Original Point | 2.25 |
| RM-287+50-E15 | 09/20/05 | 735,064.77 | 2,468,785.83 | 817.4 | Original Point | 2.0 |
| RM-287+50-W30 | 09/19/05 | 735,035.66 | 2,468,725.94 | 817.2 | Original Point | 2.0 |
| RM-287+50-W5 | 09/19/05 | 735,047.79 | 2,468,751.71 | 816.5 | Original Point | 2.0 |
| RM-287+50-W50 | 10/03/05 | 735,025.96 | 2,468,708.44 | na | Sept/Oct. Step-Out | 2.25 |
| RM-289+00-W10 | 09/19/05 | 735,133.93 | 2,468,699.33 | 817.8 | Original Point | 2.0 |
| RM-289+00-W40 | 10/03/05 | 735,122.21 | 2,468,671.72 | na | Sept/Oct. Step-Out | 2.0 |
| RM-290+00-E100 | 09/20/05 | 735,229.65 | 2,468,811.11 | 816.7 | Original Point | 2.0 |
| RM-290+00-W100 | 09/19/05 | 735,217.10 | 2,468,580.56 | 816.8 | Original Point | 2.5 |
| RM-292+30-N10 | 09/19/05 | 735,424.73 | 2,468,815.42 | 817.4 | Original Point | 2.0 |
| RM-292+30-N40 | 10/03/05 | 735,441.51 | 2,468,840.29 | na | Sept/Oct. Step-Out | 2.25 |
| RM-292+30-S10 | 09/19/05 | 735,399.51 | 2,468,783.39 | 817.5 | Original Point | 2.0 |
| RM-292+30-S40 | 09/19/05 | 735,378.54 | 2,468,758.21 | 817.4 | Original Point | 2.75 |
| RM-292+30-S80 | 09/19/05 | 735,355.81 | 2,468,732.81 | 817.1 | Original Point | 2.0 |
| RM-293+30-N10 | 09/19/05 | 735,442.06 | 2,468,687.64 | 817.7 | Original Point | 2.0 |
| RM-293+30-N40 | 10/03/05 | 735,471.29 | 2,468,680.89 | na | Sept/Oct. Step-Out | 2.0 |
| RM-293+30-S10 | 09/19/05 | 735,408.43 | 2,468,706.49 | 816.9 | Original Point | 2.0 |
| RM-293+30-S30 | 09/19/05 | 735,382.82 | 2,468,717.98 | 816.1 | Original Point | 2.5 |
| RM-294+20-S10 | 10/03/05 | 735,383.62 | 2,468,619.98 | na | Sept/Oct. Step-Out | 2.25 |
| RM-294+20-S30 | 10/03/05 | 735,361.40 | 2,468,621.65 | na | Sept/Oct. Step-Out | 2.75 |
| RM-296+50-E20 | 09/19/05 | 735,480.97 | 2,468,419.92 | 816.7 | Original Point | 2.0 |
| RM-296+50-E50 | 10/03/05 | 735,499.44 | 2,468,443.56 | na | Sept/Oct. Step-Out | 2.25 |
| RM-296+50-W10 | 09/19/05 | 735,439.79 | 2,468,379.99 | 817.6 | Original Point | 1.5 |
| RM-296+50-W40 | 09/19/05 | 735,415.47 | 2,468,357.64 | 816.6 | Original Point | 2.25 |
| RM-296+50-W60 | 10/03/05 | 735,401.33 | 2,468,343.50 | na | Sept/Oct. Step-Out | 2.25 |
| RM-297+90-E10 | 09/19/05 | 735,553.83 | 2,468,381.09 | 816.8 | Original Point | 2.0 |
| RM-297+90-E25 | 09/19/05 | 735,558.41 | 2,468,393.75 | 817.0 | Original Point | 2.5 |
| RM-297+90-E50 | 10/03/05 | 735,565.30 | 2,468,417.78 | na | Sept/Oct. Step-Out | 2.0 |
| RM-298+00-W120 | 10/03/05 | 735,493.05 | 2,468,233.88 | na | Sept/Oct. Step-Out | 2.0 |

**Table 4. In-Channel Analytical Results Summary
HARP OU2/L & OU3**

| Sample Location and Depth (Inches) | Sample Date | Percent Solids | PCB Aroclors (mg/kg) | | | | | | | | Total PCBs (mg/kg) |
|------------------------------------|-------------|----------------|----------------------|---------|---------|---------|---------|---------|---------|---------|--------------------|
| | | | 1016 | 1221 | 1232 | 1242 | 1248 | 1254 | 1260 | | |
| RK-252+50-IC 6 - 8 | 10/04/05 | 66.4 | < 0.040 | < 0.040 | < 0.040 | < 0.040 | < 0.040 | < 0.040 | < 0.040 | < 0.040 | < 0.040 |
| RK-254+80-IC 0 - 6 | 08/24/05 | 34.8 | < 0.076 | < 0.076 | < 0.076 | < 0.076 | 0.700 | 2.400 | 0.640 | 3.700 | |
| RK-254+80-IC 6 - 9 | 08/24/05 | 44.8 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | |
| RK-257+00-IC 0 - 3 | 08/24/05 | 50.5 | < 0.053 | < 0.053 | < 0.053 | < 0.053 | 0.380 | 0.960 | 0.240 | 1.600 | |
| RK-257+00-IC 3 - 8 | 08/24/05 | 47.0 | < 0.280 | < 0.280 | < 0.280 | < 0.280 | 1.100 | 0.610 Q | 0.290 Q | 2.000 | |
| RK-257+00-IC 8 - 10 | 08/24/05 | 72.4 | < 0.073 | < 0.073 | < 0.073 | < 0.073 | < 0.073 | 0.530 | 0.100 Q | 0.630 | |
| RK-259+00-IC 0 - 5 | 08/24/05 | 28.1 | < 0.094 | < 0.094 | < 0.094 | < 0.094 | 0.380 | 1.600 | 0.460 | 2.400 | |
| RK-259+00-IC 5 - 18 | 08/24/05 | 38.0 | < 0.070 | < 0.070 | < 0.070 | < 0.070 | < 0.070 | 0.070 Q | < 0.070 | 0.070 Q | |
| RK-263+50-IC 0 - 6 | 08/23/05 | 40.5 | < 0.066 | < 0.066 | < 0.066 | < 0.066 | < 0.066 | 0.880 | 0.200 Q | 1.100 | |
| RK-263+50-IC 6 - 8 | 08/23/05 | 48.4 | < 0.055 | < 0.055 | < 0.055 | < 0.055 | < 0.055 | < 0.055 | < 0.055 | < 0.055 | |
| RK-265+00-IC 0 - 7 | 08/23/05 | 52.1 | < 0.051 | < 0.051 | < 0.051 | < 0.051 | < 0.051 | 1.400 | 0.360 | 1.800 | |
| RK-265+00-IC 7 - 17 | 08/23/05 | 37.6 | < 0.071 | < 0.071 | < 0.071 | < 0.071 | < 0.071 | 0.084 Q | < 0.071 | 0.084 Q | |
| RL-266+40-IC 0 - 7 | 08/23/05 | 46.3 | < 0.057 | < 0.057 | < 0.057 | < 0.057 | < 0.057 | 0.620 | 0.150 Q | 0.770 | |
| RL-266+40-IC 7 - 9 | 08/23/05 | 69.2 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.076 Q | < 0.038 | 0.076 Q | |
| RL-268+70-IC 0 - 7 | 08/23/05 | 39.4 | < 0.067 | < 0.067 | < 0.067 | < 0.067 | < 0.067 | 0.640 | 0.150 Q | 0.790 | |
| RL-268+70-IC 7 - 14 | 08/23/05 | 47.3 | < 0.056 | < 0.056 | < 0.056 | < 0.056 | < 0.056 | < 0.056 | < 0.056 | < 0.056 | |
| RL-272+00-IC 0 - 2 | 08/23/05 | 63.8 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | 0.410 | 0.094 Q | 0.510 | |
| RL-272+00-IC 2 - 8 | 08/23/05 | 68.6 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | 0.240 | 0.055 Q | 0.300 | |
| RL-277+70-IC 0 - 8 | 08/23/05 | 58.8 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | 0.580 | 0.120 Q | 0.700 | |
| RL-277+70-IC 8 - 10 | 08/23/05 | 69.7 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.088 Q | < 0.038 | 0.088 Q | |
| RL-282+00-IC 0 - 10 | 08/23/05 | 64.3 | < 0.041 | < 0.041 | < 0.041 | < 0.041 | < 0.041 | 1.300 | 0.270 | 1.600 | |
| RM-287+50-IC 0 - 6 | 08/23/05 | na | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | 0.750 | 0.160 | 0.910 | |
| RM-287+50-IC 6 - 12 | 08/23/05 | 61.2 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | |
| RM-290+00-IC 0 - 7 | 08/23/05 | 57.7 | < 0.046 | < 0.046 | < 0.046 | < 0.046 | < 0.046 | 0.650 | 0.140 Q | 0.790 | |
| RM-293+30-IC 0 - 8 | 08/23/05 | 44.8 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | < 0.059 | 0.900 | 0.190 Q | 1.100 | |
| RM-293+30-IC 8 - 11 | 08/23/05 | 78.9 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | |
| RM-295+40-IC 0 - 7 | 08/23/05 | 58.4 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | 1.200 | 0.250 | 1.500 | |
| RM-295+40-IC 7 - 12 | 08/23/05 | 56.1 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | |
| RM-298+50-IC 0 - 11 | 08/23/05 | 50.3 | < 0.053 | < 0.053 | < 0.053 | < 0.053 | < 0.053 | 0.380 | 0.088 Q | 0.470 | |
| RN-304+50-IC 0 - 7 | 08/23/05 | 38.3 | < 0.069 | < 0.069 | < 0.069 | < 0.069 | < 0.069 | 1.100 | 0.310 | 1.400 | |
| RN-304+50-IC 7 - 15 | 08/23/05 | 49.0 | < 0.054 | < 0.054 | < 0.054 | < 0.054 | < 0.054 | 0.076 Q | < 0.054 | 0.076 Q | |
| RN-307+60-IC 0 - 10 | 08/23/05 | 42.1 | < 0.063 | < 0.063 | < 0.063 | < 0.063 | < 0.063 | 1.300 | 0.340 | 1.600 | |
| RN-311+60-IC 0 - 8 | 08/23/05 | 56.4 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | < 0.047 | 0.800 | 0.180 | 0.980 | |
| RN-311+60-IC 8 - 10 | 08/23/05 | 77.9 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | 0.060 Q | < 0.034 | 0.060 Q | |
| RN-314+00-IC 0 - 11 | 08/23/05 | 52.4 | < 0.051 | < 0.051 | < 0.051 | < 0.051 | < 0.051 | 1.500 | 0.260 | 1.800 | |
| RN-317+00-IC 0 - 8 | 08/23/05 | 28.8 | < 0.092 | < 0.092 | < 0.092 | < 0.092 | < 0.092 | 1.200 | 0.300 Q | 1.500 | |
| RO-319+60-IC 0 - 9 | 08/23/05 | 32.9 | < 0.081 | < 0.081 | < 0.081 | < 0.081 | < 0.081 | 1.700 | 0.450 | 2.100 | |
| RO-319+60-IC 9 - 12 | 08/23/05 | 74.7 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | 0.075 Q | < 0.036 | 0.075 Q | |
| RO-323+20-IC 0 - 6 | 08/23/05 | 25.7 | < 0.100 | < 0.100 | < 0.100 | < 0.100 | < 0.100 | 2.500 | 0.570 | 3.100 | |
| RO-323+20-IC 6 - 9 | 08/23/05 | 60.9 | < 0.044 | < 0.044 | < 0.044 | < 0.044 | < 0.044 | 0.210 | 0.047 Q | 0.260 | |
| RO-326+00-IC 0 - 14 | 08/23/05 | 45.8 | < 0.058 | < 0.058 | < 0.058 | < 0.058 | < 0.058 | 0.260 | < 0.058 | 0.260 | |
| RO-327+70-IC 0 - 6 | 08/23/05 | 27.8 | < 0.095 | < 0.095 | < 0.095 | < 0.095 | < 0.095 | 1.200 | 0.320 Q | 1.500 | |

**Table 5. Overbank Analytical Results Summary
HARP OU2/L & OU3**

| Sample Location and Depth (Inches) | Sample Date | Percent Solids | PCB Aroclors (mg/kg) | | | | | | | Total PCBs (mg/kg) |
|------------------------------------|-------------|----------------|----------------------|---------|---------|---------|---------|---------|---------|--------------------|
| | | | 1016 | 1221 | 1232 | 1242 | 1248 | 1254 | 1260 | |
| RK-258+00-W60 0 - 6 | 09/15/05 | 43.4 | < 0.061 | < 0.061 | < 0.061 | < 0.061 | < 0.061 | 0.130 Q | < 0.061 | 0.130 Q |
| RG-260+30-S50 0 - 6 | 09/12/05 | 77.6 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 |
| RK-261+10-W10 0 - 6 | 09/15/05 | 37.5 | < 0.071 | < 0.071 | < 0.071 | < 0.071 | < 0.071 | 0.620 | 0.250 | 0.870 |
| RK-261+10-W25 0 - 6 | 09/15/05 | 32.1 | < 0.083 | < 0.083 | < 0.083 | < 0.083 | < 0.083 | 0.087 Q | < 0.083 | 0.087 Q |
| RK-261+10-W50 0 - 6 | 09/15/05 | 77.0 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | 0.064 Q | < 0.034 | 0.064 Q |
| RK-263+80-S10 0 - 6 | 09/15/05 | 59.3 | < 0.900 | < 0.900 | < 0.900 | < 0.900 | < 0.900 | 10.000 | 3.900 | 14.000 |
| RK-263+80-S10 6 - 12 | 09/15/05 | 49.6 | < 2.100 | < 2.100 | < 2.100 | < 2.100 | < 2.100 | 25.000 | 5.800 Q | 31.000 |
| RK-263+80-S10 12 - 24 | 09/15/05 | 45.2 | < 2.900 | < 2.900 | < 2.900 | < 2.900 | < 2.900 | 29.000 | 6.700 Q | 36.000 |
| RK-263+80-S10 24 - 28 | 09/15/05 | 75.0 | < 1.800 | < 1.800 | < 1.800 | < 1.800 | < 1.800 | 14.000 | 2.700 Q | 16.000 |
| RK-263+80-S30 0 - 6 | 09/15/05 | 58.2 | < 0.091 | < 0.091 | < 0.091 | < 0.091 | < 0.091 | 1.500 | 0.500 | 2.000 |
| RK-263+80-S30 6 - 12 | 09/15/05 | 61.5 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | 0.550 | 0.140 Q | 0.690 |
| RK-265+00-E10 0 - 6 | 09/15/05 | 51.3 | < 1.000 | < 1.000 | < 1.000 | < 1.000 | < 1.000 | 13.000 | 3.600 | 16.000 |
| RK-265+00-E10 6 - 12 | 09/15/05 | 48.5 | < 2.700 | < 2.700 | < 2.700 | < 2.700 | < 2.700 | 32.000 | 7.700 Q | 40.000 |
| RK-265+00-E10 12 - 24 | 09/15/05 | 50.2 | < 0.053 | < 0.053 | < 0.053 | < 0.053 | < 0.053 | 0.370 | 0.095 Q | 0.460 |
| RK-265+00-E30 0 - 6 | 09/15/05 | 65.9 | < 0.280 | < 0.280 | < 0.280 | < 0.280 | < 0.280 | 3.800 | 1.300 | 5.100 |
| RK-265+00-E30 6 - 12 | 09/15/05 | 73.0 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | 0.120 Q | < 0.036 | 0.120 Q |
| RK-265+00-E50 0 - 6 | 09/30/05 | 64.5 | < 0.082 | < 0.082 | < 0.082 | < 0.082 | < 0.082 | 0.820 | 0.200 Q | 1.000 |
| RK-265+00-W10 0 - 6 | 09/15/05 | 67.3 | < 0.790 | < 0.790 | < 0.790 | < 0.790 | < 0.790 | 13.000 | 3.300 | 16.000 |
| RK-265+00-W10 6 - 12 | 09/15/05 | 61.0 | < 0.220 | < 0.220 | < 0.220 | < 0.220 | < 0.220 | 2.300 | 0.510 Q | 2.800 |
| RK-265+00-W10 12 - 21 | 09/15/05 | 52.7 | < 0.250 | < 0.250 | < 0.250 | < 0.250 | < 0.250 | 2.700 | 0.610 Q | 3.300 |
| RK-265+00-W30 0 - 6 | 09/15/05 | 58.9 | < 0.270 | < 0.270 | < 0.270 | < 0.270 | < 0.270 | 3.500 | 1.000 | 4.600 |
| RK-265+00-W30 6 - 12 | 09/15/05 | 58.9 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | 0.150 Q | < 0.045 | 0.150 Q |
| RK-265+00-W50 0 - 6 | 09/30/05 | 42.1 | < 0.063 | < 0.063 | < 0.063 | < 0.063 | < 0.063 | 0.220 | < 0.063 | 0.220 |
| RL-267+00-W100 0 - 6 | 09/15/05 | 55.1 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | 3.000 | 1.100 | 4.100 |
| RL-267+00-W100 6 - 12 | 09/15/05 | 68.5 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 |
| RL-267+40-E10 0 - 6 | 09/30/05 | 46.4 | < 2.900 | < 2.900 | < 2.900 | < 2.900 | < 2.900 | 17.000 | 3.900 Q | 21.000 |
| RL-267+40-E10 6 - 12 | 09/30/05 | 65.0 | < 0.410 | < 0.410 | < 0.410 | < 0.410 | < 0.410 | 4.400 B | 1.000 Q | 5.500 |
| RL-267+40-E10 12 - 18 | 09/30/05 | 69.0 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.220 B | 0.056 Q | 0.280 |
| RL-267+40-E30 0 - 6 | 09/30/05 | 52.9 | < 0.050 | < 0.050 | < 0.050 | < 0.050 | < 0.050 | 0.069 Q | < 0.050 | 0.069 Q |
| RL-268+70-E10 0 - 6 | 09/15/05 | 62.8 | < 2.100 | < 2.100 | < 2.100 | < 2.100 | < 2.100 | 30.000 | 6.800 Q | 37.000 |
| RL-268+70-E10 6 - 12 | 09/15/05 | 60.3 | < 0.880 | < 0.880 | < 0.880 | < 0.880 | < 0.880 | 14.000 | 3.200 | 17.000 |
| RL-268+70-E10 12 - 27 | 09/15/05 | 68.8 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | 1.500 | 0.360 Q | 1.800 |
| RL-268+70-E30 0 - 6 | 09/15/05 | 72.3 | < 0.550 | < 0.550 | < 0.550 | < 0.550 | < 0.550 | 7.200 | 1.900 | 9.100 |
| RL-268+70-E30 6 - 12 | 09/15/05 | 69.2 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.510 | 0.150 | 0.670 |
| RL-268+70-E60 0 - 6 | 09/30/05 | 60.2 | < 0.130 | < 0.130 | < 0.130 | < 0.130 | < 0.130 | 1.200 | 0.240 Q | 1.500 |
| RL-268+70-W10 0 - 6 | 09/15/05 | 59.2 | < 0.310 | < 0.310 | < 0.310 | < 0.310 | < 0.310 | 4.400 | 1.500 | 5.900 |
| RL-268+70-W10 6 - 12 | 09/15/05 | 61.7 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | 0.071 Q | < 0.043 | 0.071 Q |
| RL-268+70-W30 0 - 6 | 10/03/05 | 52.2 | < 0.100 | < 0.100 | < 0.100 | < 0.100 | < 0.100 | 0.960 | 0.280 Q | 1.200 |
| RL-270+00-W10 0 - 6 | 10/03/05 | 67.5 | < 0.390 | < 0.390 | < 0.390 | < 0.390 | < 0.390 | 2.800 | 0.760 Q | 3.600 |
| RL-270+00-W80 0 - 6 | 10/03/05 | 62.7 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | 0.089 Q | < 0.042 | 0.089 Q |
| RL-272+00-E100 0 - 6 | 09/15/05 | 77.4 | < 0.140 | < 0.140 | < 0.140 | < 0.140 | < 0.140 | 1.800 | 0.630 | 2.400 |
| RL-272+00-E100 6 - 12 | 09/15/05 | 81.0 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | 0.095 Q | 0.035 Q | 0.130 |

**Table 5. Overbank Analytical Results Summary
HARP OU2/L & OU3**

| Sample Location and Depth (Inches) | Sample Date | Percent Solids | PCB Aroclors (mg/kg) | | | | | | | | Total PCBs (mg/kg) |
|------------------------------------|-------------|----------------|----------------------|---------|---------|---------|---------|---------|---------|---------|--------------------|
| | | | 1016 | 1221 | 1232 | 1242 | 1248 | 1254 | 1260 | | |
| RL-272+00-E20 0 - 6 | 09/15/05 | 78.4 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | 0.200 | 0.230 | 0.430 | |
| RL-272+00-W10 0 - 6 | 09/15/05 | 71.3 | < 0.560 | < 0.560 | < 0.560 | < 0.560 | < 0.560 | 7.100 | 2.100 | 9.200 | |
| RL-272+00-W10 6 - 12 | 09/15/05 | 69.9 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.560 | 0.150 | 0.720 | |
| RL-272+00-W40 0 - 6 | 10/03/05 | 61.8 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | < 0.043 | 0.280 | 0.094 Q | 0.370 | |
| RL-274+40-S10 0 - 6 | 09/16/05 | 69.4 | < 0.110 | < 0.110 | < 0.110 | < 0.110 | < 0.110 | 1.700 | 0.340 Q | 2.000 | |
| RL-274+40-S30 0 - 6 | 09/16/05 | 74.4 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | 0.052 Q | < 0.036 | 0.052 Q | |
| RL-275+80-E10 0 - 6 | 09/15/05 | 63.4 | < 0.630 | < 0.630 | < 0.630 | < 0.630 | < 0.630 | 6.100 | 2.200 | 8.300 | |
| RL-275+80-E10 6 - 12 | 09/15/05 | 57.4 | < 1.900 | < 1.900 | < 1.900 | < 1.900 | < 1.900 | 19.000 | 5.500 Q | 25.000 | |
| RL-275+80-E10 12 - 30 | 09/15/05 | 73.7 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | |
| RL-275+80-E40 0 - 6 | 09/30/05 | 63.3 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | < 0.042 | 0.260 | 0.053 Q | 0.310 | |
| RL-277+70-E20 0 - 6 | 09/15/05 | 65.6 | < 0.200 | < 0.200 | < 0.200 | < 0.200 | < 0.200 | 2.700 | 0.700 | 3.400 | |
| RL-277+70-E20 6 - 12 | 09/15/05 | 59.2 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | < 0.045 | 0.260 | 0.086 Q | 0.350 | |
| RL-277+70-W10 0 - 6 | 09/16/05 | 55.0 | < 0.960 | < 0.960 | < 0.960 | < 0.960 | < 0.960 | 9.000 | 2.400 Q | 11.000 | |
| RL-277+70-W10 6 - 12 | 09/16/05 | 43.9 | < 2.400 | < 2.400 | < 2.400 | < 2.400 | < 2.400 | 22.000 | 6.400 Q | 29.000 | |
| RL-277+70-W10 12 - 24 | 09/16/05 | 41.9 | < 0.320 | < 0.320 | < 0.320 | < 0.320 | < 0.320 | 2.400 | 0.680 Q | 3.100 | |
| RL-277+70-W40 0 - 6 | 09/16/05 | 73.6 | < 0.180 | < 0.180 | < 0.180 | < 0.180 | < 0.180 | 2.600 | 0.590 Q | 3.200 | |
| RL-278+00-W100 0 - 6 | 09/16/05 | 73.7 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | < 0.036 | 0.160 | 0.036 Q | 0.190 | |
| RL-279+50-E100 0 - 6 | 09/15/05 | 58.2 | < 0.091 | < 0.091 | < 0.091 | < 0.091 | < 0.091 | 1.500 | 0.440 | 1.900 | |
| RL-280+10-E10 0 - 6 | 09/16/05 | 69.0 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | 1.700 | 0.360 Q | 2.000 | |
| RL-280+10-E30 0 - 6 | 09/16/05 | 70.1 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | < 0.038 | 0.280 | 0.055 Q | 0.330 | |
| RL-280+10-W15 0 - 6 | 09/16/05 | 70.0 | < 1.100 | < 1.100 | < 1.100 | < 1.100 | < 1.100 | 12.000 | 2.900 Q | 15.000 | |
| RL-280+10-W15 6 - 12 | 09/16/05 | 67.6 | < 0.079 | < 0.079 | < 0.079 | < 0.079 | < 0.079 | 0.980 | 0.210 Q | 1.200 | |
| RL-280+10-W30 0 - 6 | 09/16/05 | 73.8 | < 0.180 | < 0.180 | < 0.180 | < 0.180 | < 0.180 | 2.300 | 0.530 Q | 2.800 | |
| RL-280+10-W5 0 - 6 | 09/16/05 | 50.0 | < 0.800 | < 0.800 | < 0.800 | < 0.800 | < 0.800 | 7.000 | 1.900 Q | 9.000 | |
| RL-280+10-W5 6 - 12 | 09/16/05 | 43.1 | < 0.310 | < 0.310 | < 0.310 | < 0.310 | < 0.310 | 5.900 | 1.600 | 7.500 | |
| RL-280+10-W5 12 - 18 | 09/16/05 | 64.9 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | < 0.120 | 1.500 | 0.440 | 1.900 | |
| RL-281+80-S15 0 - 6 | 09/16/05 | 63.2 | < 1.700 | < 1.700 | < 1.700 | < 1.700 | < 1.700 | 21.000 | 4.100 Q | 25.000 | |
| RL-281+80-S15 6 - 12 | 09/16/05 | 63.7 | < 0.083 | < 0.083 | < 0.083 | < 0.083 | < 0.083 | 1.200 | 0.240 Q | 1.400 | |
| RL-281+80-S40 0 - 6 | 09/16/05 | 70.5 | < 0.110 | < 0.110 | < 0.110 | < 0.110 | < 0.110 | 1.600 | 0.330 Q | 1.900 | |
| RL-281+90-S5 0 - 6 | 09/16/05 | 62.8 | < 0.850 | < 0.850 | < 0.850 | < 0.850 | < 0.850 | 8.100 | 2.100 Q | 10.000 | |
| RL-281+90-S5 6 - 12 | 09/16/05 | 58.0 | < 1.400 | < 1.400 | < 1.400 | < 1.400 | < 1.400 | 14.000 | 3.100 Q | 17.000 | |
| RL-281+90-S5 12 - 18 | 09/16/05 | 57.0 | < 1.900 | < 1.900 | < 1.900 | < 1.900 | < 1.900 | 20.000 | 4.800 Q | 25.000 | |
| RL-282+50-N20 0 - 6 | 09/16/05 | 66.8 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | 3.400 | 0.710 Q | 4.100 | |
| RL-282+50-N40 0 - 6 | 10/03/05 | 72.7 | < 0.037 | < 0.037 | < 0.037 | < 0.037 | < 0.037 | 0.065 Q | < 0.037 | 0.065 Q | |
| RL-282+50-S10 0 - 6 | 10/03/05 | 70.1 | < 0.380 | < 0.380 | < 0.380 | < 0.380 | < 0.380 | 4.800 | 1.200 Q | 6.000 | |
| RL-282+50-S10 6 - 12 | 10/03/05 | 78.0 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | < 0.034 | 0.080 Q | 0.040 Q | 0.120 | |
| RL-282+50-S30 0 - 6 | 11/14/05 | 68.0 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | < 0.039 | 0.088 Q | < 0.039 | 0.088 Q | |
| RL-282+50-S30 6 - 12 | 11/14/05 | 79.8 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | |
| RL-282+50-S30 12 - 24 | 11/14/05 | 81.5 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | < 0.033 | |
| RM-285+50-E30 0 - 6 | 09/16/05 | 71.0 | < 0.260 | < 0.260 | < 0.260 | < 0.260 | < 0.260 | 3.500 | 0.590 Q | 4.100 | |
| RM-285+50-E5 0 - 6 | 09/16/05 | 49.4 | < 0.810 | < 0.810 | < 0.810 | < 0.810 | < 0.810 | 9.000 | 2.300 Q | 11.000 | |
| RM-285+50-E5 6 - 12 | 09/16/05 | 55.3 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | < 0.240 | 3.000 | 0.770 Q | 3.800 | |

**Table 6. Historic Sediment Analytical Results
HARP OU2/L & OU3**

| Location | Total PCBs (mg/kg) |
|-----------------|--------------------|
| RE-122+90-IC-RS | 3.300 |
| RE-124+00-IC-RS | 2.100 |
| RE-126+60-IC | 2.100 |
| RF-131+50-OXBOW | 6.600 |
| RF-147+50-IC | 3.400 |
| RF-150+00-IC | 7.700 |
| RF-ST4-IC | 2.500 |
| RF-156+20-IC | 5.300 |
| RG-172+50-IC | 5.200 |
| RG-180+10-IC | 2.100 |
| RG-183+00-IC-RS | 7.000 |
| RG-191+50-IC-RS | 2.000 |
| RG-198+00-IC-RS | 2.000 |
| RG-202+50-IC-RS | 3.900 |
| RG-205+00-IC-RS | 5.800 |
| RI-220+00-IC | 9.700 |
| RI-225+00-IC | 6.500 |
| RI-229+00-IC | 8.900 |
| RJ-233+00-IC | 20.000 |
| RJ-238+60-IC | 0.120 |
| RJ-245+00-IC-RS | 1.600 |
| RK-254+50-IC-RS | 8.000 |
| RK-261+00-IC-RS | 0.750 |
| RK-265+50-IC-RS | 5.600 |
| RL-270+00-IC-RS | 0.070 |
| RL-275+80-IC-RS | 0.050 |
| RL-279+00-IC-RS | 1.100 |
| RM-285+00-IC-RS | 0.090 |
| RM-291+00-IC-RS | 4.100 |
| RM-296+90-IC-RS | 2.500 |
| RM-302+70-IC-RS | 1.500 |
| RN-308+80-IC-RS | 3.800 |
| RN-314+90-IC-RS | 11.000 |
| RO-320+80-IC-RS | 1.300 |
| RO-328+20-IC-RS | 8.000 |
| RO-330+20-IC-RS | 5.300 |
| RP-331+90-IC-RS | 13.000 |
| RP-337+90-IC-RS | 4.600 |

Notes:

- 1) Historic sampling data collected by Earth Tech in 2003.

**Table 9. Sample Replicate List and Results
HARP OU2/L and OU3**

| Lab Sample Number | Field ID | Total PCBs (mg/kg) | Collection Date | Matrix | Relative Percentage Difference ^A |
|---|--------------------|--------------------|-----------------|----------|---|
| 863052-004 | RP-331+70-IC 0-12 | 1.2 | 08/22/05 | SEDIMENT | 58% |
| 863052-007 | RP-331+70-IC 0-12R | 0.66 | 08/22/05 | SEDIMENT | |
| 863052-025 | RL-282+00-IC 0-10 | 1.6 | 08/23/05 | SEDIMENT | 69% |
| 863052-026 | RL-282+00-IC 0-10R | 3.3 | 08/23/05 | SEDIMENT | |
| 863089-011 | RJ-237+00-IC 0-10 | 3.3 | 08/24/05 | SEDIMENT | 3% |
| 863089-012 | RJ-237+00-IC 0-10R | 3.4 | 08/24/05 | SEDIMENT | |
| 863089-021 | RG-205+90-IC 0-10 | 2.3 | 08/24/05 | SEDIMENT | 36% |
| 863089-022 | RG-205+90-IC 0-10R | 3.3 | 08/24/05 | SEDIMENT | |
| 863229-016 | RE-125+90-N10 0-6 | 3.6 | 08/29/05 | SOIL | 3% |
| 863229-015 | RE-125+90-N10 0-6R | 3.7 | 08/29/05 | SOIL | |
| 863273-009 | RF-137+80-W10 0-6 | 29 | 08/30/05 | SOIL | 11% |
| 863273-010 | RF-137+80-W10 0-6R | 26 | 08/30/05 | SOIL | |
| 863335-002 | RF-137+80-W40 0-6 | 20 | 08/30/05 | SOIL | 58% |
| 863335-004 | RF-137+80-W40 0-6R | 11 | 08/30/05 | SOIL | |
| 863335-011 | RF-140+50-E50 0-6 | 32 | 08/31/05 | SOIL | 44% |
| 863335-013 | RF-140+50-E50 0-6R | 50 | 08/31/05 | SOIL | |
| 863384-016 | RF-151+00-E30 0-6 | 30 | 09/01/05 | SOIL | NA |
| The laboratory did not receive sample RF-REP1-050901 (although it was listed on the COC). | | | | | |
| 863449-005 | RF-170+00-S70 0-6 | 38 | 09/02/05 | SOIL | 53% |
| 863449-004 | RF-REP2-050902 | 22 | 09/02/05 | SOIL | |
| 863503-002 | RF-164+80-W170 0-6 | 12 | 09/06/05 | SOIL | 8% |
| 863503-001 | RF-REP3-050906 | 13 | 09/06/05 | SOIL | |
| 863551-004 | RG-173+10-W60 0-6 | 5.3 | 09/07/05 | SOIL | 8% |
| 863551-001 | RG-REP4-050907 | 4.9 | 09/07/05 | SOIL | |
| 863606-005 | RG-183+20-W10 0-6 | 5.5 | 09/08/05 | SOIL | 31% |
| 863606-001 | RG-REP5-050908 | 7.5 | 09/08/05 | SOIL | |
| 863663-005 | RG-191+20-E40 0-6 | 2.1 | 09/08/05 | SOIL | 15% |
| 863663-001 | RG-REP6-050909 | 1.8 | 09/09/05 | SOIL | |
| 863719-009 | RH-209+50-W50 0-6 | <0.034 | 09/12/05 | SOIL | 3% |
| 863719-016 | RH-REP7-050912 | <0.033 | 09/12/05 | SOIL | |
| 863719-022 | RI-218+50-N10 0-6 | 17 | 09/12/05 | SOIL | 34% |
| 863719-027 | RI-REP7-050912 | 12 | 09/12/05 | SOIL | |
| 863790-005 | RI-221+60-S25 0-6 | 1.6 | 09/13/05 | SOIL | 36% |
| 863790-002 | RI-REP8-050913 | 2.3 | 09/13/05 | SOIL | |
| 863790-027 | RJ-233+00-S10 0-6 | 40 | 09/13/05 | SOIL | 0% |
| 863790-031 | RJ-REP8A-050913 | 40 | 09/13/05 | SOIL | |
| 863888-005 | RJ-236+50-N30 0-6 | 25 | 09/14/05 | SOIL | 44% |
| 863888-004 | RJ-REP9-050914 | 16 | 09/14/05 | SOIL | |
| 863951-003 | RK-257+00-E10 0-6 | 18 | 09/15/05 | SOIL | 6% |
| 863951-002 | RK-REP10-050915 | 17 | 09/15/05 | SOIL | |
| 864088-012 | RL-281+90-S5 0-6 | 10 | 09/16/05 | SOIL | 10% |
| 864088-020 | RL-REP11-050916 | 11 | 09/16/05 | SOIL | |
| 864071-008 | RM-289+00-W10 0-6 | 20 | 09/19/05 | SOIL | 114% |
| 864071-002 | RM-REP12-050919 | 5.5 | 09/19/05 | SOIL | |

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-266+40-IC | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 8/23/2005 | | Date Drilling Completed 8/23/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 815.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 733,626 N, 2,469,526 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.6' ORGANIC SILT : OL, very dark gray (7.5YR 3/1), nonplastic, no dilatency, low toughness, moist to wet, very soft, [gyttja], trace stems/ fibers/ wood pieces; 5% shells/ sand; organic odor. | OL | | | | | | | | |
| | | | | 0.6 - 0.75' LEAN CLAY : CL, greenish gray (10Y 6/1), medium to high plasticity, no dilatency, low toughness, moist, very soft, 5% shells; trace sand. 0.75' End of Boring. | CL | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-267+00-W100 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Local Grid Location | |
| State Plane 733,680 N, 2,469,374 E S/C/N | | | Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of | | 1/4 of Section | T | N, R | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|---------|----------------|-----------------|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | | 0.5 | 0 - 1' SILT : ML, dark brown (7.5YR 3/2), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/ fibers; organic odor. | ML | | | | | | | | | |
| | | | | 1.0 | 1' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kavatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-267+40-E10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/30/2005 | | Date Drilling Completed 9/30/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 733,733 N, 2,469,490 E S/C/N | | | Lat ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of 1/4 of Section , T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|---------|--|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 1' LEAN CLAY : CL, very dark grayish brown (10YR 3/2), medium plasticity, no dilatency, medium toughness, moist, firm, 5% roots. | CL |  | | | | | | | | |
| | | | | 1.0 | 1 - 1.9' FAT CLAY : CH, very dark grayish brown (10YR 3/2), high plasticity, no dilatency, high toughness, wet, very soft. | CH |  | | | | | | | | |
| | | | | 1.5 | | | | | | | | | | | |
| | | | | | 1.9' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-267+40-E30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/30/2005 | | Date Drilling Completed 9/30/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 733,734 N, 2,469,499 E S/C/N | | | Lat ° ' " | | <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|------|----------------|-----------------|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | | 0.5 | 0 - 1' SILT : ML, black (10YR 2/1), nonplastic, slow dilatency, low toughness, moist to wet, soft, 1% roots. 0.5' low plasticity from 0.5' to 1.0'. | ML | | | | | | | | | |
| | | | | 1.0 | 1 - 2.2' LEAN CLAY : CL, very dark grayish brown (10YR 3/2), medium plasticity, no dilatency, medium toughness, moist, firm, 5% wood fragments. | CL | | | | | | | | | |
| | | | | 1.5 | | | | | | | | | | | |
| | | | | 2.0 | | | | | | | | | | | |
| | | | | | 2.2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|---|-----------------|--------------------------|--|---|---------------------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-268+70-E10 |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | Date Drilling Completed 9/15/2005 | Drilling Method hand auger |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.9 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 733,789 N, 2,469,390 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Local Grid Location Lat _____ Long _____ <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.5' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, moist, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML | | | | 0.5 | | | | | |
| | | | 1.0 | 0.5 - 2.25' ELASTIC SILT : MH, dark brown (7.5YR 3/2), medium plasticity, no dilatency, low toughness, moist, very soft, earthy odor. | MH | | | | | | | | | |
| | | | 1.5 | 1.5' black (2.5YR 2.5/1), trace shells/ sand/ wood fragments to 2.1'. | | | | | | | | | | |
| | | | 2.0 | 2.1' dark gray (7.5YR 4/1), 1 wood piece; lean clay to 2.25'. | | | | | | | | | | |
| | | | | 2.25' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-268+70-E30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.7 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 733,772 N, 2,469,376 E S/C/N | | | Lat ° ' " | | | |
| 1/4 of T N, R | | | Long ° ' " | | | |
| Facility ID | | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|--------------------------|--|---------|----------------|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 1.0 1.5 2.0 | 0 - 2' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML | | | | | | | | | |
| | | | | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|





Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-268+70-E60 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/30/2005 | | Date Drilling Completed 9/30/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 733,808 N, 2,469,413 E S/C/N | | | Lat ° ' " | | <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|---|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1.2' SILT : ML, very dark brown (10YR 2/2), low plasticity, rapid dilatency, low toughness, moist, soft, 5% roots. | ML |  |  | | | | | | |
| | | | 1.0 | | | | | | | | | | |
| | | | 1.5 | 1.25 - 2.5' FAT CLAY : CH, very dark brown (10YR 2/2), high plasticity, no dilatency, high toughness, moist, firm. | CH |  |  | | | | | | |
| | | | 2.0 | | | | | | | | | | |
| | | | 2.5 | 2.5' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-268+70-IC | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 8/23/2005 | | Date Drilling Completed 8/23/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 814.7 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 733,743 N, 2,469,406 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat ° ' " Long ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.6' ORGANIC SILT : OL, very dark gray (7.5YR 3/1), nonplastic, no dilatency, low toughness, moist to wet, very soft, [gyttja], 5% fine sand/ shells; trace fibers/ wood fragments; organic odor. | OL | | | | | | | | | |
| | | | 1.0 | 0.6 - 1.2' ORGANIC SILT to ELASTIC SILT : OL, very dark gray (7.5YR 3/1), low plasticity, no dilatency, low toughness, moist, very soft, trace fibers/ shells/ wood fragments; organic odor. | OL | | | | | | | | | |
| | | | | 1.2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006



Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|---|--|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-268+70-W10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.1 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 733,745 N, 2,469,347 E S/C/N | | | Lat _____ " _____ " | | | |
| 1/4 of _____ 1/4 of Section _____, T _____ N, R _____ | | | Long _____ " _____ " | | | |
| Facility ID _____ | | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | | | | | | |
| | | | 1.0 | 1 - 2' LEAN CLAY : CL, dark brown (7.5YR 3/2), medium plasticity, no dilatency, medium toughness, moist, very soft, trace fibers. | CL |  | | | 0.5 | | | | | |
| | | | 1.5 | | | | | | | | | | | |
| | | | 2.0 | 1.8' light brwon (7.5 YR 6/3). | | | | | | | | | | |
| | | | | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|---|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|---|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|--|-----------------|---|--|--|---|
| Facility/Project Name HARP OU2/L & OU3 | | License/Permit/Monitoring Number | | Boring Number RL-268+70-W30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | Date Drilling Started 10/3/2005 | | Date Drilling Completed 10/3/2005 | |
| Drilling Method hand auger | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Local Grid Location | |
| State Plane 733,731 N, 2,469,332 E S/C/N | | Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of <input type="text"/> 1/4 of Section <input type="text"/> T <input type="text"/> N, R <input type="text"/> | | County Calumet | | County Code 8 | Civil Town/City/ or Village Chilton |
| Facility ID | | | | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|--|---------|--|-----------------|-----|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | | 0.5 | 0 - 1' SILT : ML, very dark gray (10YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand; 10% clay clumps. | ML |  | | | | | | | | | |
| | | | | 1.0 | 1 - 2.5' LEAN CLAY : CL, very dark grayish brown (10YR 3/2), medium plasticity, no dilatency, medium toughness, moist, very soft, trace roots/fibers/medium sand. | CL |  | | 0.5 | | | | | | | |
| | | | | 1.5 | | | | | | | | | | | | |
| | | | | 2.0 | | | | | | | | | | | | |
| | | | | 2.25 | 2.25' brown (10YR 5/3), moist, very soft. | | | | 0.5 | | | | | | | |
| | | | | 2.5 | 2.5' End of Boring. | | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

SOIL BORING LOG INFORMATION




Form 4400-122

Rev. 7-98

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-270+00-W10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 10/3/2005 | | Date Drilling Completed 10/3/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 733,906 N, 2,469,358 E S/C/N | | | Lat <input type="checkbox"/> N <input type="checkbox"/> E Long <input type="checkbox"/> S <input type="checkbox"/> W | | | |
| 1/4 of Section , T N, R | | | Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 0.5' SILT : ML, very dark gray (10YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand; 10% clay clumps. | ML |  | | | | | | | | |
| | | | 1.0 | 0.5 - 1' ELASTIC SILT : MH, dark grayish brown (10YR 4/2), medium plasticity, no dilatency, low toughness, moist, very soft, trace roots/fibers. | MH |  | | | 0.5 | | | | | |
| | | | 1.5 | 1 - 2' LEAN CLAY : CL, very dark grayish brown (10YR 3/2), medium plasticity, no dilatency, medium toughness, moist, very soft, trace roots/fibers/medium sand. | CL |  | | | 0.5 | | | | | |
| | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|---|-----------------|--------------------------|---|---|---|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-270+00-W80 |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 10/3/2005 | Date Drilling Completed 10/3/2005 | Drilling Method hand auger |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 733,948 N, 2,469,325 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (10YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand; 10% clay clumps. | ML |  | | 0.5 | | | | | |
| | | | 1.0 | 1 - 2.25' LEAN CLAY : CL, dark gray (10YR 4/1), medium plasticity, no dilatency, medium toughness, moist, firm, trace medium well sorted sand. | CL |  | | 1.5 | | | | | |
| | | | 1.5 | 1.5' 10% medium sand laminations. | | | | | | | | | |
| | | | 2.0 | | | | | | | | | | |
| | | | | 2.25' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-272+00-E20 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.9 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,049 N, 2,469,432 E S/C/N | | | Lat ° ' " | | | |
| 1/4 of T N, R | | | Long ° ' " | | | |
| Facility ID | | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|------|--|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | 1.5 | | | | | |
| | | | 1.0 | 1 - 2' LEAN CLAY : CL, grayish brown (10YR 5/2), medium plasticity, no dilatency, medium toughness, dry to moist, soft, homogenous. | CL |  | | | | | | | | |
| | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-272+00-E100 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.3 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,049 N, 2,469,521 E S/C/N | | | Lat ° ' " | | <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of T N, R | | | Long ° ' " | | <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|--|------|--|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 1' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.1'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | | | | | | |
| | | | | 1.0 | 1 - 3' LEAN CLAY : CL, grayish brown (10YR 5/2), medium plasticity, no dilatency, medium toughness, dry, firm, trace roots/ fibers/ medium sand. | CL |  | | | 2 | | | | | |
| | | | | 1.5 | 1.5' very dark gray (7.5 YR 3/1). | | | | | | | | | | |
| | | | | 2.0 | | | | | | | | | | | |
| | | | | 2.5 | | | | | | | | | | | |
| | | | | 3.0 | 3' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.


| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|--|--------------------------|--|---|--|---|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-272+00-IC | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 8/23/2005 | | Date Drilling Completed 8/23/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | | DNR Well ID No. | | Common Well Name | | |
| | | | | Final Static Water Level Feet (NAVD) | | Surface Elevation 814.9 Feet (NAVD) |
| | | | | | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | | | | |
| State Plane 734,038 N, 2,469,413 E S/C/N | | | Lat _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of _____ | | | 1/4 of Section _____ , T _____ N, R _____ | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | | County Code 8 | | Civil Town/City/ or Village Chilton |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|---|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.2' ORGANIC SILT WITH SAND : (OL)s, poorly graded, fine grained sand, subrounded sand, greenish gray (10Y 6/1), nonplastic, rapid dilatency, low toughness, wet, very soft, [well sorted], 20% fine sand; trace fibers/ stems/ shells; organic odor. 0.2 - 0.7' LEAN CLAY : CL, pinkish gray (5YR 6/2), 5% greenish gray (5BG 6/1) mottling, medium plasticity, no dilatency, medium toughness, moist, very soft. 0.5' vertical organic silt with sand seam to 0.7'. 0.7' End of Boring. | (OL)s |  | | | 0.5 | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-272+00-W10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.9 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,029 N, 2,469,398 E S/C/N 1/4 of 1/4 of Section T N, R | | | Lat ° ' " Long ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|---------|----------------|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 1' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, dry to moist, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML | | | | | | | | | |
| | | | | 1.0 | 1 - 2' ELASTIC SILT : MH, gray (7.5YR 5/1), medium plasticity, no dilatency, low toughness, moist, very soft, trace fibers/ medium sand. | MH | | | | 0.5 | | | | | |
| | | | | 1.5 | | | | | | | | | | | |
| | | | | 2.0 | 1.9' gray lean clay to 2'. 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006



Template: WDNR SBL 1998 - Project: 1778 HARPOU2 3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-272+00-W40 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 10/3/2005 | | Date Drilling Completed 10/3/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | | Surface Elevation 0.0 Feet (NAVD) | |
| | | | | | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Local Grid Location | |
| State Plane 734,009 N, 2,469,375 E S/C/N | | | Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of <input type="text"/> 1/4 of Section <input type="text"/> , T <input type="text"/> N, R <input type="text"/> | | | | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (10YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand; 10% clay clumps. | ML |  | | | | | | | |
| | | | 1.0 | 1 - 2' LEAN CLAY : CL, dark gray (10YR 4/1), medium plasticity, no dilatency, medium toughness, moist, firm, trace medium well sorted sand. | CL |  | | | | | | | |
| | | | 1.5 | 1.5' 10% medium sand laminations. | | | | | | | | | |
| | | | 2.0 | 2' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006



Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|--|--------------------------|---|--|--|---|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-274+40-S10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | | DNR Well ID No. | | Common Well Name | | |
| | | | | Final Static Water Level Feet (NAVD) | | Surface Elevation 817.4 Feet (NAVD) |
| | | | | | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | | | | |
| State Plane 734,173 N, 2,469,242 E S/C/N | | | Lat ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of 1/4 of Section , T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W | |
| Facility ID | | County Calumet | | County Code 8 | | Civil Town/City/ or Village Chilton |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | | | | | |
| | | | 1.0 | 1 - 2.25' LEAN CLAY WITH SAND : (CL)s, poorly graded, medium grained sand, rounded sand, dark gray (7.5YR 4/1), medium plasticity, no dilatency, low toughness, moist, soft, [well sorted], 15% well sorted medium grained sand; trace shells/ fibers. | (CL)s |  | | 0.5 | | | | | |
| | | | 1.5 | | | | | | | | | | |
| | | | 2.0 | | | | | | | | | | |
| | | | | 2.2' lean clay color is 7.5YR 5/4 brown with no sand to 2.25'. 2.25' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|--|------------------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-274+40-S30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.5 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | | | | |
| State Plane 734,151 N, 2,469,232 E S/C/N | | | Lat ° ' " | | Local Grid Location | |
| 1/4 of 1/4 of Section , T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, dark brown (7.5YR 3/2), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | | | | | |
| | | | 1.0 | 1 - 1.5' LEAN CLAY : CL, gray (7.5YR 5/1), 5% very dark gray (7.5YR 3/1) mottling, medium plasticity, no dilatency, medium toughness, moist, soft, trace fibers/ roots/ medium sand. | CL |  | | 1 | | | | | |
| | | | 1.5 | 1.5' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|--|---|---|------------------------------------|
| Facility/Project Name HARPOU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-275+80-E10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 816.9 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,322 N, 2,469,300 E S/C/N | | | Lat ° ' " | | | |
| 1/4 of T N, R | | | Long ° ' " | | | |
| Facility ID | | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, root material to 0.2'; trace roots/ fibers; earthy odor. 0.5' 10% fibers/ shells; trace stems/ medium sand to 1'. | ML | | | | | | | | |
| | | | 1.0 | 1 - 2.5' LEAN CLAY : CL, brown (7.5YR 5/2), 10% gray (7.5YR 6/1) mottling, medium plasticity, no dilatency, medium toughness, moist, soft, trace fibers. | CL | | | | 2 | | | | |
| | | | 2.5 | 2.5' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-275+80-E40 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/30/2005 | | Date Drilling Completed 9/30/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,299 N, 2,469,319 E S/C/N | | | Lat ° ' " Long ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of 1/4 of Section , T N, R | | | | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|--------------------------|--|---------|--|-----------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 1.0 1.5 2.0 | 0 - 1.5' SILT : ML, very dark gray (10YR 3/1), low plasticity, no dilatency, low toughness, moist to wet, soft, 5% roots. | ML |  | | | | | | | |
| | | | | | 1.5 - 2.2' FAT CLAY : CH, brown (10YR 4/3), high plasticity, no dilatency, high toughness, moist, hard. | CH |  | | | | | | | |
| | | | | | 2.2' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-277+70-E20 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | | Date Drilling Completed 9/15/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.4 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,471 N, 2,469,350 E S/C/N | | | Lat <input type="checkbox"/> N <input type="checkbox"/> E | | | |
| 1/4 of <input type="checkbox"/> 1/4 of Section <input type="checkbox"/> , T <input type="checkbox"/> N, R <input type="checkbox"/> | | | Long <input type="checkbox"/> S <input type="checkbox"/> W | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, root material to 0.2'; trace roots/ fibers; earthy odor. | ML | | | | 0.5 | | | | | |
| | | | 1.0 | 1 - 2.3' ELASTIC SILT : MH, very dark gray (7.5YR 3/1), medium plasticity, no dilatency, low toughness, moist, very soft, trace fibers/ roots/ medium sand. | MH | | | | | | | | | |
| | | | 1.5 | | | | | | | | | | | |
| | | | 2.0 | | | | | | | | | | | |
| | | | | 2.3' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-277+70-IC | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 8/23/2005 | | Date Drilling Completed 8/23/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 814.5 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,441 N, 2,469,334 E S/C/N | | | Lat <input type="checkbox"/> N <input type="checkbox"/> E | | | |
| 1/4 of <input type="checkbox"/> 1/4 of Section <input type="checkbox"/> T <input type="checkbox"/> N, R <input type="checkbox"/> | | | Long <input type="checkbox"/> S <input type="checkbox"/> W | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.7' ORGANIC SILT : OL, very dark gray (7.5YR 3/1), nonplastic, no dilatency, low toughness, wet, very soft, [gyttja], trace fibers/ stems; organic odor. 0.25' 10% sand/ shells to 0.7'. | OL | | | | | | | | |
| | | | | 0.7 - 0.8' LEAN CLAY : CL, pinkish gray (5YR 6/2), 5% greenish gray (5BG 6/1) mottling, medium plasticity, no dilatency, medium toughness, moist, very soft, <1% fibers. 0.8' End of Boring. | CL | | | 0.5 | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006




Template: WDNR SBL 1998 - Project: 1778_HARPOU2 3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|--|-----------------|--|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | License/Permit/Monitoring Number | | Boring Number RL-277+70-W10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 816.8 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | State Plane 734,428 N, 2,469,330 E S/C/N | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of | | 1/4 of Section | | T N, R | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments | |
|--------------------|---------------------------------|-------------|---------------|--|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|--|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 0.5' SILT : ML, very dark gray (7.5YR 3/1), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | 0.5 | | | | | |
| | | | 1.0 | 0.5 - 2' ELASTIC SILT : MH, dark gray (7.5YR 4/1), medium plasticity, no dilatency, low toughness, moist, very soft, trace medium sand/ shells; 10% roots and fibers to 1'; organic odor. | MH |  | | | | | | | | |
| | | | 2.0 | 2 - 2.5' LEAN CLAY : CL, brown (7.5YR 5/3), 5% gray (7.5YR 5/1) mottling, medium plasticity, no dilatency, medium toughness, moist, firm, homogenous. | CL |  | | | 2.5 | | | | | |
| | | | 2.5 | 2.5' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|---------------------|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. | Tel: (262) 523-9000 |
| | 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Fax: (262) 523-9001 |

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2 3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-277+70-W40 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.1 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,397 N, 2,469,309 E S/C/N | | | Lat ° ' " | | | |
| 1/4 of T N, R | | | Long ° ' " | | | |
| Facility ID | | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), low plasticity, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML | | | | | | | | | |
| | | | 1.0 | 1 - 2' ELASTIC SILT : MH, dark gray (7.5YR 4/1), medium plasticity, no dilatency, low toughness, moist, very soft, trace roots/ fibers/ medium sand. | MH | | | 0.5 | | | | | | |
| | | | 1.5 | 1.5' 10% medium sand to 1.9'. | | | | | | | | | | |
| | | | 2.0 | 1.9' 1 poorly graded medium sand, rounded grains. | | | | | | | | | | |
| | | | | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.



| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-278+00-W100 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.5 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,418 N, 2,469,254 E S/C/N 1/4 of _____ 1/4 of Section _____, T _____ N, R _____ | | | Lat _____ Long _____ | | Local Grid Location Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|--|---------|--|-----------------|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | 4.5 | | | | | |
| | | | | 1.0 | 1 - 2' FAT CLAY : CH, dark gray (7.5YR 4/1), high plasticity, no dilatency, high toughness, dry, firm, trace roots/ fibers; crumbly texture. | CH |  | | | | | | | | |
| | | | | 1.5 | | | | | | | | | | | |
| | | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.



| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|--|-----------------|--------------------------|--|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-279+50-E100 |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/15/2005 | Date Drilling Completed 9/15/2005 | Drilling Method hand auger |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.3 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,620 N, 2,469,371 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Local Grid Location Lat ° ' " Long ° ' " Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), low plasticity, slow dilatency, low toughness, moist, very soft, root material to 0.2'; trace roots/ fibers; earthy odor. | ML |  | | | | | | | |
| | | | 1.0 | 1 - 2.75' LEAN CLAY : CL, light olive brown (2.5Y 5/3), 5% reddish yellow (7.5YR 6/6) mottling, medium plasticity, no dilatency, medium toughness, moist, soft, homogenous, trace fibers. 1.25' very dark gray (7.5 YR 3/1). | CL |  | | 1.5 | | | | | |
| | | | 2.0 | | | | | | | | | | |
| | | | 2.5 | | | | | | | | | | |
| | | | | 2.75' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kavatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-280+10-E10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.2 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,682 N, 2,469,221 E S/C/N | | | Lat <input type="checkbox"/> N <input type="checkbox"/> E | | | |
| 1/4 of T N, R | | | Long <input type="checkbox"/> S <input type="checkbox"/> W | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark gray (7.5YR 3/1), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | | | | | | |
| | | | 1.0 | 1 - 2.75' LEAN CLAY : CL, greenish gray (10Y 5/1), medium plasticity, no dilatency, medium toughness, moist, very soft, trace fibers. | CL |  | | 0.5 | | | | | | |
| | | | 2.0 | | | | | | | | | | | |
| | | | 2.5 | 2.25' light brown (7.5YR 6/3), 10% gray (7.5YR 6/1) mottling, mottled to 2.75'. | | | | | | | | | | |
| | | | | 2.75' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.



| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|--|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-280+10-E30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | | Surface Elevation 818.0 Feet (NAVD) | |
| | | | | | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Local Grid Location | | | |
| State Plane 734,697 N, 2,469,240 E S/C/N | | | Lat <input type="checkbox"/> N <input type="checkbox"/> E | | | |
| 1/4 of 1/4 of Section , T N, R | | | Long <input type="checkbox"/> S <input type="checkbox"/> W | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|--|---------|---|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 0.5' SILT : ML, very dark gray (7.5YR 3/1), nonplastic, rapid dilatency, low toughness, dry, very soft, root material to 0.2'; trace roots/ fibers/ medium sand; earthy odor. | ML |  | | | 1 | | | | | |
| | | | | 1.0 | 0.5 - 2.5' LEAN CLAY : CL, very dark gray (7.5YR 3/1), medium plasticity, no dilatency, medium toughness, dry to moist, soft, clay is dry to 1'; earthy odor. 1' grayish brown (2.5Y 5/2), moist, clay is grayish brown to 2'. | CL |  | | | | | | | | |
| | | | | 2.0 | 2' light brown (7.5YR 6/3), 10% gray (7.5YR 6/1) mottling, moist, mottled to 2.5'. | | | | | | | | | | |
| | | | | 2.5 | 2.5' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-280+10-W5 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 816.6 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Local Grid Location | |
| State Plane 734,661 N, 2,469,202 E S/C/N | | | Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of <input type="text"/> 1/4 of Section <input type="text"/> , T <input type="text"/> N, R <input type="text"/> | | | | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments | |
|--------------------|---------------------------------|-------------|---------------|---|---------|--|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|--|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 1.5' ELASTIC SILT : MH, very dark gray (7.5YR 3/1), medium plasticity, no dilatency, low toughness, moist, very soft, 5% roots/fibers; trace medium sand.. | MH |  | | | 0.5 | | | | | |
| | | | 1.5 | 1.5 - 2.25' LEAN CLAY : CL, gray (7.5YR 5/1), medium plasticity, no dilatency, medium toughness, moist, very soft. | CL |  | | | 1 | | | | | |
| | | | 2.0 | | | | | | | | | | | |
| | | | | 2.25' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006

Template: WDNr SBL 1998 - Project: 1778 HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-280+10-W15 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.2 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,650 N, 2,469,198 E S/C/N | | | Lat ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|--|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 1' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | 0.5 | | | | | |
| | | | 1.0 | 1 - 2.25' ELASTIC SILT : MH, very dark brown (7.5YR 3/2), low plasticity, no dilatency, low toughness, moist, very soft, @2-2.25' 10% medium brown sand. | MH | | | | | | | | | |
| | | | 1.5 | | | | | | | | | | | |
| | | | 2.0 | | | | | | | | | | | |
| | | | | 2.25' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-280+10-W30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 818.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,632 N, 2,469,188 E S/C/N 1/4 of 1/4 of Section T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|-------------------|--|---------|----------------|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 1.0 1.5 | 0 - 1.75' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | | | | | | |
| | | | | | 1.75' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-281+80-S15 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.2 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | | | | |
| State Plane 734,694 N, 2,469,082 E S/C/N | | | Lat ° ' " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of T N, R | | | Long ° ' " | | Feet <input type="checkbox"/> S <input type="checkbox"/> W | |

| | | | |
|-------------|--------------------------|-------------------------|---|
| Facility ID | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton |
|-------------|--------------------------|-------------------------|---|

| Sample | | | | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|--|---------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | Depth In Feet | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 0.5' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | | | | | | |
| | | | 1.0 | 0.5 - 2' ELASTIC SILT : MH, very dark brown (7.5YR 3/2), low plasticity, no dilatency, low toughness, moist, very soft, trace root fibers; fine granular soil texture.. | MH | | | | | | | | | |
| | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARPOU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-281+80-S40 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.7 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,673 N, 2,469,110 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|--|---------|----------------|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 1' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | | | | | | |
| | | | | 1.0 | 1 - 2' ELASTIC SILT : MH, very dark brown (7.5YR 3/2), low plasticity, no dilatency, low toughness, moist, very soft, trace root fibers; fine granular soil texture.. | MH | | | | | | | | | |
| | | | | 1.5 | | | | | | | | | | | |
| | | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006

Template: WDNR SBL 1998 - Project: 1778 HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|--|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-281+90-S5 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | | Date Drilling Completed 9/16/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.3 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Lat <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | Local Grid Location | |
| State Plane 734,705 N, 2,469,068 E S/C/N | | | Long <input type="text"/> ° <input type="text"/> ' <input type="text"/> " | | <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| 1/4 of <input type="text"/> 1/4 of Section <input type="text"/> T <input type="text"/> N, R <input type="text"/> | | | | | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|--|---|---------|----------------|-----------------|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | 0.5 | 0 - 0.5' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | 0.5 | | | | | | |
| | | | 1.0 | 0.5 - 1.5' ELASTIC SILT : MH, very dark brown (7.5YR 3/2), low plasticity, no dilatency, low toughness, moist, very soft, trace root fibers; gray lean clay @ 1.4-1.5'. | MH | | | | | | | | | | |
| | | | 1.5 | 1.5' End of Boring. | | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-282+00-IC | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 8/23/2005 | | Date Drilling Completed 8/23/2005 | |
| | | | | | Drilling Method hand auger | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 815.0 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,705 N, 2,469,149 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample Number and Type | Length Att. & Recovered (in) | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | USCS | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|------------------------------|---------------------------------|-------------|---------------|--|-------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| | | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0.5 | 0 - 0.8' ORGANIC SILT WITH SAND : (OL)s, poorly graded, fine grained sand, rounded sand, greenish gray (10Y 5/1), nonplastic, rapid dilatency, low toughness, moist to wet, very soft, [well sorted], 30% fine sand; trace fibers/ shells/ stems; organic odor. | (OL)s | | | | | | | | |
| | | | | 0.75' Sand content increases at base; however, no sand recovered at 0.8'. 0.8' End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kavatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006 Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | |
|--|-----------------|--------------------------|--|---|---------------------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-282+50-N20 |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 9/16/2005 | Date Drilling Completed 9/16/2005 | Drilling Method hand auger |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 817.9 Feet (NAVD) | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,705 N, 2,469,001 E S/C/N 1/4 of 1/4 of Section 1 , T N , R R | | | Local Grid Location Lat ° ' " Long ° ' " Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W | | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | |

| Sample | | | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments | |
|--------------------|---------------------------------|-------------|---------------|---|---------|----------------|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|--|
| Number and Type | Length Att. & Recovered (in) | Blow Counts | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | 0.5 | 0 - 0.5' SILT : ML, very dark brown (7.5YR 3/2), medium plasticity, rapid dilatency, low toughness, dry, very soft, 0-0.2 root mat; trace roots/fibers/medium sand. | ML | | | | 0.5 | | | | | |
| | | | 1.0 | 0.5 - 1' ELASTIC SILT : MH, very dark brown (7.5YR 3/2), 5% yellowish red (5YR 4/6) mottling, low plasticity, no dilatency, low toughness, dry, very soft, trace root fibers; fine granular soil texture.. | MH | | | | 0.5 | | | | | |
| | | | 1.5 | 1 - 2' SILT : ML, black (7.5YR 2.5/1), low plasticity, slow dilatency, low toughness, moist, very soft, trace fibers and medium sand; @1.8-1.85 laminated black and grey medium sand; @1.95-2 brown lean clay. | ML | | | | | | | | | |
| | | | 2.0 | 2' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kouatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006



Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|--|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-282+50-N40 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 10/3/2005 | | Date Drilling Completed 10/3/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | | Surface Elevation 0.0 Feet (NAVD) | |
| | | | | | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> | | | Lat _____" | | Local Grid Location | |
| State Plane 734,725 N, 2,469,004 E S/C/N | | | Long _____" | | <input type="checkbox"/> N <input type="checkbox"/> E | |
| 1/4 of 1/4 of Section , T N, R | | | | | Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|---------|--|-----------------|--|---------------------|-----------------|---------------------|-------|--|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | | |
| | | | | 0.5 | 0 - 1' SILT : ML, very dark grayish brown (10YR 3/2), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand. | ML |  | | | | | | | | | |
| | | | | 1.0 | 1 - 1.5' FAT CLAY : CH, yellowish brown (10YR 5/4), high plasticity, no dilatency, high toughness, dry to moist, firm to hard, trace roots/fibers. | CH |  | | | 3 | | | | | | |
| | | | | 1.5 | 1.5' End of Boring. | | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006



Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|--|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-282+50-S10 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 10/3/2005 | | Date Drilling Completed 10/3/2005 | |
| | | | | | Drilling Method hand auger | |
| WT Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | Borehole Diameter inches | |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,650 N, 2,469,001 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ Long _____ | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |

| Sample | | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------------------|-------------|---------------|---|---------|---|-----------------|--|---------------------|-----------------|---------------------|-------|--|------------------|
| Number and Type | Length Att. & Recovered (in) | Compressive Strength | | | | | | | | Moisture Content | Liquid Limit | Plasticity Index | P 200 | | |
| | | | | 0.5 | 0 - 0.5' SILT : ML, very dark grayish brown (10YR 3/2), low plasticity, slow dilatency, low toughness, moist, very soft, trace roots/fibers/medium sand. | ML |  | | | 2 | | | | | |
| | | | | 1.0 | 0.5 - 1.5' FAT CLAY : CH, yellowish brown (10YR 5/4), high plasticity, no dilatency, high toughness, dry to moist, firm, trace roots/fibers. | CH |  | | | | | | | | |
| | | | | 1.5 | 1.5' End of Boring. | | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|



Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778_HARPOU2_3.GPJ

Route To: Watershed/Wastewater ☐ Waste Management ☐
Remediation/Redevelopment ☒ Other ☐

Page 1 of 1

| | | | | | | |
|---|-----------------|--------------------------|---|---|---|-----------------------------|
| Facility/Project Name HARP OU2/L & OU3 | | | License/Permit/Monitoring Number | | Boring Number RL-282+50-S30 | |
| Boring Drilled By: Name of crew chief (first, last) and Firm Randy Barnhill Natural Resource Technology, Inc. | | | Date Drilling Started 11/14/2005 | | Date Drilling Completed 11/14/2005 | |
| Drilling Method hand auger | | | | | | |
| WI Unique Well No. | DNR Well ID No. | Common Well Name | Final Static Water Level Feet (NAVD) | Surface Elevation 0.0 Feet (NAVD) | | Borehole Diameter inches |
| Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Plane 734,630 N, 2,469,001 E S/C/N 1/4 of 1/4 of Section , T N, R | | | Lat _____ ' _____ " _____ " Long _____ ' _____ " _____ " | | Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W | |
| Facility ID | | County Calumet | County Code 8 | Civil Town/City/ or Village Chilton | | |


| Sample | | Blow Counts | Depth In Feet | Soil/Rock Description And Geologic Origin For Each Major Unit | U S C S | Graphic Log | Well Diagram | Soil Properties | | | | | RQD/ Comments |
|--------------------|---------------------------------|-------------|---------------|---|---------|---|-----------------|-------------------------|---------------------|-----------------|---------------------|-------|------------------|
| Number and Type | Length Att. & Recovered (in) | | | | | | | Compressive Strength | Moisture Content | Liquid Limit | Plasticity Index | P 200 | |
| | | | 0 - 0.5' | ELASTIC SILT : MH , black (10YR 2/1), nonplastic, no dilatency, moist, very soft, trace roots/fibers. | MH |  | | | | | | | |
| | | | 0.5 - 2' | FAT CLAY : CH , brown (10YR 4/3), high plasticity, no dilatency, high toughness, moist, hard, trace roots to 1'. | CH |  | | | | | | | |
| | | | 2' | End of Boring. | | | | | | | | | |

I hereby certify that the information on this form is true and correct to the best of my knowledge.

| | | |
|-------------------------------------|--|--|
| Signature Eric P. Kovatch | Firm Natural Resource Technology, Inc. 23713 W Paul Road, Suite D Pewaukee, WI. 53072 | Tel: (262) 523-9000 Fax: (262) 523-9001 |
|-------------------------------------|--|--|

Date Modified: 1/6/2006
This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Template: WDNR SBL 1998 - Project: 1778 HARPOU2.3.GPJ



| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|--|-------------------------|---|
| Sample Location: RL-268+70-E10 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: dry | | |
| Described By: David Richardson | | |
| Date Described: September 30, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Lower surface than RL-268+70-W10. Adjacent to stream defined roughly by the field line | | |
| Depth (inches) | Soil Horizon | Description |
| 0-10 | A | 10YR 2/1 black, silt loam, ML, dry, friable, 5% roots, no mottles, fine granular structure |
| 10-17 | A2 | 10YR 2/1 black, silty clay loam, ML, damp, friable, 2% roots, no mottles, fine granular structure, increase in clay due to argillic condition, clay skins on ped faces |
| 17-41 | A3 | 10YR 2/1 black, sandy loam, SM, moist, friable, 1% roots, 10% 5YR 3/3 dark reddish brown mottles, fine granular structure, no clay skins, shell fragments in bottom 10 inches |
| 41- | C | 10YR 5/2 grayish brown, clay loam, CL, damp, firm, no roots, 2% 5GY 5/1 greenish gray mottles, coarse subangular blocky structure |
| | | End of core at 50 inches in C horizon |
| | | |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|--|-------------------------|---|
| Sample Location: RL-268+70-E30 | | |
| Geomorphic Setting: High terrace | | |
| Water Level in Sample Tube Hole: 31 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: September 30, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Edge of hay field. Clear scarp between E10 and E30. Surficial A horizon gone due to clay skins present at surface in A horizon or due to plow zone. Surface away from stream across east side of stream. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-14 | Ap | 10YR2/1 black, silty clay loam, ML, damp, friable, 2% roots, 10% 5YR 3/4 dark reddish brown mottles, fine subangular blocky structure, clay skins on ped faces |
| 14-38 | A2 | 10YR 2/1 black, silt loam, ML, dry, friable, 2% roots, 20% 5YR 3/3 dark reddish brown mottles, fine granular structures, no clay skins |
| 38-46 | B | 10YR 3/2 very dark grayish brown, silty clay loam, ML, moist, friable, trace roots, 15% 5YR 3/4 dark reddish brown mottles, medium subangular blocky structure, no clay skins |
| 46- | C | 10YR 3/2 very dark grayish brown, sandy loam, SM, wet, friable, no roots, 5% 10YR 4/4 dark yellowish brown mottles, medium granular structure |
| | | End of core at 51 inches in C horizon |
| | | |
| | | |

| |
|--|
| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin |
| Sample Location: RL-268+70-W10 |
| Geomorphic Setting: Intermediate terrace |
| Water Level in Sample Tube Hole: 27 inches below ground surface |
| Described By: David Richardson |
| Date Described: September 30, 2003 |
| Soil Sample Collected: |
| Remarks: Same surface on west side of Pine Creek from oxbow location to tributary stream (south to north). Approximately same elevation as E30. |

| Depth (inches) | Soil Horizon | Description |
|-------------------|-----------------|--|
| 0-11 | A | 10YR 2/1 black, silt loam, ML, dry, friable, 5% roots, no mottles, fine granular structure |
| 11-19 | A2 | 10YR 2/1 black, silty clay loam, ML, dry, friable, 2% roots, no mottles, fine granular structure, increase in clay content due to argillic condition similar to Bt horizon. Indicative of a stable soil, clay skins on ped faces |
| 19-33 | C | 2.5YR 4/2 dark grayish brown, silty clay loam, ML (more clay than A2), damp, friable, trace roots, 15% 10YR 4/4 dark yellowish brown mottles, coarse subangular blocky structure, no definitive clay skins (not argillic), below 24 inches some very fine sand layers within the silty clay loam |
| 33- | 2C | 10YR 5/2 grayish brown, sandy clay loam, SM, moist, friable/firm, trace roots, 25% 10YR 4/4 dark yellowish brown and 10YR 5/1 gray mottles, coarse subangular blocky structure |
| | | End of core at 38 inches in 2C horizon |
| | | |
| | | |

| | | |
|--|-------------------------|--|
| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
| Sample Location: RL-274+40-S5 | | |
| Geomorphic Setting: Low terrace | | |
| Water Level in Sample Tube Hole: 22 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 2, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Low terrace area 100 feet long by 30 feet wide. Atypical in this reach of the stream. Very little terrace development due to low channel gradient. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-5 | A | 10YR 2/1 black silt loam, ML, moist, friable, 10% roots, no mottles, fine granular structure |
| 5-19 | A2 | 10YR 2/1 black, silt loam, ML, moist, friable, 5% roots, 10% 5YR 3/3 dark reddish brown mottles, fine granular structure |
| 19-22 | C | 10YR 5/1 gray, silty clay loam, CL, moist, friable, trace roots, no mottles, coarse subangular blocky structure, clay skins on ped faces |
| 22- | 2C | 7.5YR 4/2 brown, clay loam, CL, damp, firm, no roots, 25% 10B 6/1 bluish gray mottles, medium angular blocky structure |
| | | End of core at 31 inches in 2C horizon |
| | | |
| | | |

| | | |
|---|---------------------|--|
| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
| Sample Location: RK-274+40-S30 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: dry | | |
| Described By: David Richardson | | |
| Date Described: October 2, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Surface on west side of stream in Reach L adjacent to the stream in most locations. Similar surface as east side of stream adjacent to the channel. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-5 | A | 10YR 2/1 black, silt loam, ML, dry, friable, 10% roots, no mottles, fine granular structure |
| 5-19 | A2 | 10YR 2/1 black, silty clay loam, CL, damp, friable, 5% roots, 5%YR 3/4 dark reddish brown mottles, fine granular structure |
| 19-28 | A3 | 10YR 2/1 black, silty clay loam, CL, damp, friable, 2% roots, no mottles, medium subangular blocky structures, clay skins on ped faces |
| 28- | C | 10YR 5/4 yellowish brown, silty clay loam, CL, damp, friable, 1% roots, 40% 10YR 5/1 gray mottles, medium subangular blocky structures |
| | | End of core at 31 inches in C horizon |
| | | |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-------------------------|--|
| Sample Location: RL-281+80-S5 | | |
| Geomorphic Setting: Low terrace | | |
| Water Level in Sample Tube Hole: 9 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 2, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Floodplain/low terrace area roughly 50 long by 20 feet wide. Isolated areas adjacent to the stream. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-8 | A | 10YR 2/1 black, silt loam, ML, wet, friable, 5% roots, no mottles, fine granular structure |
| 8-20 | A2 | 10 YR2/1 black, silt loam, ML, wet, friable, 5% roots, no mottles, fine granular structure, layers of black non-native color, sweet odor |
| 20-33 | 2A | 10YR 2/1 black, silt loam, ML, moist, friable, 10% roots, no mottles, medium subangular blocky structure, buried A horizon, trace coarse sand and pebbles, shell fragments |
| 33- | C | 7.5YR 4/2 brown, clay loam, CL, damp, firm, trace roots, 10% N 5/0 gray mottles, medium subangular blocky structure |
| | | End of core at 37 inches in C horizon |
| | | |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-------------------------|---|
| Sample Location: RL-281+80-S25 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: 26 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 2, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Steep scarp between low and intermediate terraces | | |
| Depth (inches) | Soil Horizon | Description |
| 0-5 | A | 10YR 2/1 black, silt loam, ML, dry, friable, 10% roots, no mottles, fine granular structure |
| 5-22 | A2 | 10YR 2/1 black, silty clay loam, CL, damp, friable, 5% roots, 10% 5YR 3/4 dark reddish brown mottles, fine granular structure, clay skins of ped faces |
| 22-30 | A3 | 10YR 2/1 black, silt loam, ML, wet, friable, 5% roots, no mottles, fine granular structure, few coarse sand |
| 30- | C | 5YR 4/2 dark reddish gray, clay loam, CL, damp, firm, trace roots, 15% 5GY 6/1 greenish gray and 10YR 4/4 dark yellowish brown mottles, medium angular blocky structure |
| | | End of core at 37 inches in C horizon |
| | | |
| | | |

| | | |
|---|-------------------------|--|
| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
| Sample Location: RL-281+80-S75 | | |
| Geomorphic Setting: high terrace | | |
| Water Level in Sample Tube Hole: dry | | |
| Described By: David Richardson | | |
| Date Described: October 2, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Upland surface which is the dominant surface away from the channel on the south and west side of the channel. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-5 | A | 10YR 2/1 black, silt loam, ML, damp, friable, 10% roots, no mottles, fine granular structure |
| 5-14 | A2 | 10YR 2/1 black, silty clay loam, CL, damp, friable, 5% roots, 10% 5YR 3/4 dark reddish brown mottles, fine granular structure, clay skins of ped faces |
| 14- | C | 7.5YR 5/3 brown, clay loam, CL, damp, firm, trace roots, 40% 5YR 3/4 dark reddish brown mottles, medium angular blocky structure |
| | | End of core at 22 inches in C horizon |
| | | |
| | | |
| | | |

| | |
|-----------|--|
| | |
| P101/2PL | 0-6" (RP001L – 6 ppm) |
| P102/4PL | 0-12" (RP002L – 13.3 ppm) |
| P103/6PL | 0-6" (RP004L – 7.28 ppm) |
| P105/10PL | 6-12" (RP006L – 6.05 ppm, duplicate sample analysis is 2.26 ppm) |
| P202/3PR | 0-6" (RP502R – 5.55 ppm, RP506R – 7.46 ppm) |

Polygons Not Sampled – OU-3 Reaches N, O and P

| Polygon | Similar Polygon Identified in Original Sampling Plan and Results from Sampling Similar Polygon |
|---|--|
| 6NL <u>ok</u> | 4NL 8.4/39/0.22 |
| 9NL <u>ok</u> | 1NL 15/0.89/0.4 |
| 13NL <u>ok</u> | 1OR 6.4/2.6 |
| 9NR I have 8NR, not 9NR – 1 sample inside 9NR, rest are at boundary between 8/9NR | 7NR 13/0.11 |
| 11NR | |
| 3OL | 3OR 0.15/? away from stream |
| 4OL | 5OR 31/1.9 |
| 5OL | 5OR 31/1.9 |
| 6OL | 7OR <0.033/? away from stream |
| 8OL | 11OL 4/0.23 perpendicular to stream -- need to identify sample location |
| 12OR | 13OR 0.92/? away from stream |
| | |
| 1PL | 1PR 10/4.4/? |
| 3PL | 8PL 0.21/? away from stream |
| 5PL | 7PL 20/01 |
| 10PL | 12PL 8.8/2 |
| 11PL | 12PR 10/6 |
| 12PL | 11PR 13/0.043 |
| 15PL | 11PR 13/0.043 |
| 16PL | 14PL <0.036 away from stream |
| 6PR | 14PL <0.036 away from stream |
| 7PR | 14PL <0.036 away from stream |
| 8PR | 3PR 12/0.083 |
| | |

Comment [jmg1]: Refer to your other document for O and P polygon comments/additions

Locations where the stream has moved laterally and deposition of PCBs on the inside of the meander is likely and where not previously sampled.

| Approximate Location | Comment |
|----------------------|--|
| 310+80-E10 | Within polygon 5NR I picked out the same ones for N so |
| 313+00-E10 | Within polygon 8NR we are in agreement -- three for three |
| 314+90-W10 | Within polygon 10NL |
| | |
| 322+00-E10 | Within 5OR OK with these five |
| 323+00-W10 | Within 5OL |
| 324+70-W10 | Within 7OL |
| 325+00-E10 | Within 5OL |
| 325+70-W10 | Within 7OL |
| | |
| 333+40-E10 | Within 3PR |
| 11PR/12PR | The tight meander area but this could be captured by your comment (11 PR -- Downstream portion near 339+70) in the under-sampled list |
| | |
| | |

Locations that appear to be under-sampled. {Note: This list is prepared without the knowledge of where TRC may have collected step-out samples.

| | |
|------------------------|---|
| Western portion of 5NR | See lateral deposition sample above (H) |
| 7NL upstream | At about 310+30-W20 (M) |
| 7NL downstream | At about 312+50-W10 (M) |
| 8NR downstream | See lateral deposition sample at 313+00-E10; upstream of 9NR (H) Also at meander between 204 and 204a |
| 10NL upstream | At about 313+50-W30 (M) Also at 314+50 |
| 12NL | Downstream of 13NL; sample taken |
| 11NR | Upstream and downstream samples |
| N110 | Upland boundary |
| 5NL | Downstream, upland sample at boundary between 0-6 and 6-12 boundary |
| 7OL | See lateral deposition samples above |
| 3OR | Downstream at about 320+00-e10 |
| 5OR | At about 322+80-E20 |
| 11OR | Upstream portion at about 327+30 |
| 7OLa | The depression in this polygon |
| 1PR | Upstream and downstream of 2PR; TRC will likely claim recent samples cover; |
| 3PR | Upstream portions; upstream end of P202 not identified |
| 9PR | Between 8PR and 12PR |
| 9PR | Near 341+00-N10 |
| 2PL | Upstream portion near 331+00-S10; sample taken 2.13 |
| 2PL | In internally drained area along road embankment (M) |
| 11PR | Downstream portion near 339+70 |
| 10PL | Portion downstream of 11PL; included in removal area P104 |

Comment [jmg2]: For this category of Reach P, our comments were almost a one for one match. I have no additions to this section.

Selected locations where only the 0 to 6 inch depth was analyzed. Alternatively, simply state that all samples where only the 0 to 6 inch depth was analyzed need to be sampled.


| | |
|----------------|--|
| RN-305+90-N90 | |
| RN-305+90-S40 | |
| RN-309+40-N10 | |
| RN-311+00-W100 | |
| RN-311+60-W40 | |
| RN-313-00-E100 | |
| RN-315+50-E10 | |
| RN-315+50-W40 | |


Polygons Not Sampled – OU-3 Reaches N, O and P


JMG Comments in Orange

| Polygon | Similar Polygon Identified in Original Sampling Plan and Results from Sampling Similar Polygon |
|---------------|---|
| 6NL | 4NL 8.4/39/0.22 |
| 9NL | 1NL 16/0.91, but 9NL is farther away from the stream |
| 13NL | 1OR 6.4/2.6; not fully sampled, but included in removal area |
| 9NR | 7NR 13/0.11; subsequently sampled and found 13.2/0.17 |
| 11NR | Far from stream and data from polygons around it is low (below 1) |
| 3OL | 3OR 0.15/? away from stream |
| 4OL | 5OR 31/1.9; not sampled, but identified for removal to depth of 12 inches (floor PRV?) |
| 5OL | 5OR 31/1.9 |
| 6OL | 7OR <0.033/? away from stream |
| 8OL | 11OL 4/0.23 perpendicular to stream -- need to identify sample location; eastern half appears to be lower elevation |
| 12OR | 13OR 0.92/? away from stream |
| 7OR | Is away from stream |
| 11OR | Bracketed by low concentrations |
| 10OR | Could be low |
| RO 330+20-S50 | |
| 1PL | 1PR 10/4.4/? |
| 3PL | 8PL 0.21/? away from stream |
| 5PL | 7PL 20/01; sampled 3.08/9.86 |
| 10PL | 12PL 8.8/2 -- appears to have been sampled 23/28/0.45 |
| 11PL | 12PR 10/6; sampled at one end at depth of 6 to 12 inches; identified for removal to 12 inches |
| 12PL | 11PR 13/0.043 |
| 15PL | 11PR 13/0.043 |
| 16PL | 14PL <0.036 away from stream |
| 6PR | 14PL <0.036 away from stream; TRC will claim that a sampled originally identified for 10PR falls within 6PR. If so, then 10PR is not sampled |
| 7PR | 14PL <0.036 away from stream |
| 8PR | 3PR 12/0.083; sampled 11.3; southern part identified for removal |
| 4PR | There are samples taken at the boundary between 4PR and 1PR and 6PR. Since these are boundary samples, I identified this as having no sampling. |

Comment [jmg1]: I have it identified as no samples in 10PR based on its location in 6PR.







EARTHTECH


4135 Technology Parkway, Sheboygan, WI 53083 (920) 458-8711

| | |
|--------------------|-------------------|
| DRAWN BY: SMF | DATE: May 4, 2005 |
| CHECKED BY: JT/SRK | EDITED BY: SMF |
| FILE NAME: Reach N | |

FIGURE 14
PRE-INVESTIGATION SWAC
OU3
REACH N

TECUMSEH PRODUCTS COMPANY
NEW HOLSTEIN, WISCONSIN

| | |
|----------------|-------|
| PROJECT NUMBER | 44420 |
|----------------|-------|



| | |
|--|-------------------------|
| <p>EARTH TECH</p> <p><small>A tyco INTERNATIONAL LTD. COMPANY</small></p> <p><small>4135 Technology Parkway, Sheboygan, WI 53083 (920) 455-8711</small></p> | |
| DRAWN BY: JRD | DATE: NOVEMBER 26, 2003 |
| CHECKED BY: JDW | EDITED BY: JDW |
| FILE NAME: OU3 112603 JW.dwg | |
| <p>FIGURE 7</p> <p>OU3</p> <p>REACH N</p> | |
| <p>TECUMSEH PRODUCTS COMPANY</p> <p>NEW HOLSTEIN, WISCONSIN</p> | |
| PROJECT NUMBER | 44420.02 |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-----------------|--|
| Sample Location: RN-317+00-N5 | | |
| Geomorphic Setting: Low terrace | | |
| Water Level in Sample Tube Hole: 12 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Representative location of north side of stream | | |
| Depth (inches) | Soil Horizon | Description |
| 0-10 | A | 10YR 2/1 black, silt loam, ML, moist, friable, 5% roots, no mottles, fine granular structure |
| 10-13 | A2 | 10YR 2/1 black, silty clay loam, CL, moist, friable, 5% roots, 10% 7.5YR 3/4 dark brown mottles, fine granular structure, thin clay skins on ped faces |
| 13-29 | 2Ab | 10YR 2/1 black, silt loam, ML, wet, friable, 25% roots, no mottles, fine granular blocky structure, wood fragments, former O horizon that was exposed to air and decomposed to a mineral A horizon |
| 29- | 2C | 7.5YR 5/2 brown, clay loam, CL, damp, firm, no roots, 15% 10GY 6/1 greenish gray mottles, medium angular blocky structure |
| | | End of core at 33 inches in 2C horizon |
| | | |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-----------------|---|
| Sample Location: RN-317+00-S5 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: 31 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Representative location for south side of channel in Reach N. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-8 | A | 10YR 2/1 black, silt loam, ML, moist, friable, 5% roots, no mottles, fine granular structure |
| 8-17 | A2 | 10YR 2/1 black, silt clay loam, CL, moist, friable, 5% roots, 10% 5YR 3/3 dark reddish brown mottles, fine granular structures, clay skins on ped faces |
| 17-24 | A3 | 10YR 2/1 black, silty clay loam, CL, damp, friable, 10% roots, no mottles, fine subangular blocky structure, clay skins on ped faces |
| 24-34 | 2Ab | 10YR 2/1 black, silt loam, ML, moist, friable, 25% roots, no mottles, medium subangular blocky structure, no clay skins, former O horizon |
| 34- | 2C | 7.5YR 5/2 brown, clay loam, CL, damp, firm, no roots, 15% 10GY 6/1 greenish gray mottles, medium angular blocky structure |
| | | End of core at 39 inches in 2C horizon |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|---------------------|---|
| Sample Location: RO-323+50-N10 | | |
| Geomorphic Setting: Low terrace | | |
| Water Level in Sample Tube Hole: 13 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Selected one representative location instead of two since same surface on the inside of the meander bend. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-4 | A | 10YR 2/1 black, silt loam, ML, moist, friable, 10% roots, no mottles, fine granular structure |
| 4-21 | A2 | 10YR 2/1 black, silty clay loam, CL, moist, friable, 10% roots, 10% 5YR 3/4 dark reddish brown mottles, fine granular structures, clay skins on ped faces |
| 21-37 | 2Ab | 10YR 2/1 black, silt loam, ML, wet, friable, 25% roots, no mottles, medium subangular blocky structure, former O horizon |
| 37- | 2C | 5Y 4/1 dark gray, silty clay loam, CL, wet, firm, trace roots, no mottles, medium subangular blocky structure |
| | | End of core at 44 inches in 2C horizon |
| | | |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-----------------|---|
| Sample Location: RP-334+30-S5 | | |
| Geomorphic Setting: Low terrace | | |
| Water Level in Sample Tube Hole: 12 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Low terrace in Reach P. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-12 | A | 10YR 2/1 black, silt loam, ML, wet, friable, 10% roots, no mottles, fine granular structure |
| 12-19 | A2 | 10YR 2/1 black, silty clay loam, CL, wet, friable, 10% roots, no mottles, medium subangular blocky structure, clay skins on ped faces |
| 19-36 | 2Ab | 10YR 2/1 black, silt loam, ML, wet, friable, 25% roots, no mottles, medium subangular blocky structure, former O horizon |
| 36-54 | 2Ab2 | 10YR 2/1 black, silt loam, ML, wet, friable, 25% roots, no mottles, medium subangular blocky structure, 10% shell fragments and trace coarse sand and pebbles, former O horizon |
| 54- | 2C | 10YR 5/1 gray, silty clay loam, CL, wet, firm, no roots, no mottles, medium subangular blocky structure |
| | | End of core at 60 inches in 2C horizon |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-------------------------|---|
| Sample Location: RP-334+30-S20 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: 10 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Representative of intermediate terrace on south and west side of channel. | | |
| Depth (inches) | Soil Horizon | Description |
| 0-4 | A | 10YR 2/1 black, silt loam, ML, moist, friable, 10% roots, no mottles, fine granular structure |
| 4-20 | A2 | 10YR 2/1 black, silt loam, ML (more clay than above), wet, friable, 10% roots, 10% 5YR 3/4 dark reddish brown mottles, fine granular structures, thin clay skins on ped faces |
| 20-33 | A3 | 10YR 2/1 black, silt loam, ML, moist, friable, 2% roots, 5% 5YR 3/4 dark reddish brown mottles, fine granular structure, no clay skins on ped faces |
| 33-52 | 2Ab | 10YR 2/1 black, silt loam, ML, wet, friable, 25% roots, no mottles, medium subangular blocky structure, 15% shell fragments, trace coarse sand |
| 52- | 2C | 10YR 5/1 gray, silty clay loam, CL, wet, firm, no roots, no mottles, medium subangular blocky structure |
| | | End of core at 60 inches in 2C horizon |
| | | |

| Site Name: Pine Creek Waterway Soil Characterization Study, New Holstein, Wisconsin | | |
|---|-------------------------|---|
| Sample Location: RP-340+40-N10 | | |
| Geomorphic Setting: Intermediate terrace | | |
| Water Level in Sample Tube Hole: 12 inches below ground surface | | |
| Described By: David Richardson | | |
| Date Described: October 7, 2003 | | |
| Soil Sample Collected: | | |
| Remarks: Representative intermediate terrace in Reach P | | |
| Depth (inches) | Soil Horizon | Description |
| 0-8 | A | 10YR 2/1 black, silty clay loam, CL, moist, friable, 10% roots, no mottles, fine granular structure |
| 8-19 | A2 | 10YR 2/1 black, silty clay loam, CL, moist, friable, 10% roots, 10% 5YR 3/4 dark reddish brown mottles, fine granular structures, clay skins on ped faces |
| 19-29 | C | 10YR 3/1 dark gray, silty clay loam, CL, wet, firm, 2% roots, 5% 5YR 3/4 dark reddish brown mottles, medium subangular blocky structure, no clay skins |
| 29-35 | 2Ab | 10YR 2/1 black, silt loam, ML, moist, friable, 25% roots, no mottles, fine granular structure, former O horizon |
| 35- | 2C | 7.5YR 5/2 brown, clay loam, CL, moist, firm, no roots, 10% 5G 6/1 greenish gray mottles, medium angular blocky structure |
| | | End of core at 42 inches in 2C horizon |
| | | |

Draft M E M O

Date: December 4, 2003

To: Philip Simon, ATS
Peter Simon, ATS

From: Dave Richardson, Earth Tech
Steve Rowe-Krumdick, Earth Tech
John Wiater, Earth Tech

Subject: **HARP - OU3; Overbank Sampling and Analysis Plan (SAP)
Pine Creek, Reaches H through P: Geomorphological Characterization and
Soil Descriptions, and OU3 Off-Channel Sampling Plan
New Holstein, Wisconsin**

INTRODUCTION

This memorandum characterizes the stream environment of the Third Operable Unit (OU3) of the Hayton Area Remediation Project (HARP). The OU3 Soil Sampling Plan is based on geomorphological characterization and soil descriptions performed in spring and fall of 2003, a review of aerial photography, and mapped topographic contours.

The purpose of the geomorphological characterization is to determine the depositional environments within OU3 and understand the storage and transport of PCB contaminated sediment through the system. The depositional environments in OU3 have been mapped and a focused sampling strategy has been developed to determine the concentration and extent of PCB contaminated sediment. Geomorphological principles demonstrated in HARP OU1/Segment 7 and OU2 have been applied to OU3. On a geologic timescale, the release and transport of PCB within the HARP System (Jordan and Pine Creeks) is a relatively recent phenomenon so the focus of this sampling plan is surface and near surface depositional areas.

For the purposes of investigation, OU3 has been divided into 9 reaches (H through P) based on channel gradient and the similarity of depositional environments within a reach. The reaches are presented on Figure 1A. It is important to note that Reach H, which was originally classified as part of OU2 in the HARP RI/FS, is being included in this OU3 effort. As discussed in the OU2 sampling plan, characterization of Reach H was deferred because of limitations in the aerial photographic coverage available at the time the plan was developed. However, reclassification of Reach H into OU3 also makes sense from a geomorphological perspective because of changes in stream gradient.

AERIAL PHOTOGRAPH INTERPRETATION

Ann Arbor Technical Services (ATS) purchased historical aerial photographs of Pine Creek within OU3. The dates of the photographs range from 1938 to 2001. In meandering portions of the stream, the stream energy (erosive forces) alternates from bank to bank, which will increase the rate of meandering. Increased erosion on the outside of a meander bend would be offset by increased deposition on the inside of the downstream meander bend. For OU3, aerial photographs for the years 1951, 1973, 1986, and 1992 were sufficient to document the relatively minor meanders that were observed.

Experience with HARP OU1 Segment 7 and OU2 has shown the highest concentration PCB laden sediments are located in sediment deposited on the inside of the meander bends. This mechanistic model suggests that the high concentration PCB sediments remained at the ground surface or were buried in-place by overbank deposition as the channel migrated in the direction of the outside meander bend. In either scenario, the channel migration or burial by overbank deposition would limit re-suspension and further transport of the PCBs.

The aerial photographs were assigned survey coordinates and projected in ArcInfo using the Wisconsin State Plane coordinate system. The aerial photographs were then imported into AutoCAD, scaled, and adjusted according to known landmarks (road crossings, road intersections, bridges etc). The stream channel was then visually located and digitally traced according to its location during that particular year. In several of the aerial photographs, poor photo quality and/or the season in which the photo was taken (due to overgrown vegetation) prevented the tracing of the entire stream channel as it meandered through the landscape. Some photographs were not used due to poor quality of the aerials or the presence of a better quality photograph within a similar period.

The aerial photograph review compared the former channel bed locations over several years and the 1997 topographic survey of the channel. The comparison of the channel locations indicated the amount of channel migration between the times of the photographs. To determine locations of the historical overbank deposits potentially containing significant PCB concentrations, it was assumed that the PCB laden sediments arrived downstream of the confluence of Pine and Jordan Creeks sometime after 1966 [see ATS Technical Memorandum (July 23, 2001), and OU1/Segment 7 Remediation SOW]. It is assumed that the channel bottom and inside meander bends at the time of the PCB release, and for a time period after, will contain the highest concentration of PCBs. Due to the uncertainty associated with the interpretation of aerial photographs, emphasis was placed on the aerial photographs taken between 1952 and the 1970s to estimate the location of the late 1960s-early 1970s channel. The location of the channel from the late 1960s to the present location is of primary concern for this project.

GEOMORPHOLOGICAL CHARACTERIZATION

The purpose of the Geomorphological Characterization was to determine the location, similarities, and differences between depositional areas adjacent to Pine Creek in OU3. It was anticipated that recent depositional areas, identified during the geomorphological investigation, would be sampled to determine the presence and extent of PCB contamination. In-channel sediment deposition within OU3 was previously characterized in April 1998 (Pine Creek Waterway Soil/Sediment Study Final Technical Memorandum - Rust, June 1998). The 1998 study indicated that the majority of the in-channel deposits in OU3 were half channel and full channel sediment deposits rather than the gravel and cobble substrate materials observed in OU2. The half channel deposits are located along the inside of meander bends. The full channel deposits occur where the channel widens in low gradient areas. Although the information obtained during the 1998 investigation may be updated by another sediment inventory, the information previously obtained is sufficient for conceptual planning purposes. General channel bed information for the reach is presented in a text note on each of the figures.

The geomorphological characterization for bank and over-bank deposits is a two-step process that involves the interpretation of historical aerial photographs of Pine Creek and the description of soil profiles to identify areas of historical lateral migration and overbank deposition.

GEOMORPHOLOGICAL ANALYSIS

Earth Tech utilized the results of the aerial photographic review, the 1997 detailed topographic mapping, the longitudinal profile of Pine Creek, and notes collected during several site visits from 1998 to the

present, to estimate the number and location of various depositional environments and compare and contrast the different deposits. An Earth Tech geomorphologist selected representative locations for detailed soil descriptions to provide information on each type of depositional environment. Figures illustrating the location of the soil descriptions for each reach are provided in Attachment A.

In a stream environment, it is important to be able to relate one area to another when evaluating depositional environments. The soil profile is the most accurate way to determine if two surfaces have undergone similar depositional and erosion factors. Soil description locations were selected based on their setting in the stream environment. The channel gradient, location relative to a meander bend, elevation, likelihood of sediment deposition, and number of similar surfaces were parameters used to select the soil description locations. To clarify the setting for a soil description location, the terms *floodplain* and *low, intermediate, and high terrace* are used in a relative sense and are not based on flood elevation determinations. The soil profile descriptions were used to confirm or change the prefield determination of floodplain, low, intermediate, or high terrace terminology. Although the terms are not based on flood stages, the use of the term low terrace relates similar surfaces, within a designated reach, based on topography and soil development.

A hand-operated 2-inch diameter sampling tube was used to examine the soil profile. The soil horizons, soil characteristics, and potential sediment deposition layers were described. Soil characteristics such as horizon designation, Munsell soil color, texture, moisture, plasticity, organic content, mottling, structure, and any other notable features were recorded on field forms. This information will be used to ascertain the similarities and differences between the soil profiles and identify representative locations for soil sampling.

RESULTS

The following sections describe the soil profile descriptions, geomorphic surfaces, and sampling plan for each reach of the stream in OU3. The figures showing each reach, the historic air photo channels, and sampling locations are included in Attachment A. The soil profile descriptions are included in Attachment B. The sampling table is included in Attachment C.

Reach H (Station 208+00 to 217+80)

No soil descriptions were completed within Reach H during 2003. During a previous investigation, a four soil sample location transect was completed at 215+00. Analysis of the historical aerial photographs show the channel has been stable from 1951 to the 1997. The only deviation from the current channel was at 215+00 where the 1951 channel was present south of the current channel location. The former channel was evaluated by the four core soil transect.

The transect at 215+00 included a soil description and soil sample on the floodplain, low terrace, intermediate terrace south of the current channel and high terrace located north of the current channel. This transect was selected because it was the area with the greatest likelihood for PCB deposition in Reach H.

Soil samples will be collected for laboratory analysis from a transect at 209+80. The transect will include a soil sample from the low terrace and intermediate terrace west of the current channel and the high terrace on the east side of the current channel. Two additional samples will be collected from the high terraces north and south of the current channel at 215+00. These samples will determine the horizontal extent of the PCB contamination at this transect.

Reach I (Station 217+80 to 232+00)

Four soil descriptions were completed within Reach I. Two soil descriptions were located in the low terrace, one on an intermediate terrace, and one on a high terrace. Analysis of the historical aerial photographs showed the channel has been stable since 1951.

The low terrace soil description at 221+60-S25 includes three A horizons from ground surface to a depth of approximately 19 inches. The A horizons overlie a buried A, B and C horizon. The three A horizons are due to overbank sedimentation. The low terrace at 231+30-S10 includes three A horizons overlying a C horizon. The three A horizons are 43 inches thick which is indicative of sedimentation.

The intermediate terrace location at 231+30-S50 has two A horizons overlying a B and two C horizons. The A horizons are 16 inches thick, which does not show signs of sedimentation. The distance from the channel has probably limited sedimentation.

The high terrace location at 231+30-N10 has two A horizons overlying a buried A horizon and C horizon. The two A horizons overlying a buried A horizon is indicative of overbank sedimentation but the sedimentation may not be recent.

Soil samples for laboratory analysis will be collected in a floodplain and low terrace located south of the channel at 221+60. The low, intermediate, and high terrace will be sampled at 231+30. The low and intermediate terraces are located south of the channel and the high terrace is located north of the channel. Two additional samples will be collected from the high terrace north and south of the channel at 221+00 and 226+00.

Reach J (Station 232+00 to 250+00)

Four soil descriptions were completed within Reach J. Two soil descriptions were located on the floodplain, one on the low terrace, and one on the intermediate terrace. Analysis of the historical aerial photographs showed the channel has been relatively stable for a meandering portion of the stream; however, at a few locations the channel has migrated up to 25 feet since 1951.

The floodplain soil profiles are indicative of recent sedimentation. The soil profile at 249+00-W10 has two A horizons which are 35 inches thick which is indicative of sedimentation occurring during soil development. The A horizons overlie a C horizon. The floodplain at 249+40-N10 has a 22-inch thick A horizon overlying a well-sorted C horizon. The C horizon is an in channel deposit. The C horizon overlies a buried A horizon.

The low terrace soil description at 246+20-S10 includes 2 A horizons from ground surface to a depth of approximately 29 inches. The two A horizons are thick due to overbank sedimentation. The A horizons overlie a buried A and two C horizons.

The intermediate terrace location at 246+20-S50 has 2 A horizons overlying a C horizon. The A horizons are 16 inches thick and do not show signs of sedimentation. The distance from the channel has probably limited the sedimentation.

Soil samples for laboratory analysis will be collected from a high terrace north of the channel at 232+50 to determine if the 1951 channel has filled with PCB contaminated sediment. The intermediate terrace south of the channel at 235+60 and the intermediate terrace north of the channel at 236+40 will be sampled to determine if the 1951 channel has filled with PCB contaminated sediment. The high terrace adjacent to the channel at 235+60 will be representative of that surface. Low and intermediate terrace samples located south of the channel at 246+20 will represent similar surfaces in Reach J. The floodplain

will be sampled at 249+00 and 249+40 to determine if PCB contaminated sediment is present in the 1951 channel. Two additional samples will be collected from the high terrace north and south of the channel at 246+00 and 237+00, respectively.

Reach K (Station 250+00 to 266+00)

Seven soil descriptions were completed within Reach K. One soil description was located on the floodplain, four on the low terrace, and two on the intermediate terrace. Analysis of the historical aerial photographs showed the channel has been relatively stable for a meandering portion of the stream; however, there are a few locations where the channel has migrated a maximum of 25 feet since 1951.

The floodplain soil profile is indicative of recent sedimentation. The soil profile at 262+80 S10 has three A horizons totaling 43 inches thick, indicative of sedimentation occurring during soil development. The A horizons overlie B and C horizons. The C horizon is a clay loam. The soil profile, to a depth of 58 inches, does not include sand or pebbles that would indicate this was an in-channel area. This floodplain has been adjacent to the channel for a long period of time.

Two low terrace soil descriptions include two or three A horizons from ground surface to a depth of approximately 40 inches. The A horizons are thick due to overbank sedimentation during soil development. The A horizons overlie C horizons in both profiles. At 254+00-N20, the C horizon is clay loam. The clay loam indicates a period of ponded water for the clay particles to be deposited. At 258+00-W10, the C horizon is fine loamy sand underlain by gravel, indicative of a former channel area. The low terrace at 253+30-S50 has a 4-inch A horizon overlying a clay loam C horizon. This is an area of former agriculture production and the A horizon has been eroded over the years. This profile does not show sedimentation. The low terrace at 262+80-S30 is adjacent to a floodplain. This location has two A horizons which are 18 inches thick. The underlying C horizons are angular gravel and fine sandy loam. This is a former channel or point bar deposit.

The intermediate terrace locations are very different profiles due to their proximity to the stream. At 255+30-S10, this terrace is adjacent to a low terrace and shows no evidence of sedimentation. The profile has a 10 inch A horizon overlying a clay loam C horizon. The intermediate terrace at 262+80-N10 is adjacent to the channel. Based on the aerial photos, the channel has been stable in this area since 1951. The three A horizons have a total thickness of 40 inches, indicative of sedimentation during soil development. In addition, the A horizons overlie two buried A horizons. This core ended at 58 inches in the second buried A horizon.

Soil samples for laboratory analysis will be collected from three low terrace locations at 253+30 to determine if the 1951 channel has filled with PCB contaminated sediment. The low terrace west of the channel at 258+00 will be sampled due to the thickness of the A horizons that indicate sedimentation has occurred during soil development. The floodplain and intermediate terrace located at 262+80 will be sampled due to thick A horizons on the floodplain and intermediate terrace. The intermediate terrace is representative of similar surfaces adjacent to the channel in Reach K. Two low terrace and one intermediate terrace samples will be used to characterize the former oxbow channel at 263+80. Two additional samples will be collected from the high terrace north and south of the channel at 253+30 and 260+80, respectively.

Reach L (Station 266+00 to 284+00)

Eight soil descriptions were completed within Reach L. Two soil descriptions were located on the low terrace, four on the intermediate terrace, and two on the high terrace. Analysis of the historical aerial

photographs showed the channel has been relatively stable; however, there are four locations where the 1951 channel was present outside the existing channel.

The two low terrace soil descriptions include two A horizons from ground surface to a depth of approximately 20 inches. This is a natural thickness for A horizons and does not indicate sedimentation during soil development. At 274+40-S5, the two C horizons underlying the A horizons are clay loam. The clay loam indicates a period of ponded water for the clay particles to be deposited. This location appears to be stable with little sedimentation. At 281+80-S5, the two surface A horizons overlie a buried A horizon and a clay loam C horizon. This is a portion of the stream that shows the 1951 channel was south of the existing channel. Although the soil profile does not indicate a channel bed, the buried A horizon indicates sedimentation has occurred during soil development.

The intermediate terrace locations at 268+70 are very different profiles due to their setting relative to a meander bend. One location is 10 feet east of the channel on the inside of a meander bend and the other is 10 feet west of the channel on the outside of the same meander. The soil profile at E10 has three A horizons totaling 41 inches thick, overlying a clay loam C horizon. The soil profile at W10 has two A horizons to a depth of 19 inches overlying two C horizons. The E10 location has evidence of sedimentation due to channel migration whereas the W10 location does not. The intermediate terrace at 274+40-S30 has three A horizons to a depth of 28 inches overlying a silty clay loam C horizon. Although the three A horizons are present, 28 inches thick is not abnormal in a former plow zone. The intermediate terrace at 281+80-S25 has three A horizons totaling 30 inches thick. The A horizons overlie a clay loam C horizon. This location does not show signs of recent sedimentation.

Two high terrace locations were examined, one at 268+70-E30 and 281+80-S75. At 268+70-E30, the surface A horizon has clay skins which are indicative of clay movement downward in the soil profile. Because clay skins are not present at the surface, this means an overlying A horizon has been eroded away due to agricultural practices. The underlying A horizon is 24 inches thick, indicative of sedimentation during soil development. Sedimentation is likely at this location because it is the inside of a meander bend and the 1951 channel is mapped on the aerial photos as being within 15 feet of this location. Below the two A horizons lie B and C horizons. The high terrace at 281+80-S75 is a typical upland soil profile consisting of two A horizons to a depth of 14 inches and a clay loam C horizon. This profile does not show evidence of sedimentation.

Soil samples for laboratory analysis will be collected from an intermediate terrace and high terrace transect at 268+70 to determine if the 1951 channel has filled with PCB contaminated sediment. The intermediate terrace at 272+00 will be sampled as a representative location where the intermediate terrace is adjacent to the stream. The intermediate terrace at 276+00 will be sampled due to the location of the 1951 channel and the potential for sedimentation in that channel. The low and intermediate terraces on the south side of the channel at 281+80 and the intermediate terrace north of the channel at 282+50 will be sampled to determine if the 1951 channel has filled with PCB contaminated sediment and to obtain a representative intermediate terrace location for Reach L. Four additional samples will be collected from the high terrace. Two west of the channel at 267+00 and 277+00 and two east of the channel at 272+00 and 279+50.

Reach M (Station 284+00 to 304+00)

Six soil descriptions were completed within Reach M. One soil description was located on the low terrace and five on the intermediate terrace. Analysis of the historical aerial photographs showed the channel has been stable; however, the meanders that begin at 295+00 show areas where the 1951 channel was present outside the existing channel.

The low terrace soil description south of the channel at 299+90-S15 includes three A horizons from ground surface to a depth of approximately 42 inches. The A horizons are thick due to overbank sedimentation during soil development. A buried A horizon and clay loam C horizon underlay the three A horizons. This soil profile does not show evidence of a former channel but is indicative of sedimentation above the buried A horizon.

The intermediate terrace locations have similar soil profiles that consist of two or three A horizons overlying a buried A horizon and a silty clay loam or clay loam C horizon. The two or three A horizons vary in thickness from 19 to 40 inches. The buried A horizon has an increase in organic matter from the overlying A horizons. The 293+30-S10 location had a well sorted fine sand C horizon between three A horizons and the buried A horizon. The well sorted sand is indicative of a running water channel setting. At 293+30-S30, the soil profile included three A horizons overlying a silty clay loam C horizon. This location is a depression on the intermediate terrace and is located at the approximate location of the 1951 channel. The soil profile does not show any evidence of a channel deposit.

Soil samples for laboratory analysis will be collected from an intermediate terrace at 289+00 to represent the intermediate terrace adjacent to the channel on the west side of the stream. Samples will be collected from two intermediate locations (south) and high terrace (north) transect at 293+30 to determine if the 1951 channel has filled with PCB contaminated sediment and to have a sample from the high terrace adjacent to the channel. The low and intermediate terraces on the south side of the channel at 299+90 will be sampled to determine if the 1951 channel has filled with PCB contaminated sediment. Four additional samples will be collected from the high terrace. Two west of the channel at 290+00 and 301+00 and two east of the channel at 290+00 and 300+00.

Reach N (Station 304+00 to 318+00)

Two soil descriptions were completed within Reach N. One soil description was located on the low terrace and one on the intermediate terrace. Analysis of the historical aerial photographs showed the channel has been stable except in the meanders at 305+00 and 308+00 where the 1951 channel is outside of the existing channel. The channel was not visible in the 1951 aerial photograph due to ponding in the area from approximately 310+00 to 325+00.

The low terrace soil description at 317+00-N5 includes two A horizons from ground surface to a depth of approximately 13 inches. The A horizons overlie a buried A and C horizon. This low terrace location represents the low terrace found on the north and east side of Pine Creek.

The intermediate terrace location at 317+00-S5 has three A horizons overlying a buried A horizon and a clay loam C horizon. The A horizons are 24 inches thick. The A horizons do not show signs of sedimentation. The intermediate terrace is expansive on the west side of the stream channel.

Soil samples for laboratory analysis will be collected at two locations on the intermediate terrace at 304+50 due to the tight inside meander bend. The locations will show the contrast in sedimentation with distance from the stream. A sample will be collected from the low terrace locations at 305+90 and 308+20, and the intermediate terrace at 307+30 to determine if the 1951 channel has filled with PCB contaminated sediment. Samples will be collected from the low and intermediate terraces north and south respectively at 317+00. These samples will be representative of the terraces found adjacent to the channel in Reach M. Two additional samples will be collected from the intermediate and low terraces west of the channel at 311+00 and east of the channel at 313+00, respectively.

Reach O (Station 318+00 to 331+00)

One soil description was completed within Reach O. The soil description was located on the low terrace. Analysis of the historical aerial photographs showed the channel has been stable except between 325+00 and 327+00 where the 1951 channel is outside of the existing channel. The channel was not visible in the 1951 aerial photograph due to ponding in the area from approximately 310+00 to 325+00.

The low terrace soil description at 323+50-N10 includes two A horizons from ground surface to a depth of approximately 21 inches. The A horizons overlie a buried A and C horizon. This low terrace location is on the inside of a meander bend and should be subject to more sedimentation than other low terrace locations.

A soil sample for laboratory analysis will be collected at transect 324+00 on the low terrace, representing the terraces found adjacent to the channel in Reach O. A sample will be collected at 326+80 on the intermediate terrace to determine if the 1951 channel was located south of the existing channel and if so, whether the former channel filled with PCB contaminated sediment. A sample will be collected from the low terrace at 329+00. This sample will be representative of the low terraces adjacent to the large wetland areas in Reach O. Two additional samples will be collected from the high and low terraces north and south of the channel at 327+00 and 328+00, respectively.

Reach P (Station 331+00 to 342+00)

Three soil descriptions were completed within Reach P. One soil description was located on the low terrace and two on the intermediate terrace. Analysis of the historical aerial photographs showed the channel has been stable since 1951.

The low terrace soil description at 334+30-S5 includes two A horizons from ground surface to a depth of approximately 19 inches. The A horizons overlie two buried A horizons and a C horizon. The surface A horizons are indicative of sedimentation occurring during soil development because they are formed in a setting adjacent to the existing channel that is affected by the ponding of the Hayton dam. This location's hydrology is wetter now than prior to the placement of the dam.

The intermediate terrace location at 334+30-S20 has three A horizons overlying a buried A horizon and a C horizon. The A horizons are 33 inches thick which shows signs of sedimentation. The intermediate terrace at 340+40-N10 includes two A horizons overlying a C horizon, a buried A horizon and a second C horizon. The two A horizons and uppermost C horizon overlying a buried A horizon is indicative of overbank sedimentation, but the sedimentation may not be recent.

Soil samples for laboratory analysis will be collected on the low and intermediate terraces located south of the channel at 334+30. The intermediate terrace will be sampled at 340+40. Three additional samples will be collected from the high terrace north and south of the channel. The high terrace sample north of the channel is at 338+00. The high terrace samples south of the channel are located at 335+00 and 339+00.

CONCLUSIONS

The aerial photograph review and geomorphological characterization have led to a targeted sampling plan. Because the focus is on depositional areas, the number of samples is reduced and the reliability in extrapolating data is increased because it is done on the basis of the geomorphologic model. The aerial photographs were used to determine the historic location of the stream channel. In a meandering stream situation, this information was helpful to target areas that have shown historic lateral channel migration which, in turn, were used to determine areas of deposition.

The geomorphological characterization for a stream is developed using a number of parameters that provide information about the stream's setting. The longitudinal profile is used to determine the channel gradient which provides information about stream velocity. The stream velocity dictates the areas of erosion or deposition. The stream geomorphology provides information about the amount of channel migration and terrace development. The terrace development provides information about the amount of channel migration and the potential for erosion and deposition areas. The soil profile provides information about the degree of soil development, and whether erosion or sediment deposition has occurred at the location. A comparison of soil profile information can be used to determine if similar terraces have had similar levels of soil development.

Field investigation is used to determine the existing geomorphology of the channel, floodplain, and terraces, and to ground truth information obtained from the aerial photos. The samples that will be collected as part of this sampling plan will be used to verify the relative age of depositional areas, and determine the vertical extent of PCB contamination. This information can be extrapolated to similar surfaces in each reach. Soil descriptions from different surfaces are used to determine the extent of recent deposition and to determine which surfaces have similar soil profiles. Similar soil profiles on the low terraces present within a Reach indicate the surfaces have undergone the same deposition or erosion factors.

Geomorphological data obtained in 2003 from soil descriptions in Reaches H through P have been used to select soil sample locations which target the areas of deposition/sedimentation. Implementation of this sampling plan will further define depositional areas as they relate to PCB impact. The PCB data from this sampling and analysis plan, together with existing geomorphologic information for OU3, will provide the information necessary to develop the remedial plan for OU3.

SCHEDULE

Given approval by WDNR on or before March 1, 2004, Tecumseh proposes to conduct this OU3 sampling and analysis during July 2004, when this largely wetland area will be dry enough for access. This sampling could be conducted earlier at the Department's discretion but we believe the nature of OU3 is such that access will be much more difficult if the sampling is conducted much earlier than July before spring high water level conditions subside. Weather permitting, the results of this field survey should be available on or before August 15, 2004.

ATTACHMENT A

FIGURES

Figures 1A and 1 through 9

ATTACHMENT B
SOIL CORE DATA SHEETS

ATTACHMENT C

**Table TM1
SOIL SAMPLING PLAN**



230 West Monroe Street
Suite 2370
Chicago, IL 60606

312.578.0870 PHONE
312.578.0877 FAX

www.TRCSolutions.com

October 11, 2011

Mr. Jim Baumann
Special Assistant to Bureau Director
Bureau of Watershed Management
Wisconsin Department of Natural Resources
101 S. Webster Street, Box 7921
Madison, WI 53707-7921

Ms. Jean Greensley
U.S. Environmental Protection Agency
Remediation and Reuse Branch
Land and Chemicals Division
77 W. Jackson Boulevard
Chicago, IL 60604-3511

**Re: Characterization Sample Results
Operable Unit 3, Reaches N, O and P
Hayton Area Remediation Project**

Dear Mr. Baumann and Ms. Greensley:

During our meeting on October 5, 2011, WDNR proposed that WDNR, EPA and TRC would review available information to determine data gaps in Reaches N, O and P of the Hayton Area Remediation Project, Operable Unit 3 (OU3) by October 20, 2011. WDNR requested that TRC provide recent sample results for Reaches N, O and P no later than October 12th.

Enclosed for your review are figures and tables that include all recent sample results for Reaches N, O and P. Electronic copies of this submittal are also being provided via email to James.Baumann@Wisconsin.gov and Greensley.Jean@epamail.epa.gov.

Based on the enclosed sample results, some of the proposed removal boundaries of Reaches N, O and P have been modified, as shown on Figures 1 through 3. TRC is currently collecting additional characterization samples in Reaches N, O and P to further characterize the areas.

Please contact me at (312) 578-0870, extension 8486, with any questions.

Sincerely,




Christopher D. Harvey, PE
Program Manager

Enclosures: *Figure 1 - Sample Results and Excavation Boundaries, Reach N*
Figure 2 - Sample Results and Excavation Boundaries, Reach O
Figure 3 - Sample Results and Excavation Boundaries, Reach P
Table 1- Reach N Characterization Sample Results
Table 2- Reach O Characterization Sample Results
Table 3 - Reach P Characterization Sample Results

**Table 1. Reach N Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|--------------------|-------------------------------|-----------------|
| RN 001L 0-6" | 0.662 | |
| RN 002L 0-6" | 2.95 | |
| RN 003L 0-6" | 2.63 | |
| RN 004L 0-6" | 1.15 | |
| RN 004L 6-12 | 4.62 | |
| RN 005L 0-6" | 2.79 | |
| RN 005L 6-12" | 2.0 | |
| RN 006L 0-6" | 1.57 | |
| RN 006L 6-12" | 2.11 | |
| RN 007L 0-6" | 1.38 | |
| RN 008L 0-6" | 0.87 | |
| RN 008L 6-12" | 2.17 | |
| DUP 94 | 2.4 | |
| RN 009L 0-6" | 1.75 | |
| RN 009L 6-12" | 1.86 | |
| RN 010L 0-6" | 2.44 | |
| RN 011L 0-6 | 2.53 | |
| RN 011L 6-12 | 0.158 (J) | |
| RN 012L 0-6 | 5.79 | |
| RN 013L 6-12 | 8.96 | |
| RN 014L 0-6 | 6.71 | |
| RN 015L 6-12 | 12.4 | |
| DUP 106 | 8.21 | |
| RN 016L 6-12 | 3.46 | |
| RN 017L 0-6 | 8.11 | |
| RN 017L 12-18 | ROCK | |
| RN 017L 6-12 | 13.8 | |
| RN 018L 0-6 | 10.9 | |
| RN 018L 6-12 | 3.21 | |
| RN 019L 0-6 | 3.83 | |
| RN 020L 6-12 | 5.43 | |
| RN 021L 0-6 | 0.936 | |
| DUP 126 | 1.66 | |
| RN 021L 6-12 | 0.121 (J) | |
| RN 022L 0-6 | 14.5 | |
| RN 022L 6-12 | 0.975 | |
| RN 023L 0-6 | 3.48 | |
| RN 023L 6-12 | 9.09 | |
| RN 024L 6-12 | 5.76 | |
| RN 025L 0-6 | 4.65 | |
| RN 025L 6-12 | 4.39 | |
| RN 025L 12-18 | 22.2 | |
| RN 500R 0-6" | 0.797 | |
| RN 501R 0-6" | 0.544 | |
| RN 501R 6-12" | 0.086 | |
| RN 502R 0-6" | 1.51 | |

**Table 1. Reach N Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|--------------------|-------------------------------|------------------------------------|
| RN 502R 6-12" | 2.37 | |
| RN 503R 0-6" | 1.65 | |
| RN 504R 0-6" | 0.745 | |
| RN 505R 0-6" | 1.33 | |
| RN 506R 0-6" | 2.39 | |
| RN 507R 0-6" | 1.09 | |
| RN 508R 0-6" | 1.1 | |
| RN 509R 0-6 | 1.09 | |
| RN 509R 6-12 | 0.0602 (J) | |
| RN 510R 0-6 | 2.18 | |
| RN 511R 0-6 | 1.09 | |
| RN 512R 0-6 | 7.69 | |
| RN 513R 0-6 | 2.44 | |
| RN 514R 0-6 | 3.12 | Collected near the top of the bank |
| RN 514R 6-12 | 1.21 | Collected near the top of the bank |
| DUP 109 | 0.657 | Collected near the top of the bank |
| RN 515R 6-12 | 0.191 | |
| RN 516R 6-12 | 0.576 | Collected near the top of the bank |
| RN 517R 0-6 | 0.748 | |
| RN 518R 0-6 | 0.926 | Collected near the top of the bank |
| RN 519R 0-6 | 0.79 | |
| RN 520R 0-6 | 1.78 | Collected near the top of the bank |

(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit

**Table 2. Reach O Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|--------------------|-------------------------------|--------------------------------|
| RO 001L 0-6" | 1.77 | |
| RO 002L 0-6" | 3.92 | |
| RO B003L 0-6" | 2.6 | |
| RO 004L 0-6" | 3.19 | Located at the top of the bank |
| RO 005L 0-6" | 2.45 | |
| RO 006L 0-6" | 3.07 | |
| RO 007L 0-6" | 2.78 | |
| RO 500R 6-12" | 9.21 | |
| DUP 103 | 9.59 | |
| RO 501R 0-6" | 8.74 | |
| RO 502R 0-6" | 1.02 | |
| RO 503R 0-6" | 7.3 | |
| RO 504R 6-12" | 4.37 | |
| RO 505R 6-12" | 6.59 | |
| RO 506R 0-6" | 4.91 | |
| RO 507R 6-12" | 11.3 | |
| DUP 130 | 14.9 | |
| RO 508R 0-6" | 0.732 | |

(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit

**Table 3. Reach P Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|---------------|-----------------------|--------------------------------|
| RP 001L 0-6" | 6.0 | |
| RP 002L 0-6" | 8.41 | |
| RP 002L 6-12" | 13.3 | |
| DUP 104 | 12.2 | |
| RP 003L 0-6" | 4.38 | Located at the top of the bank |
| RP 004L 0-6" | 7.28 | |
| RP 005L 0-6" | 4.45 | |
| RP 006L 6-12" | 6.05 | |
| DUP 105 | 2.26 | |
| RP 007L 0-6 | 2.13 | Located at the top of the bank |
| RP 008L 0-6 | 5.9 | |
| RP 008L 6-12 | 4.92 | |
| RP 009L 0-6 | 3.08 | |
| RP 009L 6-12 | 9.86 | |
| RP 009L 12-18 | <0.0437 | |
| RP 009L 18-24 | <0.0396 | |
| DUP 120 | <0.417 | |
| RP 010L 0-6 | 3.15 | Located at the top of the bank |
| RP 011L 0-6 | 0.915 | |
| RP 012L 6-12 | 0.114 (J) | |
| RP 013L 6-12 | 4.54 | |
| RP 014L 6-12 | 2.93 | |
| RP 015L 0-6 | 1.12 | |
| RP 016L 0-6 | 1.26 | |
| RP 017L 0-6 | 2.54 | |
| RP 018L 0-6 | 2.08 | Located at the top of the bank |
| RP 018L 6-12 | 0.256 | Located at the top of the bank |
| RP 019L 6-12 | 3.69 | |
| RP 500R 0-6" | 4.58 | |
| RP 501R 0-6" | 1.49 | |
| RP 502R 0-6" | 5.55 | |
| RP 503R 0-6" | 2.96 | |
| RP 504R 0-6" | 4.39 | |
| RP 504R 6-12" | 2.78 | |
| DUP 121 | 4.32 | |
| RP 505R 0-6" | 4.56 | |
| RP 506R 0-6 | 7.46 | |
| RP 507R 6-12 | 2.79 | |
| RP 508R 0-6 | 1.58 | |

(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit



TABLE TM1
HARP OU3 Sediment Sampling
Sediment Sampling to Identify PCB Deposition Areas

| Location | Old Name | New Name | Notes | Purpose | | | Media | Surface Represented | Analytical Method | Sediment Classification | Protocol ⁽⁴⁾ | | | | | Target Sample Interval ⁵ |
|----------|-------------|----------------------|--------------------------------|---------------------------------|-------------------------|----------|-------------------|---------------------|-----------------------------|-------------------------|-------------------------|-----------------------|--------------|----------------|-----------|-------------------------------------|
| | | | | Area Delineation ⁽¹⁾ | Field QA ⁽²⁾ | Resample | | | | | GeoProbe | Sampling Tube and CAB | Bucket Auger | Piston Sampler | Hand Core | |
| Reach L | | RL-267+00-W100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RL-268+70-E30 | | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RL-268+70-E5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | WDNR-012-93 | RL-270+00-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RL-272+00-E100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RL-272+00-W5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | FVD-RI-SD29 | RL-275+80-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RL-276+00-E5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RL-277+30-W100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | WDNR-011-93 | RL-279+00-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | WDNR-011-93 | RL-279+00-IC-RS-DUP | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | NA | | | | | | SAME AS ORIG. |
| | | RL-279+50-E100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RL-281+80-S15 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RL-281+80-S5 | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RL-281+80-S5.....DUP | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | NA | | | | | | SAME AS ORIG. |
| | | RL-282+50-N25 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.4 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| Reach M | WDNR-010-93 | RM-285+00-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RM-289+00-W10 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RM-290+00-E100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RM-290+00-W100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | WDNR-009-93 | RM-291+00-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RM-293+30-N5 | | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RM-293+30-S30 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RM-293+30-S5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | WDNR-008-93 | RM-296+90-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RM-299+00-E100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RM-299+90-S15 | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RM-299+90-S25 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RM-301+00-S100 | SWAC | | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | WDNR-007-93 | RM-302+70-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| Reach N | | RN-304+50-S30 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RN-304+50-S5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RN-304+50-S5.....DUP | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | NA | | | | | | SAME AS ORIG. |
| | | RN-305+90-N10 | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RN-307+30-S10 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RN-308+20-N10 | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | WDNR-006-93 | RN-308+80-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RN-311+00-W100 | SWAC | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RN-313+00-E100 | SWAC | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | WDNR-005-93 | RN-314+90-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RN-317+00-N5 | | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RN-317+00-S5 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |

TABLE TM1
HARP OU3 Sediment Sampling
Sediment Sampling to Identify PCB Deposition Areas

| Location | Old Name | New Name | Notes | Purpose | | Media | Surface Represented | Analytical Method | Sediment Classification | Protocol ⁽⁴⁾ | | | | | Target Sample Interval ⁵ |
|----------|--------------|---------------------|--------------------------------|---------------------------------|-------------------------|-------------------|---------------------|-----------------------------|-------------------------|-------------------------|----------|-----------------------|--------------|----------------|-------------------------------------|
| | | | | Area Delineation ⁽¹⁾ | Field QA ⁽²⁾ | | | | | Resample | GeoProbe | Sampling Tube and CAB | Bucket Auger | Piston Sampler | |
| Reach O | WDNR-004-93 | RO-320+80-IC-RS | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RO-324+00-E5 | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RO-326+80-W20 | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RO-327+00-N50 | SWAC | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-2 |
| | | RO-328+00-S100 | SWAC | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | WDNR-002-93 | RO-328+20-IC-RS | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RO-329+00-S10 | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | WDNR-0021-93 | RO-330+20-IC-RS | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | WDNR-0021-93 | RO-330+20-IC-RS-DUP | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| Reach P | FVD-RI-SD32 | RP-331+90-IC-RS | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RP-334+30-S20 | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RP-334+30-S5 | | | | Overbank Sediment | Low Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1.5 |
| | | RP-335+00-S100 | SWAC | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | FVD-RI-SD33 | RP-337+90-IC-RS | Sampled May '03 ⁽⁶⁾ | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RP-338+00-N100 | SWAC | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RP-339+00-S100 | SWAC | | | Overbank Sediment | High Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1 |
| | | RP-340+40-N5 | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-1.5 |

NOTES:

⁽¹⁾ Contaminated Area Soil/Sediment delineation.

⁽²⁾ Field Duplicates were scoped for an overall frequency of 1 per 20 investigative samples. During the May 2003 In-channel sample event (see note 8 below), two duplicates were collected over the 25 samples as noted in the table. For the OU3 off-channel sampling, 5 additional duplicates are proposed for the 83 samples.

⁽³⁾ Field rinseate blank samples (Field Blanks) will be collected from the stainless steel bowl and spoon or trowel mixing devices at a rate of one per twenty samples. Distilled water will be poured over a decontaminated stainless steel bowl and spoon or trowel and into a sample bottle for the analysis of PCBs. Additionally, for each piece of chemical analysis sampling equipment that does not utilize a CAB liner (dredge, bucket auger, and spade), one Field Blank will be collected per event that equipment was used by pouring distilled water over the decontaminated equipment and into a sample bottle for the analysis of PCBs.

⁽⁴⁾ Protocol defined in Project QAPP.

⁽⁵⁾ Sediment samples collected from top of sediment through depth of river channel sediments.

⁽⁶⁾ Unified Soil Classification System (USCS). Protocol defined in Project QAPP

⁽⁷⁾ In-channel (IC) sediments (originally presented in the May 5, 2003, *HARP OU3 In-Channel Sediment Sampling* - See note 8 below) have been renamed for presentation purposes to avoid confusion over the originally proposed "Silt" and "Sand" suffixes. The predominant grain size of the actual sample location in many instances did not contain the anticipated sediment type. Therefore, the suffixes of "Silt" and "Sand" have been removed from the Table and the mapping in this memorandum.

⁽⁸⁾ Earth Tech performed in-channel sampling in OU3, Reaches H through S, in May 2003. These sample locations were presented in the *HARP OU3 In-Channel Sediment Sampling* spreadsheet sent to Jim Baumann of WDNR by Earth Tech (05/07/03). The results of this sampling will be submitted under separate cover.

--- No sediment classification available for this location.

| TABLE TM1 HARP OU3 Sediment Sampling Sediment Sampling to Identify PCB Deposition Areas | | | | | | | | | | | | | | | | |
|---|-------------|----------------------------|--------------------------------|---------------------------------|----------------------------|----------|-------------------|--------------------------------|-----------------------------|-------------------------|-------------------------|-----------------------|--------------|----------------|-----------|-------------------------------------|
| Location | Old Name | New Name | Notes | Purpose | | | Media | Surface Represented | Analytical Method | Sediment Classification | Protocol ⁽⁴⁾ | | | | | Target Sample Interval ⁵ |
| | | | | Area Delineation ⁽¹⁾ | Field QA ⁽²⁾⁽³⁾ | Resample | | | | | GeoProbe | Sampling Tube and CAB | Bucket Auger | Piston Sampler | Hand Core | |
| OU3 | | | | | | | | | | | | | | | | |
| Reach Q | | RQ-347+50-W25 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RQ-358+00-S25 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RQ-358+00-S75 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| Reach R | | RR-364+50-N25 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | | RR-370+00-S100 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | 0-3 |
| | FVD-RI-S035 | RR-374+30-IC-RS | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| Reach S | | RS-387+00-IC | Sampled May '03 ⁽⁸⁾ | | | | Sediment | In-Channel | USEPA 8082-WIS, USEPA 160.3 | USCS ⁽⁶⁾ | | | | | | (5) |
| | | RS-389+00-N50 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS (5) | | | | | | 0-3 |
| | | RS-389+00-N50..DUP | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS (5) | | | | | | 0-3 |
| | | RS-389+00-S50 | | | | | Overbank Sediment | Int. Terrace | USEPA 8082-WIS, USEPA 160.3 | USCS (6) | | | | | | 0-3 |
| Field | | RO-320+80-IC-RINS | Sampled May '03 ⁽⁸⁾ | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| Rinstate | | RS-387+00-IC-RINS | Sampled May '03 ⁽⁸⁾ | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| Blanks ⁽⁷⁾ | | BLANK-BOWL-3-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-BOWL-4-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-PDREDGE-1-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-EDREDGE-1-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-AUGER-1-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-SPADE-1-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| | | BLANK-"equipment"-1-"date" | | | | | Rinse | Sample collected if needed (3) | Method USEPA 8082-WIS | | | | | | | |
| NOTES: | | | | | | | | | | | | | | | | |
| ⁽¹⁾ Contaminated Area Soil/Sediment delineation. | | | | | | | | | | | | | | | | |
| ⁽²⁾ Field Duplicates were scooped for an overall frequency of 1 per 20 investigative samples. During the May 2003 in-channel sample event (see note 8 below), two duplicates were collected over the 25 samples as noted in the table. For the OU3 off channel | | | | | | | | | | | | | | | | |
| ⁽³⁾ Field rinsata blank samples (Field Blanks) will be collected from the stainless steel bowl and spoon or trowel mixing devices at a rate of one per twenty samples. Distilled water will be poured over a decontaminated stainless steel bowl and spoon | | | | | | | | | | | | | | | | |
| ⁽⁴⁾ Protocol defined in Project QAPP. | | | | | | | | | | | | | | | | |
| ⁽⁵⁾ Sediment samples collected from top of sediment through depth of river channel sediments. | | | | | | | | | | | | | | | | |
| ⁽⁶⁾ Unified Soil Classification System (USCS). Protocol defined in Project QAPP | | | | | | | | | | | | | | | | |
| ⁽⁷⁾ In-channel (IC) sediments (originally presented in the May 5, 2003, <i>HARP OU3 In-Channel Sediment Sampling</i> - See note 8 below) have been renamed for presentation purposes to avoid confusion over the originally proposed "Silt" and "Sand" suffixes. | | | | | | | | | | | | | | | | |
| ⁽⁸⁾ Earth Tech performed in-channel sampling in OU3, Reaches H through S, in May 2003. These sample locations were presented in the <i>HARP OU3 In-Channel Sediment Sampling</i> spreadsheet sent to Jim Baumann of WDNR by Earth Tech (05/07/03). The results | | | | | | | | | | | | | | | | |
| --- No sediment classification available for this location. | | | | | | | | | | | | | | | | |



230 West Monroe Street
Suite 2370
Chicago, IL 60606

312.578.0870 PHONE
312.578.0877 FAX

www.TRCSolutions.com

October 11, 2011

Mr. Jim Baumann
Special Assistant to Bureau Director
Bureau of Watershed Management
Wisconsin Department of Natural Resources
101 S. Webster Street, Box 7921
Madison, WI 53707-7921

Ms. Jean Greensley
U.S. Environmental Protection Agency
Remediation and Reuse Branch
Land and Chemicals Division
77 W. Jackson Boulevard
Chicago, IL 60604-3511

**Re: Characterization Sample Results
Operable Unit 3, Reaches N, O and P
Hayton Area Remediation Project**

Dear Mr. Baumann and Ms. Greensley:


During our meeting on October 5, 2011, WDNR proposed that WDNR, EPA and TRC would review available information to determine data gaps in Reaches N, O and P of the Hayton Area Remediation Project, Operable Unit 3 (OU3) by October 20, 2011. WDNR requested that TRC provide recent sample results for Reaches N, O and P no later than October 12th.

Enclosed for your review are figures and tables that include all recent sample results for Reaches N, O and P. Electronic copies of this submittal are also being provided via email to James.Baumann@Wisconsin.gov and Greensley.Jean@epamail.epa.gov.

Based on the enclosed sample results, some of the proposed removal boundaries of Reaches N, O and P have been modified, as shown on Figures 1 through 3. TRC is currently collecting additional characterization samples in Reaches N, O and P to further characterize the areas.

Please contact me at (312) 578-0870, extension 8486, with any questions.

Sincerely,





Christopher D. Harvey, PE
Program Manager

Enclosures: *Figure 1 - Sample Results and Excavation Boundaries, Reach N*
Figure 2 - Sample Results and Excavation Boundaries, Reach O
Figure 3 - Sample Results and Excavation Boundaries, Reach P
Table 1- Reach N Characterization Sample Results
Table 2- Reach O Characterization Sample Results
Table 3 - Reach P Characterization Sample Results

**Table 1. Reach N Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|---------------|-----------------------|----------|
| RN 001L 0-6" | 0.662 | |
| RN 002L 0-6" | 2.95 | |
| RN 003L 0-6" | 2.63 | |
| RN 004L 0-6" | 1.15 | |
| RN 004L 6-12 | 4.62 | |
| RN 005L 0-6" | 2.79 | |
| RN 005L 6-12" | 2.0 | |
| RN 006L 0-6" | 1.57 | |
| RN 006L 6-12" | 2.11 | |
| RN 007L 0-6" | 1.38 | |
| RN 008L 0-6" | 0.87 | |
| RN 008L 6-12" | 2.17 | |
| DUP 94 | 2.4 | |
| RN 009L 0-6" | 1.75 | |
| RN 009L 6-12" | 1.86 | |
| RN 010L 0-6" | 2.44 | |
| RN 011L 0-6 | 2.53 | |
| RN 011L 6-12 | 0.158 (J) | |
| RN 012L 0-6 | 5.79 | |
| RN 013L 6-12 | 8.96 | |
| RN 014L 0-6 | 6.71 | |
| RN 015L 6-12 | 12.4 | |
| DUP 106 | 8.21 | |
| RN 016L 6-12 | 3.46 | |
| RN 017L 0-6 | 8.11 | |
| RN 017L 12-18 | ROCK | |
| RN 017L 6-12 | 13.8 | |
| RN 018L 0-6 | 10.9 | |
| RN 018L 6-12 | 3.21 | |
| RN 019L 0-6 | 3.83 | |
| RN 020L 6-12 | 5.43 | |
| RN 021L 0-6 | 0.936 | |
| DUP 126 | 1.66 | |
| RN 021L 6-12 | 0.121 (J) | |
| RN 022L 0-6 | 14.5 | |
| RN 022L 6-12 | 0.975 | |
| RN 023L 0-6 | 3.48 | |
| RN 023L 6-12 | 9.09 | |
| RN 024L 6-12 | 5.76 | |
| RN 025L 0-6 | 4.65 | |
| RN 025L 6-12 | 4.39 | |
| RN 025L 12-18 | 22.2 | |
| RN 500R 0-6" | 0.797 | |
| RN 501R 0-6" | 0.544 | |
| RN 501R 6-12" | 0.086 | |
| RN 502R 0-6" | 1.51 | |

**Table 1. Reach N Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|---------------|-----------------------|------------------------------------|
| RN 502R 6-12" | 2.37 | |
| RN 503R 0-6" | 1.65 | |
| RN 504R 0-6" | 0.745 | |
| RN 505R 0-6" | 1.33 | |
| RN 506R 0-6" | 2.39 | |
| RN 507R 0-6" | 1.09 | |
| RN 508R 0-6" | 1.1 | |
| RN 509R 0-6 | 1.09 | |
| RN 509R 6-12 | 0.0602 (J) | |
| RN 510R 0-6 | 2.18 | |
| RN 511R 0-6 | 1.09 | |
| RN 512R 0-6 | 7.69 | |
| RN 513R 0-6 | 2.44 | |
| RN 514R 0-6 | 3.12 | Collected near the top of the bank |
| RN 514R 6-12 | 1.21 | Collected near the top of the bank |
| DUP 109 | 0.657 | Collected near the top of the bank |
| RN 515R 6-12 | 0.191 | |
| RN 516R 6-12 | 0.576 | Collected near the top of the bank |
| RN 517R 0-6 | 0.748 | |
| RN 518R 0-6 | 0.926 | Collected near the top of the bank |
| RN 519R 0-6 | 0.79 | |
| RN 520R 0-6 | 1.78 | Collected near the top of the bank |

(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit

**Table 2. Reach O Characterization Sample Results
Hayton Area Remediation Project**

10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|---------------|-----------------------|--------------------------------|
| RO 001L 0-6" | 1.77 | |
| RO 002L 0-6' | 3.92 | |
| RO B003L 0-6" | 2.6 | |
| RO 004L 0-6" | 3.19 | Located at the top of the bank |
| RO 005L 0-6" | 2.45 | |
| RO 006L 0-6" | 3.07 | |
| RO 007L 0-6" | 2.78 | |
| RO 500R 6-12" | 9.21 | |
| DUP 103 | 9.59 | |
| RO 501R 0-6" | 8.74 | |
| RO 502R 0-6" | 1.02 | |
| RO 503R 0-6" | 7.3 | |
| RO 504R 6-12" | 4.37 | |
| RO 505R 6-12" | 6.59 | |
| RO 506R 0-6" | 4.91 | |
| RO 507R 6-12 | 11.3 | |
| DUP 130 | 14.9 | |
| RO 508R 0-6 | 0.732 | |


(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit


**Table 3. Reach P Characterization Sample Results
Hayton Area Remediation Project**


10/11/2011

| Sample Name | Total PCBs (mg/kg) | Comments |
|---------------|-----------------------|--------------------------------|
| RP 001L 0-6" | 6.0 | |
| RP 002L 0-6" | 8.41 | |
| RP 002L 6-12" | 13.3 | |
| DUP 104 | 12.2 | |
| RP 003L 0-6" | 4.38 | Located at the top of the bank |
| RP 004L 0-6" | 7.28 | |
| RP 005L 0-6" | 4.45 | |
| RP 006L 6-12" | 6.05 | |
| DUP 105 | 2.26 | |
| RP 007L 0-6 | 2.13 | Located at the top of the bank |
| RP 008L 0-6 | 5.9 | |
| RP 008L 6-12 | 4.92 | |
| RP 009L 0-6 | 3.08 | |
| RP 009L 6-12 | 9.86 | |
| RP 009L 12-18 | <0.0437 | |
| RP 009L 18-24 | <0.0396 | |
| DUP 120 | <0.417 | |
| RP 010L 0-6 | 3.15 | Located at the top of the bank |
| RP 011L 0-6 | 0.915 | |
| RP 012L 6-12 | 0.114 (J) | |
| RP 013L 6-12 | 4.54 | |
| RP 014L 6-12 | 2.93 | |
| RP 015L 0-6 | 1.12 | |
| RP 016L 0-6 | 1.26 | |
| RP 017L 0-6 | 2.54 | |
| RP 018L 0-6 | 2.08 | Located at the top of the bank |
| RP 018L 6-12 | 0.256 | Located at the top of the bank |
| RP 019L 6-12 | 3.69 | |
| RP 500R 0-6" | 4.58 | |
| RP 501R 0-6" | 1.49 | |
| RP 502R 0-6" | 5.55 | |
| RP 503R 0-6" | 2.96 | |
| RP 504R 0-6" | 4.39 | |
| RP 504R 6-12" | 2.78 | |
| DUP 121 | 4.32 | |
| RP 505R 0-6" | 4.56 | |
| RP 506R 0-6 | 7.46 | |
| RP 507R 6-12 | 2.79 | |
| RP 508R 0-6 | 1.58 | |

(J) Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit







Locations that appear to be under-sampled. {Note: This list is prepared without the knowledge of where TRC may have collected step-out samples.

| | | |
|--------------------------|--|--|
| ✓ Western portion of 5NR | See lateral deposition sample above (H) | |
| ✓ 7NL upstream | At about 310+30-W20 (M) <i>agree</i> | |
| ✓ 7NL downstream | At about 312+50-W10 (M) <i>agree</i> | |
| ✓ 8NR downstream | See lateral deposition sample at 313+00-E10; upstream of 9NR (H) - <i>sample @ meander bend between 304 & 304a</i> | |
| ✓ 10NL upstream | At about 313+50-W30 (M) + 314+50 @ meander | |
| ✓ 12NL | Downstream of 13NL; sample taken | |
| | <i>1116-40 & dis samples, 1116- upland boundary, 5 NL dis, up @ 0-6/6-18 boundary,</i> | |
| 7OL | See lateral deposition samples above | |
| 3OR | Downstream at about 320+00-e10 | |
| 5OR | At about 322+80-E20 | |
| 11OR | Upstream portion at about 327+30 | |
| 1PR | Upstream and downstream of 2PR; TRC will likely claim recent samples cover; | |
| 3PR | Upstream portions; upstream end of P202 not identified | |
| 9PR | Between 8PR and 12PR | |
| 9PR | Near 341+00-N10 | |
| 2PL | Upstream portion near 331+00-S10; sample taken 2.13 | |
| 2PL | In internally drained area along road embankment (M) | |
| 11PR | Downstream portion near 339+70 | |
| 10PL | Portion downstream of 11PL; included in removal area P104 | |

well-matched for this section

Selected locations where only the 0 to 6 inch depth was analyzed. Alternatively, simply state that all samples where only the 0 to 6 inch depth was analyzed need to be sampled.

| | |
|---------------------|--|
| ✓ RN-305+90-N90 | |
| ✓ RN-305+90-S40 | |
| ✓ RN-309+40-N10 | |
| ✓ RN-311+00-W100 | |
| ✓ RN-311+60-W40 | |
| ✓ RN-313-00-E100 | |
| ✓ RN-315+50-E10 | |
| <i>315+50 - W40</i> | |
| RO-319+60-N30 | |
| RO-323+40-N50 | |
| RO-327+00-N30 | |
| RO-328+00-S100 | |
| RO-328+70-N10 | |
| | |

Locations where the stream has moved laterally and deposition of PCBs on the inside of the meander is likely and where not previously sampled.

| Approximate Location | Comment |
|--|---|
| 310+80-E10 | Within polygon 5NR <i>I picked out the same ones for N so</i> |
| 313+00-E10 | Within polygon 8NR <i>we are in agreement - three for three</i> |
| 314+90-W10 | Within polygon 10NL |
| | |
| 322+00-E10 | Within 5OR |
| 323+00-W10 | Within 5OL |
| 324+70-W10 | Within 7OL |
| 325+00-E10 | Within 5OL |
| 325+70-W10 | Within 7OL |
| | |
| ✓ 333+40-E10 | Within 3PR |
| <i>+ 19/14 Sonaxelux @ 11 pr / 13 pr & 14 pr</i> | |
| | |
| | |

Polygons Not Sampled – OU-3 Reaches N, O and P
JMG Comments in Orange

| Polygon | Similar Polygon Identified in Original Sampling Plan and Results from Sampling Similar Polygon |
|----------------------|--|
| 6NL | 4NL 8.4/39/0.22 |
| 9NL | 1NL 16/0.91, but 9NL is farther away from the stream |
| 13NL | 1OR 6.4/2.6; not fully sampled, but included in removal area |
| 9NR | 7NR 13/0.11; subsequently sampled and found 13.2/0.17 |
| 11NR | Far from stream and data from polygons around it is low (below 1) |
| 3OL | 3OR 0.15/? away from stream |
| 4OL - I have sampled | 5OR 31/1.9; not sampled, but identified for removal to depth of 12 inches (floor PRV?) |
| 5OL | 5OR 31/1.9 |
| 6OL | 7OR <0.033/? away from stream |
| 8OL | 11OL 4/0.23 perpendicular to stream -- need to identify sample location; eastern half appears to be lower elevation |
| 12OR | 13OR 0.92/? away from stream |
| 1PL | 1PR 10/4.4/? |
| 3PL | 8PL 0.21/? away from stream |
| 5PL | 7PL 20/01; sampled 3.08/9.86 |
| 10PL | 12PL 8.8/2 -- appears to have been sampled 23/28/0.45 |
| 11PL | 12PR 10/6; sampled at one end at depth of 6 to 12 inches; identified for removal to 12 inches |
| 12PL | 11PR 13/0.043 |
| 15PL | 11PR 13/0.043 |
| 16PL | 14PL <0.036 away from stream |
| 6PR | 14PL <0.036 away from stream; TRC will claim that a sampled originally identified for 10PR falls within 6PR. If so, then 10PR is not sampled |
| 7PR | 14PL <0.036 away from stream |
| 8PR | 3PR 12/0.083; sampled 11.3; southern part identified for removal |

4pr - boundary w/ 1 pr & 6pr → have to call as no samples

I'd as 11/3 - clearly 11 6pr

[illegible]

Reach P

Poly n/s

- 1) 1pl ✓
- 2) 13pl ✓
- 3) 15pl ✓
- 4) 4pr ~~km~~
- ~~5) 4pr - 1000~~
- ~~6) 4pr~~
- ✓ 5) 7pr
- 6) 10pr
- 7) 16pl ✓

Exp. limit

- 1) P101/2pl - RP 0012 06" ^{6.0 ppm}
- ✓ 2) P102 - 0-12"
 - RP003L 6-12" 13.3
 - ~~RP003L 6-12"~~
- ✓ 3) P103 - 6pl
 - RP004L 0-6" 7.28 ppm
- ✓ 4) P105/10pl
 - RP006L 6-12" 6.05 ppm
 - dupl is 2.26
- 5) P202 ~~4~~ RP505R 0-6" (5.55)
 - RP506R 0-6" (7.46)

6" Sample Issue

- 1) RP-332+70-540 ✓
- 2) RP-335+00-5100 (.210 ppm)
- 3) RP-336+70-560 (9.3 ppm)
- 4) RP-338+00-540 (.120)
- 5) RP-339+00-5100 (L.036)
- 6) RP-340+60-510 (.1508)
- ✓ 7) RP-332+70-1135 (2.5)
- 8) RP-332+70-1150 (.170)
- 9) RP-335+00-1170 (.370)
- 10) RP-338+00-1150 (.780)
- ~~11) RP-338+00-1140 (.360)~~
- 11) RP-338+50-1140 (.360)
- 12) RP-338+00-1100 (.380)

Stream Kuread

11pr

Under Sampled

- 1) depression - 2pl
- 2) 13pl - d/s
- ✓ 3) skinny ~~up~~ area of 3pr
- 4) 6pr - but away from stream
+ low - 4pr + d/s
- ✓ 5) just if. reach. limits for
P202 - upland + upstream
- ✓ 6) 1pr - upstream
- ✓ 7) 9pr - d/s
- ✓ 8) 11pr - tight meadows - also
relates to stream Kuread
- ✓ 9) 12pr - tight meadows

1. 9NL not sampled -- yes, I failed to remove that one from the list. It will be deleted.
2. 11NR -- Please keep in mind that of the six samples you mention, three were not analyzed to a depth of more than 6 inches and RN-311+60-E10 is 13 mg/kg. The sample proposed for this polygon ended up 80 or so feet to the north. I'll discuss with Jean.
3. 4OL -- Please look again. The samples you cite appear to be in 2OL and not in 4OL. 4OL is rather small and abuts the stream.
4. 323+00-W10 -- Yes, you are correct, the location is within 2OL and not 5OL. I'll make the change.
5. 325+00-E10 -- Yes, you are correct, the location is within 5OR and not 5OL. I'll make the change.
6. 1PR -- please look again. It appears the two samples are within 2PR. The step out sample you mention was not analyzed at a depth greater than 6 inches. The original sample for 2PR seems to be at a different elevation than 1PR.

You question a number of locations identified where only the 0 to 6 inch depth was analyzed. Again, I'll discuss each one with Jean. Please keep in mind that state administrative rules require a full profile analysis. For step out samples we may agree that the original sample meets the requirements. However, these are original samples and not step out samples. The sample locations listed are a subset of locations that do not have a full profile. Each was based on some factor, such as proximity to the stream or a sample with a high concentration. For example, for RO-318+20-N80 there is a sample of 44 mg/kg within 30 feet.

Jim Baumann
Special Assistant, Bureau of Watershed Management
Wisconsin Department of Natural Resources
P. O. Box 7921
Madison, WI 53707
608/266-9277
james.baumann@wisconsin.gov

From: Harvey, Christopher (Chicago,IL-US) [mailto:CHarvey@trcsolutions.com]
Sent: Friday, October 21, 2011 10:09 AM
To: Baumann, James S - DNR; Greensley.Jean@epamail.epa.gov
Cc: Wildeman, Anna J (20109); Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR;
Danesh, Paymon (Chicago,IL-US)
Subject: RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P
Jim and Jean,

We have reviewed the draft list of proposed data gaps in HARP OU3 Reaches N, O and P that



RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Harvey, Christopher (Chicago,IL-US)

10/22/2011 03:25 PM

To: Baumann, James S - DNR, Jean Greensley

Cc: "Wildeman, Anna J (20109)", "Johnson, Deborah D - DNR",

"Rasmussen, Russell A - DNR", "Danesh, Paymon (Chicago,IL-US)"

Jim,

Thank you for looking at these so quickly. I need further clarification regarding your ending comment about a full profile analysis. Where is a full profile analysis defined? Based on Wisconsin Administrative Code NR347.06, the number and location of sediment samples can be collaboratively specified based on the initial evaluation and the potential for contamination. In addition, in NR347.06(6)(d), "If previous sampling data or other adequate available information demonstrates that the possibility of contamination is negligible, analysis for any chemical may be waived, in writing, by the department."

Based on the data and limited potential for contamination, TRC proposes that the previously referenced locations with only 0-6" sample results are adequately characterized and do not require additional vertical sampling.

Regarding the other two areas we to recheck:

4OL: I think the source of confusion is that the boundaries of 4OL are drawn differently in the SAP versus the Technical Memorandum (it extends further upstream and downstream in the latter). TRC will collect additional samples at the requested location.

1PR: You are correct, existing samples are in 2PR. TRC will collect the requested samples.

If you have any questions, please contact me at 312-578-0870, ext. 8486.

Thank you,

Chris

From: Baumann, James S - DNR [mailto:James.Baumann@Wisconsin.gov]

Sent: Friday, October 21, 2011 11:51 AM

To: Harvey, Christopher (Chicago,IL-US); Greensley.Jean@epamail.epa.gov

Cc: Wildeman, Anna J (20109); Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR; Danesh, Paymon (Chicago,IL-US)

Subject: RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Chris,

I'll contact Jean and go through each of your comments. This is why we sent it as a draft.

We will try to respond by the middle of next week. During the interim, there are a few that I can address right away and a few where I ask for you to look at again:

Reach N

Underlined

- 1) 21ML - Rock @ 12-18" RN 017L
- 2) 18ML - 6-12" - 9.09 ppm, nothing lower
- 3) 5ML - RN 012L - 0-6" 5.79 ppm ^(N10) exp. limit is 6" sample taken @ 2ML 5ML boundary
- 4) 20R - RN 512R 0-6" 7.69, N206, ^{fast forward N10 boundary} exp. limit is 6" per - pushy for @ 20R
- 5) 13ML ~~204922~~ RN 015L - 6-12" - 12.4 ppm
- 6) 16ML RN 014L - 0-6" 6.71 ppm, N107, exp. to 6", per
- 7) 21ML RN 024L - 6-12" - 5.76 ppm exp. limit is 12" - push more clay
- 8) 5ML RN 013L - 8.96 @ 6-12" - 0-12" exp. limit - per, N103
- 9) 18ML RN 025L - 12-18" 22.2 ppm - 0-18" removal - need clay sample

More sampling

- 1) 17 ml sample @ pitout - sample @ ups & d/s
- 2) 8 ml sample @ meander bend between 204 & 204a
- 3) N110 - no samples to define upland boundary
- 4) N109 - up boundary - polygon sample to line W, not E, N20330 to line east has 9.09 @ 6-12" (N20330 6-12")
- 5) 5ML upland - one more sample d/s end/upland boundary
- 6) 7ML - long stretch w/ samples by meander only - no ups & d/s data
- 7) 8ML - lg. polygon w/ one sample only - it is low 0-6 → 2.2
- 8) 10 ml - ~~no ups & d/s samples~~ - line w/ right meander - take line 315+00
- 9) 18 ml - RN 025L - 12-18 22.2 ppm - no removal id'd (above N109)

Beach / data gaps

No Samples in Polygons

x9 NL 13 NL x 40000
to 6"

x6 NL

8 NR - 9 NR is removal to 6"

~~11 NR~~ 11 NR -

Inc. Sampling in Polygons

1 NL

Undefined Limits

1) 18 ml? - RN 023L - 6-12 20.9 ppm

2) 18 ml? - RN 025L - 12-18 22.2 ppm - no removal id'd (above N109)

3) N109 - RN 024L - 6-12 - 5.76 ppm

Removal is to 12" (prv or more clac)

4) ~~N102~~ No bottom defined

4) N101 - 5.79 @ RN 012L 0.6, exc. limit is 6"

sample taken @ 2 NL / 5 NL boundary

prv

5) 5 NL upland - bit arbitrary but →

one more sample - d/s end / upland

boundary

6) N103 - RN 013L 8.96 @ 6-12 → 10-12

excavation → prv

7) 7 NL - long stretch of samples

by meafader only - no up or

d/s data

8) 8 NL - large polygon for sample only - it is low 0-6 → 2.2

9) 10 NL - no d/s samples - there is a slight mound - Lake Kuu

315 x 100

10) N107 - RN 014L - 0-6 → 6.71 - exc. to 6", prv

11) N206 - RN 512R 0-6 → 7.69 → 0-6 exc. - prv - also dotted

line between N206 & 0202 (area w/o boundary) → justify

More Definition

1) N110 - no samples to def.

upland boundary

2) N109 - upland boundary - polygon?

sample to Kuepo, not east

RN 023L to Kuepo has 9.09 @

6-12" (RN 023L 6-12")

- 11) 17 nr - sample @ put out - sample w/s & d/s
 - 12) 8 nr sample by mandrel bed between 204 & 204a
 - 13) H301 0-12 excavation - bottom not defined
 - 13) H108 - 0-18 in manual, bottom not defined
- BL0256 12-18" 22.2 - prv or chao - should
take chao sample

stream monument

X 5 nr - d/s along mandrel

X 10 nr along mandrel 315+00, plus w/s

only 0-6

exc. issues

N/S polygons

RO 001L 0-6

10R/0202 60-12
(R0507, R0505, R0503)

~~70R~~ far from
between
100R could be low

~~RO 319+60-5150 (2.2)~~

0201/40R (R0501R)
(R0503R)

100R bracketed
by low
180R ✓

RO 007L 0-6

RO 324+00-560 (4.2)

60L ✓

RO 328+00-5100 (4.4) ✓

30L ✓

RO 330+20-550 low

50L ✓

RO 330+30-115 low

80L ✓

RO 328+70-1150 low

~~RO 330+20-550~~

RO 328+70-1130 low

RO 328+70-1110 (1.1) ✓

UTM dep

RO 327+00-1130 low ✓

90L

RO -323+40-1150 (1.2) ✓

~~100L~~

RO -319+60-1130 low ✓

~~110L~~

~~RO -319+60-1150 low~~

depression in 70R

RO -319+60-1170 low

RO -318+20-1180 low

Polygons Not Sampled – OU-3 Reaches N, O and P

The polygons listed below were not sampled as part of the original sampling plan or any subsequent sampling. We've limited the list to those likely to have PCB deposits exceeding 5 mg/kg. We have not listed polygons located as some distance from the stream. For those polygons identified we have listed the similar polygons identified in the sample results. In a few situations, the polygon is identified as being part of a removal area, but the depth may not have been determined.

| Polygon | Similar Polygon Identified in Original Sampling Plan and Results from Sampling Similar Polygon |
|---------|--|
| 6NL | 4NL 8.4/39/0.22 |
| 9NL | 1NL 16/0.91, but 9NL is farther away from the stream |
| 13NL | 1OR 6.4/2.6; not fully sampled, but included in removal area - depth sample needed |
| 11NR | Original sample located 80 to 100 feet downstream from location shown in sampling plan. Sample should be about 40 to 50 feet directly east of RN—311+6—E40 |
| 3OL | 3OR 0.15/? away from stream |
| 4OL | 5OR 31/1.9; not sampled, but identified for removal to depth of 12 inches – sample at depth of >12 inches needed |
| 5OL | 5OR 31/1.9 |
| 8OL | 11OL 4/0.23 perpendicular to stream -- sample in northeastern portion of polygon at about W20 |
| 10OL | In polygon identified as 10OLa in recent submittal |
| 1PL | 1PR 10/4.4/? |
| 11PL | 12PR 10/6; sampled at one end at depth of 6 to 12 inches; identified for removal to 12 inches |
| 12PL | 11PR 13/0.043 |
| 15PL | 11PR 13/0.043 |
| 8PR | 3PR 12/0.083; sampled 11.3; southern part identified for removal – western portion needs to be sampled |
| 4PR | Western portion |

Locations where the stream has moved laterally and deposition of PCBs on the inside of the meander is likely and where not previously sampled.

| Approximate Location | Comment |
|----------------------|---------------------|
| 310+80-E10 | Within polygon 5NR |
| 313+00-E10 | Within polygon 8NR |
| 314+90-W10 | Within polygon 10NL |
| | |

| | |
|------------|--|
| 322+00-E10 | Within 5OR |
| 323+00-W10 | Within 5OL 2OL |
| 324+70-W10 | Within 7OL |
| 325+00-E10 | Within 5OL 5OR |
| 325+70-W10 | Within 7OL |
| | |
| 333+40-E10 | Within 3PR |
| 11PR/12PR | The tight meander area near 339+70 (also listed under under-sampled locations) |

Selected locations that are under-sampled.

| Location | Comment |
|------------------------|---|
| Western portion of 5NR | See lateral deposition sample above |
| 7NL upstream | At about 310+30-W20 |
| 7NL downstream | At about 312+50-W10 |
| 8NR downstream (two) | See lateral deposition sample at 313+00-E10; upstream of 9NR Also at meander between 204 and 204a in 8NR |
| 10NL upstream (two) | At about 313+50-W30 and at 314+50-W10 |
| 11NR (two) | Upstream and downstream samples. Also identified in listing of unsampled polygons. |
| N110 | Upland boundary (also identified by TRC) |
| 5NL | Downstream and upland boundaries between 0-6 and 6-12 boundary - between N103 and N101 - could be deleted - polygon |
| | |
| 7OL | See lateral deposition samples above |
| 7OLa | In depression shown on figure |
| 3OR | Downstream at about 320+00-e10 |
| 5OR | At about 322+80-E20 |
| 11OR | Upstream portion at about 327+30 |
| | |
| 1PR - the will collect | Upstream and downstream of 2PR |
| 3PR | Upstream portions; upstream end of P202 not identified |
| 9PR | Between 8PR and 12PR |
| 9PR | Near 341+00-N10 |
| 2PL | In internally drained area along road embankment |
| 11PR | Downstream portion near 339+70 |
| 10PL | Portion downstream of 11PL; included in removal area P104, but depth sampled needed |

Selected locations where only the 0 to 6 inch depth was analyzed.

| | | |
|-----|----------------|--|
| | RN-305+90-N90 | |
| | RN-305+90-S40 | |
| | RN-309+40-N10 | |
| | RN-311+00-W100 | |
| | RN-311+60-W40 | |
| | RN-313-00-E100 | |
| | RN-315+50-E10 | |
| | RN-315+50-W40 | |
| | | |
| | RO-319+60-N30 | |
| | RO-323+40-N50 | |
| | RO-327+00-N30 | |
| | RO-328+00-S100 | |
| | RO-328+70-N10 | |
| 21R | RO-319+60-S150 | |
| 21R | RO-324+00-S60 | |
| 21L | RO-330+20-S50 | |
| | RO-330+30-N5 | |
| 21L | RO-328+70-N50 | |
| | RO-328+70-N30 | |
| 21L | RO-319+60-N50 | |
| 21L | RO-319+60-N70 | |
| 21L | RO-318+20-N80 | |
| | | |
| | RP-332+70-S40 | |
| | RP-332+70-N35 | |
| 21L | RP-336+70-S60 | |

Polygons/Sections where characterization does not support excavation depth

| Polygon/location | Comment |
|------------------|--|
| 18ML | 9.09 at 12-18" and 22.2 (RN025L) at 12-18" |
| 5NL and 5NL/N103 | 5.79 (RN012L) at 0-6" and 8.16 (RN013L) at 6-12" – downstream boundary N103 and N101 |
| 20R/N206 | 7.69 (RN512R) at 0-6" |
| 12NL | 12.4 (RN015L) at 6-12" |
| 10NL/N107 | 6.7 (RN014L) at 0-6" |
| 21ML | 5.76(RN024L) at 6-12" |
| | |

| | | |
|----|-----------|--|
| | 1OR/O202 | 0-12" (RO507, RO505, RO500R) |
| | 4OR/O201 | (RO501R, RO503R) |
| | | |
| me | P101/2PL | 0-6" (RP001L – 6 ppm) |
| | P102/4PL | 0-12" (RP002L – 13.3 ppm) |
| | P103/6PL | 0-6" (RP004L – 7.28 ppm) |
| | P105/10PL | 6-12" (RP006L – 6.05 ppm, duplicate sample analysis is 2.26 ppm) |
| me | P202/3PR | 0-6" (RP502R – 5.55 ppm, RP506R – 7.46 ppm) |



RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Baumann, James S - DNR to: Harvey, Christopher (Chicago,IL-US), Jean Greensley 10/24/2011 08:41 AM
Cc: "Wildeman, Anna J (20109)", "Johnson, Deborah D - DNR",
"Rasmussen, Russell A - DNR", "Danesh, Paymon (Chicago,IL-US)"

Chris,

You asked for more information on where sampling requirements are identified. Section NR 347.06 is the best place to look in state requirements. Jean would be in a much better position to identify applicable federal requirements. A few specific state administrative rules sections that are pertinent are:

- S. NR 347.06(4)(e) identifies the information obtained visually to characterize the sample site. This information is commonly reported on the soil boring log form.
- S. NR 347.06(6)(a) identifies that each observed layer in the sample needs to be analyzed. Other sections discuss sample depths to at least parent material.

Throughout the project area we have seen greater concentrations at greater depths. This only makes sense since the older deposited sediment was of higher concentration. A number of recent samples show the increased concentration with depth where the top six inches were less than 5 mg/kg including at least three sites in Reach M collected in the last month and at least one more in Reach K. It would be hard to make a technical argument to support a presumption that all of the samples that were analyzed to a depth of 0 to 6 inches do not have PCB concentrations of significance.

Jean and I independently reviewed the information and then compared our notes. We looked at all of the sample locations where only the top six inches was analyzed and identified a subset where we thought that there was sufficient potential to have greater depths analyzed. As I indicated on Friday, we will review the ones you are questioning and get back to you as soon as we can.

Jim Baumann
Special Assistant, Bureau of Watershed Management
Wisconsin Department of Natural Resources
P. O. Box 7921
Madison, WI 53707
608/266-9277
james.baumann@wisconsin.gov

From: Harvey, Christopher (Chicago,IL-US) [mailto:CHarvey@trcsolutions.com]
Sent: Saturday, October 22, 2011 3:25 PM
To: Baumann, James S - DNR; Greensley.Jean@epamail.epa.gov
Cc: Wildeman, Anna J (20109); Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR;
Danesh, Paymon (Chicago,IL-US)
Subject: RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Jim,

Thank you for looking at these so quickly. I need further clarification regarding your ending comment about a full profile analysis. Where is a full profile analysis defined? Based on

Wisconsin Administrative Code NR347.06, the number and location of sediment samples can be collaboratively specified based on the initial evaluation and the potential for contamination. In addition, in NR347.06(6)(d), "If previous sampling data or other adequate available information demonstrates that the possibility of contamination is negligible, analysis for any chemical may be waived, in writing, by the department."

Based on the data and limited potential for contamination, TRC proposes that the previously referenced locations with only 0-6" sample results are adequately characterized and do not require additional vertical sampling.

Regarding the other two areas we to recheck:

4OL: I think the source of confusion is that the boundaries of 4OL are drawn differently in the SAP versus the Technical Memorandum (it extends further upstream and downstream in the latter). TRC will collect additional samples at the requested location.

1PR: You are correct, existing samples are in 2PR. TRC will collect the requested samples.

If you have any questions, please contact me at 312-578-0870, ext. 8486.

Thank you,

Chris

From: Baumann, James S - DNR [mailto:James.Baumann@Wisconsin.gov]
Sent: Friday, October 21, 2011 11:51 AM
To: Harvey, Christopher (Chicago,IL-US); Greensley.Jean@epamail.epa.gov
Cc: Wildeman, Anna J (20109); Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR; Danesh, Paymon (Chicago,IL-US)
Subject: RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Chris,

I'll contact Jean and go through each of your comments. This is why we sent it as a draft.

We will try to respond by the middle of next week. During the interim, there are a few that I can address right away and a few where I ask for you to look at again:

1. 9NL not sampled -- yes, I failed to remove that one from the list. It will be deleted.
2. 11NR -- Please keep in mind that of the six samples you mention, three were not analyzed to a depth of more than 6 inches and RN-311+60-E10 is 13 mg/kg. The sample proposed for this polygon ended up 80 or so feet to the north. I'll discuss with Jean.
3. 4OL -- Please look again. The samples you cite appear to be in 2OL and not in 4OL. 4OL is rather small and abuts the stream.
4. 323+00-W10 -- Yes, you are correct, the location is within 2OL and not 5OL. I'll make the change.

5. 325+00-E10 -- Yes, you are correct, the location is within 5OR and not 5OL. I'll make the change.

6. 1PR -- please look again. It appears the two samples are within 2PR. The step out sample you mention was not analyzed at a depth greater than 6 inches. The original sample for 2PR seems to be at a different elevation than 1PR.

You question a number of locations identified where only the 0 to 6 inch depth was analyzed. Again, I'll discuss each one with Jean. Please keep in mind that state administrative rules require a full profile analysis. For step out samples we may agree that the original sample meets the requirements. However, these are original samples and not step out samples. The sample locations listed are a subset of locations that do not have a full profile. Each was based on some factor, such as proximity to the stream or a sample with a high concentration. For example, for RO-318+20-N80 there is a sample of 44 mg/kg within 30 feet.

Jim Baumann
Special Assistant, Bureau of Watershed Management
Wisconsin Department of Natural Resources
P. O. Box 7921
Madison, WI 53707
608/266-9277
james.baumann@wisconsin.gov

From: Harvey, Christopher (Chicago,IL-US) [mailto:CHarvey@trcsolutions.com]
Sent: Friday, October 21, 2011 10:09 AM
To: Baumann, James S - DNR; Greensley, Jean@epamail.epa.gov
Cc: Wildeman, Anna J (20109); Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR; Danesh, Paymon (Chicago,IL-US)
Subject: RE: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P
Jim and Jean,

We have reviewed the draft list of proposed data gaps in HARP OU3 Reaches N, O and P that was provided by you. There are some items on the list that need further clarification which we have listed below. We have also identified items in the list that we believe are already adequately characterized and do not represent data gaps.

We plan to begin sampling in Reaches N, O and P in the near future to address the data gaps and submit the sample results to you by November 20, 2011. We would appreciate your comments by Tuesday, October 25th.

Polygons not sampled

- 9NL: The results cited for the similar polygon (1NL) are actually in 1NR. All of the results in 1NL are less than 5ppm. Polygon 9NL is more similar to 1NL than 1NR, since 9NL and 1NL are both upland of an outer meander, while 1NR is part of an inner meander. TRC proposes that 9NL does not represent a significant concern and does not need to be sampled.
- 11NR: There are six sample locations between the creek and 11NR that are <5 ppm (RN 517R, RN504R, RN 510R, RN-313+00-E100, RN-311+60-E40, RN-311+60-E80), which makes it unlikely that there are significant PCB concentrations in 11NR. TRC proposes that 11NR does not represent a significant concern and does not need to be sampled.
- 4OL: 4OL already has three locations that were sampled at a depth of >12 inches. TRC proposes that 4OL does not require additional sampling.

Locations where the stream moved laterally with likely deposition on an unsampled inner meander

- 323+00-W10: Please clarify. The station ID description places the sample at the inner meander at the downstream end of 2OL (not 5OL as indicated).
- 325+00-E10: Please clarify. The station ID description places the sample at the inner meander at the downstream end of 5OR (not 5OL as indicated).

Under-sampled locations

- 8NR downstream (two): Needs clarification. The two proposed samples seem to be at the same location, described in two different ways.
- 5NL: Need clarification on where it is under-sampled. Do you mean the downstream/upland boundary of N103, at approximately 13 feet west of RN-309+40-S40?
- 1PR: The downstream end of 1PR is not under-sampled. A sample has already been collected 15' feet away from the downstream end (RP 501R 0-6"=1.49 ppm). TRC proposes that an additional sample is not necessary.

→ agree and remove and

Selected locations where only the 0-6" depth was analyzed

- Sampling in Reaches N through P has identified areas where a PCB-impacted layer greater than 5 ppm is covered by a layer with lesser impacts. However, they are typically near the creek (most are within 15 feet) or near irregular terrain such as a tributary, and the 0-6" layer has a result that is close to 5 ppm (not less than 1 ppm).
- Some of the proposed data gap locations have 0-6" layer results that are less than 1 ppm and are located far from the creek in a typical setting, or have some other surrounding context that makes it unreasonable to consider such areas as data gaps. As such, TRC proposes that the following locations are adequately characterized and do not require additional vertical sampling:
 - RN-305+90-S40 (located over 40 feet away from the creek on an outer meander; and is upland of a nearby sample location RN-305+90-S10 6-12" = 0.89 ppm).
 - RN-311+00-W100 (located over 50 feet away from the creek; and there are no surrounding impacts)

- RN-311+60-W40 (has a 0-6" result of 0.28 ppm; and is upland of a nearby sample location RN 005L 6-12" = 2.0 ppm)
- RO-319+60-N30 (has a 0-6" result of 0.15 ppm; and is over one foot higher in elevation than a nearby sample RO-319+60-N10 6-12" = 2.6 ppm.)
- RO-327+00-N30 (has a 0-6" result of 0.12 ppm, the overbank is relatively steep at that location, and there are no surrounding impacts).
- RO-319+60-S150 (located over 70 feet away from the creek on an outer meander)
- RO-324+00-S60 (located upland of a nearby sample location RO-324+00-S40 6-12" = 0.083 ppm).
- RO-330+20-S50 (has a 0-6" result of 0.074 ppm; is over 50 feet away from the creek, and is upland of a nearby sample RO-330+20-S15 6-12" = 1.7 ppm).
- RO-328+70-N50 (has a 0-6" result of 0.092 ppm, and the overbank is relatively steep at that location)
- RO-319+60-N50 (has a 0-6" result of 0.044 ppm, and is approximately two feet higher in elevation than nearby sample location RO-319+60-N10 6-12" = 2.6 ppm).
- RO-319+60-N70 (has a 0-6" result of <0.033 ppm, and is approximately two feet higher in elevation than nearby sample location RO-319+60-N10 6-12" = 2.6 ppm).
- RO-318+20-N80 (has a 0-6" result of 0.047 ppm).
- RP-336+70-S60 (located upland of a nearby sample location RP-336+70-S40 6-12" = 1.2 ppm).

Locations where characterization does not support excavation depth

- P101/2PL: The excavation depth of P101 was established by RP-332+70-S10 6-12" = 1.2 ppm, located in the center of the removal zone, in 2PL. TRC proposes that an additional sample is not necessary.
- P202/3PR: The excavation depth of P202 was established by RP-335+00-N20 6-12" = 0.083 ppm, located in 3PR near the bank, and less than 40 feet away from the cited 0-6" samples. TRC proposes that additional sampling is not necessary.

If you have any questions, please contact me at 312-578-0870, ext. 8486.

Chris

From: Baumann, James S - DNR [mailto:James.Baumann@Wisconsin.gov]
 Sent: Tuesday, October 18, 2011 1:48 PM
 To: Harvey, Christopher (Chicago,IL-US)
 Cc: Wildeman, Anna J (20109); Greensley.Jean@epamail.epa.gov; Johnson, Deborah D - DNR; Rasmussen, Russell A - DNR
 Subject: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Chris,

In accordance with the proposed schedule, attached is a draft list of data gaps for HARP OU-3 Reaches N, O and P. After carefully reviewing the information you provided last week, Jean and I grouped the data gaps by category so that the reason for the gap listing is easier to understand. We did not include polygons not sampled that are some distance from the stream.

If you have questions, I'm sure that we can discuss them Thursday during the conference call you've scheduled.

Jim Baumann
Special Assistant, Bureau of Watershed Management
Wisconsin Department of Natural Resources
P. O. Box 7921
Madison, WI 53707
608/266-9277
james.baumann@wisconsin.gov

was provided by you. There are some items on the list that need further clarification which we have listed below. We have also identified items in the list that we believe are already adequately characterized and do not represent data gaps.

We plan to begin sampling in Reaches N, O and P in the near future to address the data gaps and submit the sample results to you by November 20, 2011. We would appreciate your comments by Tuesday, October 25th.

Polygons not sampled

- 9NL: The results cited for the similar polygon (1NL) are actually in 1NR. All of the results in 1NL are less than 5ppm. Polygon 9NL is more similar to 1NL than 1NR, since 9NL and 1NL are both upland of an outer meander, while 1NR is part of an inner meander. TRC proposes that 9NL does not represent a significant concern and does not need to be sampled.
- 11NR: There are six sample locations between the creek and 11NR that are <5 ppm (RN 517R, RN504R, RN 510R, RN-313+00-E100, RN-311+60-E40, RN-311+60-E80), which makes it unlikely that there are significant PCB concentrations in 11NR. TRC proposes that 11NR does not represent a significant concern and does not need to be sampled.
- 4OL: 4OL already has three locations that were sampled at a depth of >12 inches. TRC proposes that 4OL does not require additional sampling.

Locations where the stream moved laterally with likely deposition on an unsampled inner meander

- 323+00-W10: Please clarify. The station ID description places the sample at the inner meander at the downstream end of 2OL (not 5OL as indicated).
- 325+00-E10: Please clarify. The station ID description places the sample at the inner meander at the downstream end of 5OR (not 5OL as indicated).

Under-sampled locations

- 8NR downstream (two): Needs clarification. The two proposed samples seem to be at the same location, described in two different ways.
- 5NL: Need clarification on where it is under-sampled. Do you mean the downstream/upland boundary of N103, at approximately 13 feet west of RN-309+40-S40?
- 1PR: The downstream end of 1PR is not under-sampled. A sample has already been collected 15' feet away from the downstream end (RP 501R 0-6"=1.49 ppm). TRC proposes that an additional sample is not necessary.

Selected locations where only the 0-6" depth was analyzed

- Sampling in Reaches N through P has identified areas where a PCB-impacted layer greater than 5 ppm is covered by a layer with lesser impacts. However, they are typically near the creek (most are within 15 feet) or near irregular terrain such as a tributary, and the 0-6" layer has a result that is close to 5 ppm (not less than 1 ppm).
- Some of the proposed data gap locations have 0-6" layer results that are less than 1 ppm and are located far from the creek in a typical setting, or have some other surrounding context that makes it unreasonable to consider such areas as data gaps. As

such, TRC proposes that the following locations are adequately characterized and do not require additional vertical sampling:

- RN-305+90-S40 (located over 40 feet away from the creek on an outer meander; and is upland of a nearby sample location RN-305+90-S10 6-12" = 0.89 ppm).
- RN-311+00-W100 (located over 50 feet away from the creek; and there are no surrounding impacts)
- RN-311+60-W40 (has a 0-6" result of 0.28 ppm; and is upland of a nearby sample location RN 005L 6-12" = 2.0 ppm)
- RO-319+60-N30 (has a 0-6" result of 0.15 ppm; and is over one foot higher in elevation than a nearby sample RO-319+60-N10 6-12" = 2.6 ppm.)
- RO-327+00-N30 (has a 0-6" result of 0.12 ppm, the overbank is relatively steep at that location, and there are no surrounding impacts).
- RO-319+60-S150 (located over 70 feet away from the creek on an outer meander)
- RO-324+00-S60 (located upland of a nearby sample location RO-324+00-S40 6-12" = 0.083 ppm).
- RO-330+20-S50 (has a 0-6" result of 0.074 ppm; is over 50 feet away from the creek, and is upland of a nearby sample RO-330+20-S15 6-12" = 1.7 ppm).
- RO-328+70-N50 (has a 0-6" result of 0.092 ppm, and the overbank is relatively steep at that location)
- RO-319+60-N50 (has a 0-6" result of 0.044 ppm, and is approximately two feet higher in elevation than nearby sample location RO-319+60-N10 6-12" = 2.6 ppm).
- RO-319+60-N70 (has a 0-6" result of <0.033 ppm, and is approximately two feet higher in elevation than nearby sample location RO-319+60-N10 6-12" = 2.6 ppm).
- RO-318+20-N80 (has a 0-6" result of 0.047 ppm).
- RP-336+70-S60 (located upland of a nearby sample location RP-336+70-S40 6-12" = 1.2 ppm).

Locations where characterization does not support excavation depth

- P101/2PL: The excavation depth of P101 was established by RP-332+70-S10 6-12" = 1.2 ppm, located in the center of the removal zone, in 2PL. TRC proposes that an additional sample is not necessary.
- P202/3PR: The excavation depth of P202 was established by RP-335+00-N20 6-12" = 0.083 ppm, located in 3PR near the bank, and less than 40 feet away from the cited 0-6" samples. TRC proposes that additional sampling is not necessary.

If you have any questions, please contact me at 312-578-0870, ext. 8486.

Chris

From: Baumann, James S - DNR [mailto:James.Baumann@Wisconsin.gov]

Sent: Tuesday, October 18, 2011 1:48 PM

To: Harvey, Christopher (Chicago,IL-US)

Cc: Wildeman, Anna J (20109); Greensley,Jean@epamail.epa.gov; Johnson, Deborah D - DNR;

Rasmussen, Russell A - DNR

Subject: Draft List of Data Gaps -- HARP OU-3 Reaches N, O and P

Chris,

In accordance with the proposed schedule, attached is a draft list of data gaps for HARP OU-3 Reaches N, O and P. After carefully reviewing the information you provided last week, Jean and I grouped the data gaps by category so that the reason for the gap listing is easier to understand. We did not include polygons not sampled that are some distance from the stream.

If you have questions, I'm sure that we can discuss them Thursday during the conference call you've scheduled.

Jim Baumann

Special Assistant, Bureau of Watershed Management


Wisconsin Department of Natural Resources


P. O. Box 7921

Madison, WI 53707

608/266-9277

james.baumann@wisconsin.gov







230 West Monroe Street
Suite 2370
Chicago, IL 60606

312.578.0870 PHONE
312.578.0877 FAX

www.TRCSolutions.com

July 20, 2011

Mr. Jim Baumann
Special Assistant to Bureau Director
Bureau of Watershed Management
Wisconsin Department of Natural Resources
101 S. Webster Street, Box 7921
Madison, WI 53707-7921

Ms. Jean Greensley
U.S. Environmental Protection Agency
Remediation and Reuse Branch
Land and Chemicals Division
77 W. Jackson Boulevard
Chicago, IL 60604-3511

**Re: Proposed Overbank Removal Boundaries and PRV Sample Locations
Operable Unit 3, Reach L
Hayton Area Remediation Project**

Dear Mr. Baumann and Ms. Greensley:

Enclosed for your approval are figures and tables showing revised overbank removal boundaries in Reach L of the Hayton Area Remediation Project, Operable Unit 3 (OU3). Electronic copies of this submittal are also being provided via email to James.Baumann@Wisconsin.gov and Greensley.Jean@epamail.epa.gov.

Figure 1 shows sample results and revised removal boundaries of Reach L. Table 1 lists the characterization samples that were collected and analyzed in 2011. Table 2 provides the rationale for the boundaries of each removal zone of Reach L.

Also enclosed for your approval is a list of proposed post-removal verification (PRV) samples in Reach L. The PRV samples are listed on Table 3, and their locations are shown on Figure 2.

The stream bank PRV locations were selected using the following guidelines:

- Correspond to geomorphic features, such as an individual inside meander or outside meander;
- Along straight sections of the stream, PRV samples are placed on each side of the stream at a frequency of at least one per 200 feet;
- PRV samples are not required at locations where the adjacent overbank removal depth is 18" or greater because the stream bank has been removed at a depth of at least 18"; and

Mr. J. Baumann and Ms. J. Greensley
July 20, 2011
Page 2 of 2

- PRV samples are not required where characterization of the bank is adequate to justify no removal.

Table 4 indicates the segment of stream bank (by Station ID) that is represented by each stream bank PRV sample. Table 4 also specifies the removal zones located adjacent to the stream with overbank removal depths of 18 inches or greater.

For your reference, I have also enclosed a copy of the Reach L historic sample results presented in the 2006 *Lower OU2 & OU3 Technical Memorandum*.

We would appreciate your comments and approval for Reach L by August 5, 2011.

Please contact me at (312) 578-0870, extension 8486, with any questions.


Sincerely,

A handwritten signature in black ink, appearing to read "CH", with a long horizontal stroke extending to the right.

Christopher D. Harvey, PE
Program Manager

Enclosures: *Figure 1 - Sample Results and Excavation Boundaries, Reach L*
Figure 2 - Proposed Post-Removal Verification Samples, Reach L
Table 1- Characterization Sampling Results 2011, Reach L
Table 2 - Rationale for Removal Boundaries, Reach L
Table 3 - Proposed Post-Removal Verification Samples, Reach L
Table 4 - Proposed Stream Bank PRV Samples, Reach L
Figure - Reach L (from Lower OU2 & OU3 Technical Memorandum, 2006)





| | | | | | | | | | |
|---------------------|--|----------------------|---|-----|------|---------|--|--|--|
| FIGURE NO. 2 | DATE JULY 18, 2011 | SCALE: 1" = 100' | PROPOSED POST-REMOVAL VERIFICATION SAMPLES REACH L  230 WEST MONROE STREET, SUITE 2370 CHICAGO, IL 60606 PHONE: (312) 578-0870 FAX: (312) 578-0877 | NO. | DATE | COMMENT | | | |
| | DESIGN BY: SPA | DRAWN BY: | | | | | | | |
| | SHEET NO. 2 of 2 | JOB NUMBER 107927 | | | | | | | |
| | SHEET IS: REACH PLAN PRESENTATION (7-18-2011).DWG | | | | | | | | |
| | HAYTON AREA REMEDIATION PROJECT CALUMET COUNTY, WISCONSIN | | | | | | | | |
| | | | | | | | | | |

Table 1. Characterization Sampling Results 2011
Reach L
Hayton Area Remediation Project

07/20/2011

| Sample Name | Total PCBs (mg/kg) |
|-----------------|-----------------------|
| RL 001L 0-6" | 1.5 |
| RL 002L 0-6" | 0.446 |
| RL 003L 0-6" | 4.03 |
| RL 004L 0-6" | 2.53 |
| RL 005L 0-6" | 1.64 |
| RL 005L 6-12" | 2.66 |
| DUP 86 | 1.65 |
| RL 006L 0-6" | 2.04 |
| RL 006L 6-12" | 3.53 |
| RL 007L 18-24" | 0.09 |
| DUP 93 | 0.0871 |
| RL 008L 0-6" | 0.613 |
| RL 009L 0-6" | 5.05 |
| RL 010L 0-6" | 0.662 |
| RL 011L 0-6 | 0.933 |
| RL 012L RE 0-6 | 0.729 |
| RL 013L RE 0-6 | 1.96 |
| RL 013L RE 6-12 | 3.7 |
| RL 500R 0-6" | 5.1 |
| RL 500R 6-12" | 1.64 |
| RL 501R 0-6" | 2.99 |
| RL 501R 6-12" | 1.09 |
| RL 502R 0-6" | 0.196 |
| RL 502R 6-12" | 0.0736 |
| RL 503R 0-6" | 10.4 |
| RL 504R 0-6" | 3.83 |
| RL 505R 0-6" | 2.8 |
| RL 506R 0-6" | 3.43 |
| RL 507R 0-6 | 0.366 |
| RL 507R RE 6-12 | 0.17 |

| Sample Name | Total PCBs (mg/kg) |
|--------------|-----------------------|
| RL 508R 0-6 | 15.2 |
| RL 508R 6-12 | 1.78 |
| RL 509R 0-6 | 3.21 |
| RL 510R 0-6 | 6.74 |

Table 2. Rationale for Removal Boundaries
Reach L
Hayton Area Remediation Project

07/20/2011

| Removal Zone ID | Rationale |
|-----------------|---|
| L101 | <ul style="list-style-type: none"> Upstream boundary is established by sample RL 001L 0-6" = 1.5 mg/kg. Upland boundary is established by sample RL-268+70-W30 0-6" = 1.2 mg/kg. Downstream boundary is established by sample RL 002L 0-6" = 0.446 mg/kg. Floor is established by sample RL-268+70-W10 6-12" = 0.071 mg/kg. |
| L102 | <ul style="list-style-type: none"> Upstream boundary is established by sample RL 003L 0-6" = 4.03 mg/kg. Upland boundary is established by the polygon line between 3LLc and 3LLa, with reference to sample RL-270+00-W10 0-6" = 3.6 mg/kg. Downstream boundary is established by sample RL 004L 0-6" = 2.53 mg/kg. Floor is established by sample RL-272+00-W10 6-12" = 0.72 mg/kg. |
| L103 | <ul style="list-style-type: none"> Upstream boundary is established by samples RL 013L 0-6" RE = 1.96 mg/kg; and RL 013L 6-12" RE = 3.7 mg/kg. Upland boundary is established by the polygon line between 7LL and 8LL, with reference to sample RL-277+70-W40 0-6" = 3.2 mg/kg. Downstream boundary is established by samples RL 005L 0-6" = 1.64 mg/kg; and RL 005L 6-12" = 2.66 mg/kg. Floor is established by sample RL-277+70-W10 12-24" = 3.1 mg/kg. |
| L104 | <ul style="list-style-type: none"> Upstream boundary is established by sample RL 006L 0-6" = 2.04 mg/kg. Upland boundary is established by sample RL 008L 0-6" = 0.613 mg/kg; and the polygon line between 10LL and 11LL, with reference to samples RL-280+10-W30 0-6" = 2.8 mg/kg; and RL-281+80-S40 0-6" = 1.9 mg/kg. Downstream boundary is established by sample RL 008L 0-6" = 0.613 mg/kg. Boundary with L105 is established by the polygon line between 9LL and 10LL, with reference to sample RL-280+10-W15 6-12" = 1.2 mg/kg. Boundary with L106 is established by the polygon line between 13LL and 12LL, with reference to sample RL-281+80-S15 6-12" = 1.4 mg/kg. Floor is established by samples RL-280+10-W15 6-12" = 1.2 mg/kg; and RL-281+80-S15 6-12" = 1.4 mg/kg. |
| L105 | <ul style="list-style-type: none"> Upstream boundary is established by sample RL 006L 0-6" = 2.04 mg/kg; and RL 006L 6-12" = 3.53 mg/kg. Upland boundary is established by the polygon line between 9LL and 10LL, with reference to sample RL-280+10-W15 6-12" = 1.2 mg/kg. Downstream boundary is established by the polygon line between 9LL and 12LL, with reference to sample RL-280+10-W5 12-18" = 1.9 mg/kg. Floor is established by the sample RL-280+10-W5 12-18" = 1.9 mg/kg. |
| L106 | <ul style="list-style-type: none"> Upstream boundary is established by the polygon line between 9LL and 12LL, with reference to sample RL-280+10-W5 12-18" = 1.9 mg/kg; and by the polygon line between 10LL and 12LL, with reference to sample RL-280+10-W15 6-12" = 1.2 mg/kg. Upland boundary is established by the polygon line between 13LL and 12LL, with reference to sample RL-281+80-S15 6-12" = 1.4 mg/kg. Downstream boundary is established by sample RL 008L 0-6" = 0.613 mg/kg. Floor is established by sample RL 007L 18-24" = 0.09 mg/kg. |
| L107 | <ul style="list-style-type: none"> Upstream boundary is established by sample RL 011L 0-6" = 0.933 mg/kg. Upland boundary is established by sample RL 012L 0-6" RE = 0.729 mg/kg. Downstream boundary is established by sample RL 010L 0-6" = 0.662 mg/kg. Floor is established by sample RL-282+50-S10 6-12" = 0.12 mg/kg. |

Table 2. Rationale for Removal Boundaries
Reach L
Hayton Area Remediation Project

07/20/2011

| Removal Zone ID | Rationale |
|--------------------|--|
| L201a | <ul style="list-style-type: none"> • Upstream removal continues as removal zone K205 0-6". • Upland boundary is established by the polygon line between 12KR and 10KR, with reference to sample RK-265+00-E50 0-6" = 1.0 mg/kg. • Downstream boundary is established by sample RL 508R 6-12" = 1.78 mg/kg. • Floor is established by sample RL 508R 6-12" = 1.78 mg/kg. |
| L201 | <ul style="list-style-type: none"> • Upstream boundary is established by sample RL 508R 6-12" = 1.78 mg/kg. • Upland boundary is established by the polygon line between 1LR and 2LRa, with reference to samples RL-267+40-E30 0-6" = 0.069 mg/kg and RL-268+70-E60 0-6" = 1.5 mg/kg; the polygon line between 1LR and 2LRb, with reference to RL-268+70-E30 6-12" = 0.67 mg/kg. • Downstream boundary is established by sample RL 500R 6-12" = 1.64 mg/kg. • Floor is established by samples RL-267+40-E10 12-18" = 0.28 mg/kg; and RL-268+70-E10 12-27" = 1.8 mg/kg. |
| L201b | <ul style="list-style-type: none"> • Upstream boundary established by sample RL 500R 6-12" = 1.64 mg/kg. • Upland boundary is established by the polygon line between 1LR and 2LRa, with reference to sample RL-268+70-E60 0-6" = 1.5 mg/kg. • Downstream boundary is established by sample RL 504R 0-6" = 3.83 mg/kg. • Floor is established by sample RL 500R 6-12" = 1.64 mg/kg. |
| L202 | <ul style="list-style-type: none"> • Upstream boundary is established by the polygon line between 2LRa and 2LRb, with reference to sample RL-267+40-E30 0-6" = 0.069 mg/kg. • Upland and downstream boundaries are established by the polygon line between 2LRa and 2LRb, with reference to sample RL-268+70-E60 0-6" = 1.5 mg/kg. • Boundary with L201 is established by the polygon line between 1LR and 2LRb, with reference to sample RL-268+70-E30 6-12" = 0.67 mg/kg. • Floor is established by sample RL-268+70-E30 6-12" = 0.67 mg/kg. |
| L203 | <ul style="list-style-type: none"> • Upstream boundary is established by samples RL 501R 0-6" = 2.99 mg/kg; and RL 501R 6-12" = 1.09 mg/kg. • Upland boundary is established by samples RL 507R 0-6" = 3.66 mg/kg; and RL 507R 6-12" RE = 0.170 mg/kg. • Downstream boundary is established by samples RL 502 0-6" = 0.196 mg/kg; and RL 502R 6-12" = 0.0736 mg/kg. • Floor is established by sample RL-275+80-E10 12-30" = <0.036 mg/kg. |
| L204 | <ul style="list-style-type: none"> • Upstream boundary is established by RL 509R 0-6" = 3.21 mg/kg. • Upland boundary is established by sample RL 506R 0-6" = 3.43 mg/kg. • Downstream boundary is established by sample RL 505R 0-6" = 2.8 mg/kg. • Floor is established by sample 13LR-PRE-6-12" = <0.1 mg/kg. |

**Table 3. Proposed Post-Removal Verification Samples
Reach L
Hayton Area Remediation Project**

07/20/2011


| Sample ID | In-channel¹ or Overbank | Type | Northing | Easting |
|---------------------|---|-------------|-----------------|----------------|
| RL IC PRVF 900C | In-channel | Floor | 733693 | 2469474 |
| RL IC PRVF 901C | In-channel | Floor | 733878 | 2469386 |
| RL IC PRVF 902C | In-channel | Floor | 734124 | 2469360 |
| RL IC PRVF 903C | In-channel | Floor | 734320 | 2469277 |
| RL IC PRVF 904C | In-channel | Floor | 734570 | 2469263 |
| RL IC PRVF 905C | In-channel | Floor | 734701 | 2469038 |
| RL BK PRVW 001L | Stream bank | Sidewall | 733741 | 2469462 |
| RL BK PRVW 002L | Stream bank | Sidewall | 733757 | 2469360 |
| RL BK PRVW 003L | Stream bank | Sidewall | 733886 | 2469385 |
| RL BK PRVW 004L | Stream bank | Sidewall | 733956 | 2469449 |
| RL BK PRVW 005L | Stream bank | Sidewall | 734116 | 2469363 |
| RL BK PRVW 006L | Stream bank | Sidewall | 734240 | 2469212 |
| RL BK PRVW 007L | Stream bank | Sidewall | 734427 | 2469337 |
| RL BK PRVW 008L | Stream bank | Sidewall | 734571 | 2469247 |
| RL BK PRVW 009L | Stream bank | Sidewall | 734693 | 2469165 |
| RL BK PRVW 010L | Stream bank | Sidewall | 734654 | 2468974 |
| RL BK PRVW 500R | Stream bank | Sidewall | 733752 | 2469470 |
| RL BK PRVW 501R | Stream bank | Sidewall | 733767 | 2469370 |
| RL BK PRVW 502R | Stream bank | Sidewall | 733879 | 2469394 |
| RL BK PRVW 503R | Stream bank | Sidewall | 733956 | 2469459 |
| RL BK PRVW 504R | Stream bank | Sidewall | 734127 | 2469367 |
| RL BK PRVW 505R | Stream bank | Sidewall | 734238 | 2469229 |
| RL BK PRVW 506R | Stream bank | Sidewall | 734436 | 2469349 |
| RL BK PRVW 507R | Stream bank | Sidewall | 734580 | 2469274 |
| RL BK PRVW 508R | Stream bank | Sidewall | 734706 | 2469166 |
| RL BK PRVW 509R | Stream bank | Sidewall | 734681 | 2468977 |
| RL PRVF 511R 12-18" | Overbank | Floor | 733781 | 2469372 |
| RL PRVF 512R 12-18" | Overbank | Floor | 734320 | 2469303 |
| RL PRVF 014L 12-18" | Overbank | Floor | 734439 | 2469321 |
| RL PRVF 015L 6-12" | Overbank | Floor | 734677 | 2469164 |
| RL PRVF 016L 18-24" | Overbank | Floor | 734704 | 2469086 |
| RL PRVF 017L 0-6" | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 017L 6-12" | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 017L 12-18" | Overbank | Sidewall | 734680 | 2469057 |
| RL PRVF 513R 6-12" | Overbank | Floor | 734709 | 2468931 |

¹ The locations of in-channel samples may be adjusted, or additional in-channel samples may be added, based on visual cues observed during removal.

**Table 4. Proposed Stream Bank PRV Samples - Reach L
Hayton Area Remediation Project**

07/20/2011

| PRV Sample Name or Removal Zone | Length of Streambank Represented | | Description |
|------------------------------------|-------------------------------------|-----------------------|--|
| | Upstream Station | Downstream Station | |
| Right Bank | | | |
| RL BK PRVW 500R | 266+00 | 268+00 | Outer meander along L201a and L201 |
| RL BK PRVW 501R | 268+00 | 269+45 | Inner meander along L201 and L201b |
| RL BK PRVW 502R | 269+45 | 270+50 | Straight section downstream of L201b |
| RL BK PRVW 503R | 270+50 | 272+00 | Outer meander |
| RL BK PRVW 504R | 272+00 | 273+75 | Outer meander |
| RL BK PRVW 505R | 273+75 | 276+00 | Inner meander |
| RL BK PRVW 506R | 276+00 | 278+00 | Outer meander opposite of L103 |
| RL BK PRVW 507R | 278+00 | 279+80 | Straight section |
| RL BK PRVW 508R | 279+80 | 282+00 | Outer meander opposite of L105 and L106 |
| RL BK PRVW 509R | 282+00 | 284+00 | Inner meander along L204 |
| Left Bank | | | |
| RL BK PRVW 001L | 266+00 | 268+00 | Inner meander opposite of L201a and L201 |
| RL BK PRVW 002L | 268+00 | 269+65 | Outer meander along L101 |
| RL BK PRVW 003L | 269+65 | 270+50 | Straight section |
| RL BK PRVW 004L | 270+50 | 272+00 | Inner meander |
| RL BK PRVW 005L | 272+00 | 273+75 | Inner meander |
| RL BK PRVW 006L | 273+75 | 276+00 | Outer meander |
| RL BK PRVW 007L | 276+00 | 278+00 | Inner meander along L103 |
| RL BK PRVW 008L | 278+00 | 279+80 | Straight section upstream of L105 |
| RL BK PRVW 009L | 279+80 | 281+10 | Inner meander along L105 |
| L106 | 281+10 | 282+10 | 18" removal |
| RL BK PRVW 010L | 282+10 | 284+00 | Outer meander along L107 |





**Proposed Overbank Removal Boundaries
and Sample Results
Operable Unit 3
Reaches N, O and P**

Hayton Area Remediation Project
November 2011

Prepared by:



Chicago, Illinois



230 West Monroe Street
Suite 2370
Chicago, IL 60606

312.578.0870 PHONE
312.578.0877 FAX

www.TRCSolutions.com

rec'd
7/21/11
CAS #1

November 18, 2011

Mr. Jim Baumann
Special Assistant to Bureau Director
Bureau of Watershed Management
Wisconsin Department of Natural Resources
101 S. Webster Street, Box 7921
Madison, WI 53707-7921

Ms. Jean Greensley
U.S. Environmental Protection Agency
Remediation and Reuse Branch
Land and Chemicals Division
77 W. Jackson Boulevard
Chicago, IL 60604-3511

**Re: Characterization Sample Results
Operable Unit 3, Reaches N, O and P
Hayton Area Remediation Project**

Dear Mr. Baumann and Ms. Greensley:

On October 18, 2011, WDNR and EPA provided TRC with a draft list of data gaps in HARP Operable Unit 3 Reaches N, O and P. TRC reviewed the list with WDNR and EPA and an updated draft list of data gaps was provided to TRC on October 27, 2011. WDNR proposed that TRC should submit sample data results for any samples identified in the draft list of data gaps by November 20, 2011,

Enclosed for your review are figures and tables that include all recent sample results in Reaches N, O and P. Recent results are shown in magenta on Figures 1 through 3. Electronic copies of this submittal are also being provided via email to James.Baumann@Wisconsin.gov and Greensley.Jean@epamail.epa.gov.

At this time, TRC is unable to provide results for each identified sample location, due to delays caused by site conditions. TRC has collected almost all of the identified samples, and expects to receive additional results shortly.

Based on the enclosed sample results, TRC has created new removal zones in Reaches N, O and P. The preliminary removal boundaries are shown in magenta on Figures 1 through 3. TRC plans to collect additional samples to further characterize areas with results greater than 5 ppm total PCBs.

Please contact me at (312) 578-0870, extension 8486, with any questions.

Sincerely,




Christopher D. Harvey, PE
Program Manager

Enclosures: *Figure 1 - Sample Results and Excavation Boundaries, Reach N*
Figure 2 - Sample Results and Excavation Boundaries, Reach O
Figure 3 - Sample Results and Excavation Boundaries, Reach P
Table 1 - Reach N Characterization Sample Results
Table 2 - Reach O Characterization Sample Results
Table 3 - Reach P Characterization Sample Results

Table 1. Additional Characterization Sampling Results

Reach N
Hayton Area Remediation Project

11/18/2011

| Sample Name | Total PCBs (mg/kg) | Data Gap ¹ and Location | Comments |
|---------------|-----------------------|------------------------------------|----------------------------|
| RN 012L 6-12 | 0.237 | [5] 5NL/N103 | Organic silt. |
| RN 013L 12-18 | 0.277 | [5] 5NL/N103 | Organic silt. |
| RN 014L 6-12 | 0.296 | [5] 10NL/N107 | Organic silt. |
| RN 015L 12-18 | 0.052 (J) | [5] 12NL | Organic silt. |
| RN 024L 12-18 | <0.0382 | [5] 21ML | Organic silt. |
| RN 023L 12-18 | 1.04 | [5] 18ML | Organic silt. |
| RN 025L 18-24 | 0.851 | [5] 18ML | Organic silt. |
| RN 026L 0-6 | 3.87 | [3] N110 | Organic silt. |
| DUP 137 | 3.55 | [3] N110 | Organic silt. |
| RN 027L 6-12 | 5.51 | [3] N110 | Organic silt. |
| RN 028L 0-6 | 5.31 | [1] 6NL | Organic silt. |
| RN 028L 6-12 | 1.08 | [1] 6NL | Organic silt. |
| RN 029L 0-6 | 2.24 | [1] 13NL | Organic silt. |
| RN 029L 6-12 | 3.34 | [1] 13NL | Organic silt. |
| RN 029L 12-18 | CLAY | [1] 13NL | Clay. No sample collected. |
| RN 030L 0-6 | 4.49 | [2] 314+90-W10 (10NL) | Organic silt. |
| RN 030L 6-12 | 8.23 | [2] 314+90-W10 (10NL) | Organic silt. |
| RN 031L 0-6 | 1.55 | [3] 7NL upstream | Organic silt. |
| RN 031L 6-12 | 0.317 | [3] 7NL upstream | Organic silt. |
| RN 032L 0-6 | 3.1 | [3] 7NL downstream | Organic silt. |
| RN 032L 6-12 | 0.393 | [3] 7NL downstream | Organic silt. |
| RN 033L 0-6 | 2.31 | [3] 10NL upstream | Organic silt. |
| RN 033L 6-12 | 2.41 | [3] 10NL upstream | Organic silt. |
| RN 034L 0-6 | 1.16 | [3] 10NL upstream | Organic silt. |
| RN 034L 6-12 | 5.54 | [3] 10NL upstream | Organic silt. |
| RN 035L 6-12 | 4.4 | [4] RN-305+90-S40 (1NL) | Organic silt. |
| RN 036L 6-12 | 2.5 | [4] RN-311+60-W40 (8NL) | Organic silt. |
| RN 037L 6-12 | 3.3 | [4] RN-315+50-W40 (N107) | Organic silt. |
| RN 512R 6-12 | 1.04 | [5] 20R/N206 | Organic silt. |
| DUP 140 | 1.24 | [5] 20R/N206 | Organic silt. |
| RN 521R 0-6 | <0.0317 | [1], [3] 11NR | Organic silt. |
| RN 521R 6-12 | <0.0325 | [1], [3] 11NR | Organic silt. |
| RN 522R 0-6 | 2.85 | [2] 310+80-E10 (5NR) | Organic silt. |
| RN 522R 6-12 | 6.52 | [2] 310+80-E10 (5NR) | Organic silt. |
| RN 523R 0-6 | 4.56 | [2], [3] 313+00-E10 (8NR) | Organic silt. |
| RN 523R 6-12 | 7.17 | [2], [3] 313+00-E10 (8NR) | Organic silt. |
| RN 525R 6-12 | 0.0829 (J) | [4] RN-305+90-N90 (2NR) | Organic silt. |
| DUP 138 | 0.0986 (J) | [4] RN-305+90-N90 (2NR) | Organic silt. |
| RN 526R 6-12 | 0.364 | [4] RN-309+40-N10 (5NR) | Organic silt. |
| RN 527R 6-12 | 0.4 | [4] RN-313+00-E100 (10NR) | Organic silt. |
| RN 528R 6-12 | 1.38 | [4] RN-315+50-E10 (N205) | Organic silt. |

(J) = Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

¹ Data Gap Types:

- [1] Polygons not sampled
- [2] Locations where the stream has moved laterally and deposition of PCBs on the inside of the meander is likely and where not previously sampled
- [3] Selected locations that are under-sampled
- [4] Selected locations where only the 0 to 6 inch depth was analyzed
- [5] Polygon/Sections where characterization does not support excavation depth

Table 2. Additional Characterization Sampling Results

Reach O
Hayton Area Remediation Project

11/18/2011

| Sample Name | Total PCBs (mg/kg) | Data Gap ¹ and Location | Comments |
|---------------|-----------------------|------------------------------------|---|
| RO 008L 0-6 | 4.56 | [1] 3OL | Organic silt. |
| RO 008L 6-12 | 0.773 | [1] 3OL | Organic silt. |
| RO 010L 0-6 | 2.23 | [1] 5OL | Organic silt. |
| RO 010L 6-12 | 5.18 | [1] 5OL | Organic silt., some shells |
| RO 012L 0-6 | 1.39 | [1] 10OL | Organic silt. |
| RO 012L 6-12 | 1.33 | [1] 10OL | Organic silt. |
| RO 013L 0-6 | 5.88 | [2] 323+00-W10 (2OL) | Organic silt. |
| RO 013L 6-12 | 11.5 | [2] 323+00-W10 (2OL) | Organic silt. |
| RO 014L 0-6 | 1.96 | [2] 324+70-W10 (7OL) | Organic silt. |
| RO 014L 6-12 | 11.3 | [2] 324+70-W10 (7OL) | Organic silt. |
| RO 015L 0-6 | 0.972 | [2], [3] 325+70-W10 (7OL) | Between the top of the bank and the depression. Organic silt. |
| RO 015L 6-12 | 2.19 | [2], [3] 325+70-W10 (7OL) | |
| RO 016L 0-6 | 1.81 | [3] 7OLa | In the depression. Organic silt. |
| RO 016L 6-12 | 3.85 | [3] 7OLa | |
| RO 017L 6-12 | <0.0385 | [4] RO-328+00-S100 (11OLa) | Organic silt. |
| DUP 139 | 0.0464 (J) | [4] RO-328+00-S100 (11OLa) | Organic silt. |
| RO 018L 6-12 | 0.0439 (J) | [4] RO -319+60-S150 (1OLb) | Organic silt. |
| RO 507R 12-18 | 0.314 | [5] 1OR/O202 | Organic silt. |
| RO 509R 0-6 | 7.28 | [2] 322+00-E10 (5OR) | Organic silt. |
| RO 509R 6-12 | 1.41 | [2] 322+00-E10 (5OR) | Organic silt. |
| RO 510R 0-6 | 1.16 | [2] 325+00-E10 (5OR) | Organic silt. |
| RO 510R 6-12 | 2.38 | [2] 325+00-E10 (5OR) | Organic silt. |
| RO 511R 0-6 | 2.65 | [3] 3OR | Organic silt., some shells. |
| RO 511R 6-12 | 3.29 | [3] 3OR | Organic silt., clay observed at 12". |
| RO 512R 0-6 | 1.85 | [3] 5OR | Organic silt. |
| RO 512R 6-12 | <0.0612 | [3] 5OR | Organic silt. |
| RO 513R 0-6 | 1.87 | [3] 11OR | Organic silt. |
| RO 513R 6-12 | 1.85 | [3] 11OR | Organic silt. |
| RO 515R 6-12 | <0.0302 | [4] RO-327+00-N30 (9OR/10OR) | Organic silt. |

(J) = Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

¹ Data Gap Types:


- [1] Polygons not sampled
- [2] Locations where the stream has moved laterally and deposition of PCBs on the inside of the meander is likely and where not previously sampled
- [3] Selected locations that are under-sampled
- [4] Selected locations where only the 0 to 6 inch depth was analyzed
- [5] Polygon/Sections where characterization does not support excavation depth

Table 3. Additional Characterization Sampling Results
Reach P
Hayton Area Remediation Project

11/18/2011

| Sample Name | Total PCBs (mg/kg) | Location | Comments |
|-------------|-----------------------|----------|---|
| RP 509R 0-6 | 3.21 | P202 | Immediately east of the tributary. Organic silt. |
| RP 510R 0-6 | 6.66 | P202 | Organic silt. |
| RP 511R 0-6 | 2.49 | P202 | Organic silt. |
| DUP 132 | 3.03 | P202 | Organic silt. |

(J) = Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.



- LEGEND**
- F2 CENTERLINE OF CREEK
 - O-10" SOFT SEDIMENT EXCAVATION AREA
 - AVERAGE SOFT SEDIMENT DEPTH INTERVAL, OF EXCAVATION
 - FLOOR SAMPLE LOCATION
 - ⊙ WALL SAMPLE LOCATION
 - ⊙ TSCA BOUNDARY SAMPLE
 - POLYGON BOUNDARY LINE
 - EXCAVATION BOUNDARY ALONG CREEK BANK
 - 5 PPM EXCAVATION BOUNDARY
 - SUBDIVIDER LINE FOR NON-TSCA EXCAVATION DEPTH INTERVALS
 - 50 PPM EXCAVATION BOUNDARY (TSCA)
 - SUBDIVIDER LINE FOR TSCA EXCAVATION DEPTH INTERVALS

NOTES:
1. COORDINATE SYSTEM IS NAD83, WISCONSIN STATE PLANE, SOUTH ZONE, US FT.

0 25 50 100
SCALE IN FEET

SAMPLE RESULTS AND EXCAVATION BOUNDARIES REACH O


HAYTON AREA REMEDIATION PROJECT

DRAWN BY: SPA DATE: 10/10/2011
PROJECT NO: 107827 DWG FILE: Sampling Presentation sheets



230 WEST MONROE STREET
SUITE 2370
CHICAGO, IL 60606
312-578-0870

FIGURE
2



LEGEND

F2
0-10"

CENTERLINE OF CREEK
SOFT SEDIMENT EXCAVATION
AREA
AVERAGE SOFT SEDIMENT
DEPTH INTERVAL OF EXCAVATION

FLOOR SAMPLE LOCATION
WALL SAMPLE LOCATION
TSCA BOUNDARY SAMPLE


POLYGON BOUNDARY LINE
EXCAVATION BOUNDARY ALONG
CREEK BANK

5 PPM EXCAVATION BOUNDARY
SUBDIVIDER LINE FOR
NON-TSCA EXCAVATION DEPTH
INTERVALS
50 PPM EXCAVATION BOUNDARY
(TSCA)
SUBDIVIDER LINE FOR TSCA
EXCAVATION DEPTH INTERVALS

NOTES:
1. COORDINATE SYSTEM IS NAD83, WISCONSIN STATE PLANE,
SOUTH ZONE, US FT.

0 25 50 100
SCALE IN FEET

| SAMPLE RESULTS AND EXCAVATION BOUNDARIES REACH P | | | |
|---|--------|-----------|------------------------------|
| HAYTON AREA REMEDIATION PROJECT | | | |
| DRAWN BY: | SPA | DATE: | 10/10/2011 |
| PROJECT NO: | 107927 | DWG FILE: | Sampling Presentation sheets |
| 230 WEST MONROE STREET SUITE 2370 CHICAGO, IL 60606 312-579-0870 | | | FIGURE 3 |



LEGEND

CENTERLINE OF CREEK
F2
0-10"

SOFT SEDIMENT EXCAVATION AREA
AVERAGE SOFT SEDIMENT DEPTH INTERVAL OF EXCAVATION

FLOOR SAMPLE LOCATION
WALL SAMPLE LOCATION
TSCA BOUNDARY SAMPLE

POLYGON BOUNDARY LINE
EXCAVATION BOUNDARY ALONG CREEK BANK
5 PPM EXCAVATION BOUNDARY
SUBDIVIDER LINE FOR NON-TSCA EXCAVATION DEPTH INTERVALS
50 PPM EXCAVATION BOUNDARY (TSCA)
SUBDIVIDER LINE FOR TSCA EXCAVATION DEPTH INTERVALS

NOTES:
1. COORDINATE SYSTEM IS NAD83, WISCONSIN STATE PLANE, SOUTH ZONE, US FT.

0 25 50 100
SCALE IN FEET

SAMPLE RESULTS AND EXCAVATION BOUNDARIES REACH N

HAYTON AREA REMEDIATION PROJECT


DRAWN BY: SPA DATE: 10/10/2011

PROJECT NO: 107927 DWG FILE: Sampling Presentation sheets

230 WEST MONROE STREET
SUITE 2370
CHICAGO, IL 60606
312-678-0870

FIGURE 1

735100 N



LEGEND

- F2 CENTERLINE OF CREEK
- 0-10" SOFT SEDIMENT EXCAVATION AREA
- AVERAGE SOFT SEDIMENT DEPTH INTERVAL OF EXCAVATION
- FLOOR SAMPLE LOCATION
- WALL SAMPLE LOCATION
- TSCA BOUNDARY SAMPLE
- POLYGON BOUNDARY LINE
- EXCAVATION BOUNDARY ALONG CREEK BANK
- 5 PPM EXCAVATION BOUNDARY
- SUBDIVIDER LINE FOR NON-TSCA EXCAVATION DEPTH INTERVALS
- 50 PPM EXCAVATION BOUNDARY (TSCA)
- SUBDIVIDER LINE FOR TSCA EXCAVATION DEPTH INTERVALS

NOTES:
1. COORDINATE SYSTEM IS NAD83, WISCONSIN STATE PLANE, SOUTH ZONE, US FT.

0 25 50 100
SCALE IN FEET

SAMPLE RESULTS AND EXCAVATION BOUNDARIES REACH N


HAYTON AREA REMEDIATION PROJECT


DRAWN BY: SPA DATE: 11/18/2011

PROJECT NO: 107927 DWG FILE: Sampling Presentation sheets

230 WEST MONROE STREET
SUITE 2370
CHICAGO, IL 60608
312-578-0870

FIGURE 1





SAMPLE RESULTS AND EXCAVATION BOUNDARIES
REACH P

HAYTON AREA REMEDIATION PROJECT

DRAWN BY: SPA

DATE: 11/18/2011

PROJECT NO: 107927

DWG FILE: Sampling Presentation sheets

TRC

230 WEST MONROE STREET
SUITE 2370
CHICAGO, IL 60606
312-578-0870

FIGURE
3